

University of Rajshahi

Rajshahi-6205

Bangladesh.

RUCL Institutional Repository

<http://rulrepository.ru.ac.bd>

---

Institute of Biological Sciences (IBSc)

PhD Thesis

---

2013

# Combined Effects of Predator, Xylocoris Flavipes (Reuter) and Bacterium, Spinosad for Control of Stored Product Insect Pests

Sarker, Atul Chandro


University of Rajshahi

---

<http://rulrepository.ru.ac.bd/handle/123456789/630>

*Copyright to the University of Rajshahi. All rights reserved. Downloaded from RUCL Institutional Repository.*

**COMBINED EFFECTS OF PREDATOR, *XYLOCORIS FLAVIPES*  
(REUTER) AND BACTERIUM, SPINOSAD FOR CONTROL  
OF STORED PRODUCT INSECT PESTS**



**THESIS SUBMITTED FOR THE DEGREE  
OF  
DOCTOR OF PHILOSOPHY  
IN THE  
INSTITUTE OF BIOLOGICAL SCIENCES  
RAJSHAHI UNIVERSITY, BANGLADESH**

**SUBMITTED  
by  
ATUL CHANDRO SARKER  
B Sc (Honours) M Sc in Zoology**

**June 2013**


**Entomology and Insect Biotechnology  
Laboratory  
Institute of Biological Sciences  
Rajshahi University, Bangladesh**

**DEDICATED**  
**TO**  
**MY PARENTS**  
**AND**  
**PARENTS-IN-LAW**

## **DECLARATION**

I hereby declare that the thesis entitled **Combined effects of predator, *Xylocoris flavipes* (Reuter) and bacterium, Spinosad for control of stored product insect pests** submitted in the Institute of Biological Sciences, University of Rajshahi, Bangladesh for the degree of **Doctor of Philosophy** is the result of my own investigation and was carried out under the supervisions of Professor Dr Md Wahedul Islam, Institute of Biological Sciences, University of Rajshahi and Professor Dr Selina Parween, Department of Zoology, University of Rajshahi, Bangladesh. This thesis has not been submitted elsewhere for any other degree or diploma.

**ATUL CHANDRO SARKER**  
(candidate)



## **CERTIFICATE**

This is to certify that the thesis entitled **Combined effects of predator, *Xylocoris flavipes* (Reuter) and bacterium, Spinosad for control of stored product insect pests** submitted by Atul Chandro Sarker for the degree of the **Doctor of Philosophy** is the record of bonafied research carried out at the Entomology and Insect Biotechnology laboratory, Institute of Biological Sciences, University of Rajshahi, Bangladesh under our supervisions. All the data presented in the thesis are based on his own observations and no portion thereof has previously been published or submitted for any other degree or diploma.

### **Supervisors**

**Dr Md Wahedul Islam**  
**Professor**  
**Institute of Biological Sciences**  
**Rajshahi University, Bangladesh**

**Dr Selina Parween**  
**Professor**  
**Department of Zoology**  
**Rajshahi University, Bangladesh**

# CONTENTS

|   | <b>Page No.</b> |
|---|-----------------|
| Acknowledgements  | i               |
| Abstract  | iii             |
| <b>Chapter 1 General Introduction</b>                                     | <b>1-28</b>     |
| Introduction: Insect pests of stored products and management scenario     | 1               |
| Test insects, their distribution and damage                               | 6               |
| Alternate insect control methods using at present                         | 10              |
| Environmental control   | 11              |
| Control by radiation control  | 13              |
| Chemical control  | 14              |
| Insecticides  | 14              |
| Fumigants   | 15              |
| Insect Growth Regulators (IGRs)   | 16              |
| Botanicals as control measure   | 17              |
| Biological control  | 18              |
| Parasitoids   | 21              |
| Predators   | 22              |
| Bacteria  | 24              |
| Discovery of Spinosad   | 25              |
| Application of Spinosad   | 25              |
| Background of the study   | 27              |
| Objectives of the research  | 28              |
| <b>Chapter 2 Review of Literature</b>                                     | <b>29-62</b>    |
| Effects of environmental factors on insects                               | 29              |
| Temperature and humidity  | 29              |
| Biology of <i>C. pusillus</i> , <i>R. dominica</i> and <i>X. flavipes</i> | 36              |
| Management techniques for <i>C. pusillus</i> and <i>R. dominica</i>       | 44              |
| Predatory abilities of <i>X. flavipes</i>                                 | 48              |
| An ideal bacterium  | 55              |
| Chemical description of Spinosad  | 55              |
| Efficacy of Spinosad  | 58              |

|   |                |
|---|----------------|
| <b>Chapter 3 General Methodology</b>  | <b>63-69</b>   |
| Selection of the test insects: pests and predator   | 63             |
| Selection of bacterium: Spinosad  | 64             |
| Food medium used  | 64             |
| Culture of <i>C. pusillus</i>   | 65             |
| Culture of <i>R. dominica</i>   | 66             |
| Culture of <i>X. flavipes</i>   | 67             |
| Source of Spinosad  | 68             |
| Preparation of Spinosad concentration   | 69             |
| Precautions   | 69             |
| Statistical analyses  | 69             |
| <br>  |                |
| <b>Chapter 4 Host stage specific effects on the biological parameters of <i>X. flavipes</i></b> | <b>70-90</b>   |
| Introduction  | 70             |
| Materials and Methods   | 71             |
| Results and Observation   | 72             |
| Discussion  | 87             |
| <br>  |                |
| <b>Chapter 5 Effects of Spinosad on <i>C. pusillus</i> and <i>R. dominica</i></b>               | <b>91-109</b>  |
| Introduction  | 90             |
| Materials and Methods   | 93             |
| Results and Observation   | 95             |
| Effects on egg hatchability   | 95             |
| Toxicity on larvae  | 97             |
| Toxicity on pupae   | 99             |
| Toxicity on adults  | 101            |
| Discussion  | 106            |
| <br>  |                |
| <b>Chapter 6 Effects of Spinosad on <i>X. flavipes</i></b>                                      | <b>110-121</b> |
| Introduction  | 110            |
| Materials and Methods   | 112            |
| Results and Observation   | 113            |

|  |                |
|--|----------------|
| Effects on egg hatchability  | 113            |
| Toxicity on nymphs   | 114            |
| Toxicity on adults   | 115            |
| Discussion   | 118            |
| <b>Chapter 7 Effects of <i>X. flavipes</i> and Spinosad on pest population after<br/>different storage periods</b> | <b>122-133</b> |
| Introduction   | 122            |
| Materials and Methods  | 123            |
| Results and Observation  | 125            |
| Discussion   | 131            |
| <b>Chapter 8 Summary and Conclusion</b>  | <b>134-143</b> |
| <b>References</b>  | <b>144-225</b> |
| <b>Appendices</b>  | <b>226-257</b> |



## **ACKNOWLEDGEMENTS**

I am gratefully indebted to my supervisors Professor Dr Md Wahedul Islam, Institute of Biological Sciences and Professor Dr Selina Parween, Department of Zoology, University of Rajshahi for their absolute guidance, encouraging discussion and fine outlook about the dissertation throughout the study period which make me efficient and inspired to complete the research work.

I would like to express my sincere gratitude to Professor Dr Tanzima Yeasmin, Present Director and Professor Dr M Khalequzzaman, Former Director, Institute of Biological Sciences, University of Rajshahi for PhD Fellowship and laboratory facilities.

I would like to convey my heartiest respect to Professor Dr KAMSH Mondal, Professor Dr MA Bari Miah, Professor Dr Parvez Hasan, Dr Shahinul Islam and Dr Ariful Haque, Assistant Professors, Institute of Biological Sciences and Professor Dr Bidhan Chandro Das Department of Zoology, University of Rajshahi for their help and encouragement.

I would like to convey my heartiest homage to Alhaz Mogibor Rahman MP Lalmonirhut-2 and Chairman of Parliamentary Committee, Religious Ministry of the People's Republic of Bangladesh for the good suggestions and untiring help where needed.

I acknowledge the Professor Chowdhury Dr Md Zakaria, Former Proctor, University of Rajshahi, Dr Khandker Nesar Ahmed, Chief Scientific Officer, BCSIR Laboratory, Dhaka, Dr Biredro Nath Saha, Department of Zoology, Rangpur Government College, Rangpur, Professor Dr Jahanul Islam, Department of Statistics, Md Asaduzzaman Badsa, Associate Professor, Department of Philosophy, University of Rajshahi for their helps.

With the best compliments I would like to express special thanks to Professor Shah Md. Moksed Ali, Principal, Professor Md. Khalilur Rahman, Head of Zoology Department, Associate Professor Md. Abdul Hai and all colleagues, Department of Zoology, Carmichael College, Rangpur, Professor Md Mofiq Ullah Sarker, Former Principal, Lalmonirhat Government College, Lalmonirhut; Principal, Technical High School and College, Saidpur, Nilphamari; Principal, Pirgang Government College, Takurgaon for full cooperation whenever needed.

I am grateful to The Directorate, Secondary and Higher Education Bangladesh, Dhaka, and Ministry of Education, People's Republic of Bangladesh for deputation during my study period, and University Grants Commission Bangladesh, Dhaka for M Phill fellowship, and TWAS, Italy for partial funding.

With deep faith I appreciate to acknowledge the contribution of all the scientists from where relevant literature have been collected and also grateful to Tracer, Indiana pole for kindly supplying spinosad.

I would like to convey my warm and cordial thanks to all my fellows friends of the lab specially Abul Hossain Mondal, Dr Shilpi Rani Saha, Dr Rehena Khatun, Dr Dipali Rani Saha, Md Abu Masud, Md Shah Nawoz Kader Jilani, Promoda Ranjan Sen, Shah Md Abdul Motin, Protap Chandra Roy, Mona-ashis Roy Chowdhury, Md Shajedul Karim, A K M Abdur Rahman, Md Rafiqul Islam, Md. Shariful Islam, Mohammad Harun-Or-Rashid, Md Rezaul Hoque, Md Hasanuzzaman Mst. Ummey kulsum for their spontaneous help and cooperation.

I am thankfull to Zohurul Islam Babu, Computer Land, Rajshahi University for composing the manuscript and also to Mr Rafiq Uddin Ahmed for Statistical Analyses.

With love and the best regards to my mother-in-law Gita Rani Devi, Maternal Sailendro kumer Roy, Senior brother Protap Chandro Sarker, Brother in law Ganes Chandro Roy Dakua, Prodip Roy, Narayon Chandro Ray, and Goutom Roy for their support. With love and the best wishes I devout affection to my beloved son Amorjit Sarker Arghay, Bosujit Sarker Ishan and daughter Kangkhita Sarker Nidhi. Last but not the least; I owe a deep debt of gratitude to my wife Monika Roy for her continuous moral support, patience, understanding and boldly management of family during research work.

The Author

## ABSTRACT

The flat grain beetle, *Cryptolestes pusillus* (Schon) (Coleoptera: Cucujidae) and the lesser grain borer, *Rhyzopertha dominica* (Fabricius) (Coleoptera: Bostrichidae) are the serious insect pest of stored commodities. *C. pusillus* is an internal and *R. dominica* is an internal feeder of whole wheat seed, flour, etc. The hemipteran predator, *Xylocoris flavipes* (Reuter) predate the eggs, larvae and pupae both of the pests in storage condition and checks their population in considerable level. A newly reduced risk broad-spectrum bacterium, Spinosad is effectively control the population of both *C. pusillus* and *R. dominica*. The effects of different life stages of both hosts on the biology of *X. flavipes* under laboratory condition were assessed. The influence of Spinosad on both hosts and predator and also the combined effects of *X. flavipes* and Spinosad on the population of *C. pusillus* and *R. dominica* were subsequently investigated.

The nymphs 1<sup>st</sup> up to 5<sup>th</sup> instar and adults of *X. flavipes* were found efficient to survive on eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instar and pupae of the both insect pest *C. pusillus* and *R. dominica*. The mean duration of developmental period through five nymphal instars on eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instars and pupae of were 15±2.00, 20±0.00, 22±0.58, 18±1.00, 14±1.15 and 12±1.15 days in *C. pusillus* and 18±1.00, 20±0.58, 16±2.00, 14±1.15, 12±1.15 and 13±0.58 days in *R. dominica* respectively. The adult female *X. flavipes* survived longer than the male. Average consumption rates of each nymph 1<sup>st</sup> up to 5<sup>th</sup> instar and adult stage of *X. flavipes* was found highest on eggs, 1<sup>st</sup> and 2<sup>nd</sup> instar larvae but lowest on 4<sup>th</sup> instar larvae and pupae of the both insect pests. The egg of *R. dominica* was more preferable than that of *C. pusillus*. Moreover, 1<sup>st</sup>, 2<sup>nd</sup> and 3<sup>rd</sup> instar larvae of the both host insect were more preferable to the predator than the other stages. The female predator always consumed more individuals of both the pests than the male. Average survivability rates of nymphs 1<sup>st</sup> up to 5<sup>th</sup> instar and adults were maximum on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae and minimum on 4<sup>th</sup> instar larvae and pupae. The size of the female predator was found larger than the male at all stages studied. Based

on ratio 1:1, sex ratio was found the best (male and female almost equal in number) on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae comparatively than that of other stages. Developmental period, adult longevity, consumption rates, survivability rates, size and sex ratio of *X. flavipes* always significant ( $P < 0.001$ ) in different life stages of both the insect pests.

The average percentage of egg hatchability ( $\pm$ SE) was the highest as  $25.00 \pm 1.15$  at  $0.491 \mu\text{l}/\text{cm}^2$  and the lowest  $5.00 \pm 1.02$  at  $7.863 \mu\text{l}/\text{cm}^2$  when *C. pusillus* was applied different concentrations of Spinosad and the results found highly significant ( $P < 0.001$ ). On the other hand, average ( $\pm$ SE) mortality of larvae, pupae and adults were found the highest as  $14.00 \pm 2$ ,  $8.33 \pm 0.88$  and  $15.33 \pm 1.22$  respectively at  $7.883 \mu\text{l}/\text{cm}^2$  after 72h and the lowest  $3.33 \pm 0.88$ ,  $1.67 \pm 0.33$  and  $5.00 \pm 0.58$  at  $0.491 \mu\text{l}/\text{cm}^2$  Spinosad concentrations after 24h of exposure. The larvae (72h  $LC_{50}$  was  $0.1755007 \mu\text{l}/\text{cm}^2$ ) and adults (72h  $LC_{50}$  was  $0.839572 \mu\text{l}/\text{cm}^2$ ) were found more susceptible than pupae (72h  $LC_{50}$  was  $35.94058 \mu\text{l}/\text{cm}^2$ ).

Effects of separate concentrations of Spinosad on different stages of *R. dominica* were investigated and found that average percentage of egg hatchability ( $\pm$ SE) was the highest as  $15.00 \pm 1.14$  at  $0.491 \mu\text{l}/\text{cm}^2$  and the lowest  $0.33 \pm 1.03$  at  $7.863 \mu\text{l}/\text{cm}^2$ . The effect of different concentrations on egg hatchability was highly significant ( $P < 0.001$ ). Average ( $\pm$ SE) mortality of larvae, pupae and adults were  $13.33 \pm 0.88$ ,  $8.33 \pm 1.45$  and  $17.33 \pm 1.20$  at  $7.863 \mu\text{l}/\text{cm}^2$  after 72h and the lowest  $4.67 \pm 0.33$ ,  $1.00 \pm 0.58$  and  $6.67 \pm 0.88$  at  $0.491 \mu\text{l}/\text{cm}^2$  after 24h of exposure periods. Larvae (72h  $LC_{50}$  was  $0.5433412 \mu\text{l}/\text{cm}^2$ ) and adults (72h  $LC_{50}$  was  $0.466328 \mu\text{l}/\text{cm}^2$ ) were found more susceptible than pupae (72h  $LC_{50}$  was  $22.0538 \mu\text{l}/\text{cm}^2$ ).

Different concentrations of Spinosad on different life stages of *X. flavipes* were investigated and recorded average percentage of egg hatchability ( $\pm$ SE) was highest  $35.00 \pm 1.73$  in control (untreated) and lowest  $25.00 \pm 2.12$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentrations. At 1.966, 0.983 and  $0.491 \mu\text{l}/\text{cm}^2$  concentrations, the egg hatchability was almost similar like in control medium. Effect of different concentrations on egg hatchability was not significant ( $P < 0.001$ ) comparatively than that of control medium. Average ( $\pm$ SE) mortality of nymphs and adults was found highest as  $6.67 \pm 1.76$  and  $5.00 \pm 0.45$  at  $7.863 \mu\text{l}/\text{cm}^2$  after 72h but lowest  $1.00 \pm 0.58$  and  $1.67 \pm 0.67$  at  $0.491 \mu\text{l}/\text{cm}^2$  Spinosad

concentrations after 24h of exposure. A nymph (72h  $LC_{50}$  was  $73.82966\mu\text{l}/\text{cm}^2$ ) was found more susceptible comparatively than that of the adult (72h  $LC_{50}$  was  $331.5098\mu\text{l}/\text{cm}^2$ ). Moreover, at 0.491, 0.983 and  $1.966\mu\text{l}/\text{cm}^2$  concentrations after 24h to 72h of exposure, survivability of adults were found 94 to 84% respectively.

The adult population of *C. pusillus* and *R. dominica* was significantly ( $P < 0.001$ ) reduced by *X. flavipes* and different concentrations of Spinosad alone and their combinations after 3, 6, 9 and 12 months of storage than those of control medium. After 3 months, from Spinosad concentrations reduced the population from 57.69 to 66.12% compared to control. In combination this range was from 42.86 to 51.56%. After 6 months, this reduction percentage rate was increased in both concentrations and combinations. After 9 months, this reduction percentage rate was increased continuously and after 12 months the effect of both concentration and combination were found more effective compare to early storage period. In case of the predator alone, the population of the both insect pests was higher than those of concentrations and combinations. The population of both insect pests was found more susceptible to the combinations comparatively than that of concentrations. The population of *R. dominica* was found more susceptible to different concentrations and combinations than that of *C. pusillus* at all storage periods.



# **Chapter 1**

## **General Introduction**

## INTRODUCTION

**Insect pest of stored products and management scenario:** Insects are the most diverse group of animals, including more than one million described species which are half of all known living organisms (Chapman 2006, Richard *et al.* 2007 and Wilson 2009). They appeared on the earth about 500 million years ago and are the oldest inhabitants of this planet (Saxena 1996). Some species of insects produce honey, silk and fibres, some of them pollinate flowering plants, and are now cultured primarily for pollination management in order to have sufficient pollinators in the field, orchard or greenhouse at bloom time (Smith *et al.* 1991). Some insects have also gained attention as potential sources of drugs and other medicinal substances (Aaron 2010). Fly larvae (maggots) were formerly used to treat wounds to prevent or stop gangrene, as they would only consume dead flesh. Some insects are also used as bio-control agents who are usually considered as beneficial because they can reduce the impact of pests and the use of pesticides in agriculture and food storage systems (Kenis and Branco 2010).

Although many insects attract the most attention positively but a large number of insects, alien insects and mite's species cause serious socio-economic hazards as pests of agriculture, horticulture, stored products, forestry and also may affect human or animal health (Kenis and Branco 2010). The struggle between men and insects began long before the dawn of civilization, has been continued without cessation to the present time and will continue, no doubt, as long as the human race endures. It is because of the fact that both men and certain insect species constantly want the same things at the same time (Metcalf and Flint 1962).

Men began to store foodstuffs right from the prehistoric days (Metcalf and Flint 1962, Retnakaran *et al.* 1985), to face the future demands and to ensure the supply of food but at times, insects cause so much damage to the crops that much of these get ruined. The inevitable world population growth placed increasing demands on the production of cereal and other food grains which comprise 67-80% of human food supply and diet (Kendall and Pimentel 1994, Dyson 1999). It is estimated

that losses of cereal grains in storage can range from 10 to 20% of overall production and a primary factor in these losses is the depredations of stored product insect pests (Phillips and Throne 2010). McEwen (1978) and Pimentel (1978) stated that world crop losses due to pests is approximately 35% of the total production in each year despite of best efforts. The crop loss is further increased at the post-harvest systems due to insects and other pests (Wright 1976). Globally only insect pests destroy approximately 14% of all potential food production (Pimentel 2007).

Pest problem have increased side by side with the increased amount of food stockpiled and the longer duration of storage (Khan and Mannan 1991). It is apparent that a number of insects act as enemies to the life of human, their pets and plants (Jha 1987). More than 2000 species of field and storage pests annually destroy approximately one third of world's food production, among which highest losses occur in developing Asian countries (Ahmed and Grainge 1986). A higher quality of the post harvested crops are damaged in the tropical countries by insects (Mondal and Port 1995, Mondal and Malek 1996) which are generally expressed in terms of direct weight and nutrient loss (Howe 1965a, Krishnamurthy 1975, Watters and Shuyler 1977). Moreover food losses due to insect infestation in the store is higher in tropical and sub tropical countries than in the temperate climatic zones (Girish *et al.* 1988). The annual costs arising from the two grain beetles *Oryzaephilus surinamensis* and *Rhyzopertha dominica* vary from 11.2 to 35.3 million € only in Germany (Reinhardt *et al.* 2003).

In some developed countries grain can be downgraded or rejected completely if even a single live insect is found (Pinniger *et al.* 1984, Anonymous 1990). In UK the Food Safety Act was amended recently; now all stores containing grain which might be destined for human consumption are treated as food premises and subject to inspection to ensure that food is not contaminated. The contamination of foods and animal feeds with mycotoxins is a worldwide problem (Kabak *et al.* 2006). The insect pests are detected in stored grain very soon after grain is brought in for storage (Hagstrum and Throne 1989, Dowdy and Mc Gauphey 1994) and they can



cause taint and contamination of grain with their excreta, cast skins and dead bodies (Scott 1991). Moreover, the presence of insects in stored foods directly affects both quantity and quality of the commodities (Hill 1978, Wilbur and Mills 1978, Burkholder and Faustini 1991, Khan and Mannan 1991).

A variety of pests are found in stored grain and cereal commodities and food processing facilities, depending upon geographic location, physical nature of the facility and the type of food being processed (Abd-El-Aziz 2011). Among the insect pests of stored commodities, the beetles (Coleoptera) are by far the most numerous group, followed by the moths (Lepidoptera) (Khan and Mannan 1991). Among these two groups other insects also share the stored habitat, and these are ants (Hymenoptera) (Smith 1965, Mallis 1982), cockroaches (Dictyoptera) (Cochran 1982, Mallis 1982), flies (Diptera) (Greenberg 1971, 1973, Mallis 1982), silverfish (Thysanura) (Mallis 1982) and springtails (Collembola) (Mallis 1982) psocids (Psocoptera) (Turner 1975, Mallis 1982). Globalization increased trade,, travel and transport and leading to an unprecedented homogenization of the world's biota by transport and subsequent establishment of organisms beyond their natural barriers (Wittenberg 2005). In Europe, 113 alien insect species are pests of stored products (Rees 2004) where as in Switzerland, about 800 alien species are established (Wittenberg 2005). In USA, a total of 61 species of insects have been reported at elevators or in flat storages (Hagstrum *et al.* 2010). The Canadian Grain Commission recognizes over 50 species of insects (including grain mites) as pests of stored grain. In Bangladesh 29 species of insect pests of stored products are listed by Alam (1971).

Among the insect pests the flat grain beetle, *Cryptolestes pusillus* (Schon.) is an external feeder of craked grains, a serious cosmopolitan pest of stored product commodities, and may subsequently build up huge population within very short time (Rahman *et al.* 2008). The genus has two other species *C. ferrugineus* (S) (Rusty grain beetle) and *C. turcicus* (Grouelle) (Flour mill beetle), having the same feeding habits. The lesser grain borer, *Rhyzopertha dominica* (F) is a primary pest of stored grains feeding the grain kernels, found in many regions of the world (Edde 2012).

The adults likely to fly back and forth between agriculture and non-agriculture land scapes (Ede *et al.* 2005, Mahroof and Phillips 2007, Jia *et al.* 2008 Mahroof *et al.* 2010) and is an internal feeder of sound grain. Hagstrum and Flinn (1994) reported that in farm bins *R. dominica* was present in 78.6% and *Cryptolestes* spp was present in 85.8%. Both *C. pusillus* and *R. dominica* are economically harmful and are available in stored cereal, cereal products and other commodities (Alam 1971).

Early attempts to control stored grain pests relied on methods such as mixing dry soil and wood ash with the grain, causing lethal dehydration of insects and the fumigant action of certain indigenous plant materials (Levinson and Levinson 1989). Control of stored-product pests is necessary to prevent contamination or adulteration of human foods. Persons involved in commodity or food storage, handling or processing, have the responsibility to prevent food adulteration (Abd-El-Aziz 2011). The middle decades of the twentieth century have been years of the revolution in the field of pest control triggered during the World War II by the discovery of DDT in 1939, and its successful utilization against a number of pests. It has been estimated that about 4.5 million metric tones of pesticides are used annually in the world agriculture (Smith and Van den Bosch 1967, Pimentel 1983). Pesticides sales in Bangladesh in 1954 was only 9 tons which up to 18902.5 tons of formulated products in the year 2000, went costing Tk 3001.56 million (Hasanuzzoha 2004) and the amounts of pesticides used in Bangladesh are being increased day by day.

Chemical pesticides are still indispensable in controlling insect pests both in field and storage due to their quick knockdown and killing properties. The efficacy of insecticides against storage pests varies greatly according to their chemical structures, insect species and the storage environment (Suchita *et al.* 1989). Indiscriminate and large-scale use of broad spectrum synthetic pesticides caused serious hazard including its persistence in the environment (Smith 1970, Wilkin and Fishwick 1981, Jolly *et al.* 1989, Bryne *et al.* 1994, Laliberte 1995, Bell *et al.* 1999, Rajapakse *et al.* 2000, Daghish and Wallbank 2002); toxicity to human beings (Anonymous 1981, Oudejans 1982, Hasanuzzoha 2004, Nayak *et al.*

2005), wild life including pollinator and economically beneficial insects (Munakata 1977, Pimentel 1981, 1983, Oudejans 1982, Daglish 2006); development of insect resistance to the insecticides (Georghiou and Mellon 1983, Champ 1986, Reichmuth 1992, Subramanyam 2006a); and finally, higher cost of crop production (Khan and Mannan 1991). Moreover, both multi-resistance and cross-resistance to pesticides has been reported in a large number of insects (Metcalf 1980, Georghiou and Mellon 1983). Sometimes, toxic residues of pesticides accumulate in the ecological food chain and become concentrated by bio-magnification (Metcalf and Luckman 1975). Concerns over pesticide operator safety and residues in our food and the environmental have led to a review of all organophosphorus pesticides by the Pesticide Safety Directorate in UK, their current advice is for farmers to avoid to use these pesticides altogether unless there is no alternative (Rooker 1999). Presently, there is a great concern in the post-harvest ecosystems throughout the world particularly in developing countries including Bangladesh (Champ 1979, Subramanyam and Hagstrum 1995). In spite of insecticides being the major means of defense against insect pests, the above mentioned problems have generated a sustained search for either alternative means of insects control methods for reducing the amount of insecticides required for the pest management (Mondal 1984a, Smet *et al.* 1990, Burkholder and Faustini 1991) or to search for eco-friendly new methods. Therefore, stored-product pest control strategies tend to emphasize the non-chemical aspects of pest control with the judicious use of pesticides (Abd-El-Aziz 2011).

In this respect, *Xylocoris flavipes* is a cosmopolitan predator of different preying on insect pests of stored commodities namely *Tribolium castaneum*, *T. confusum*, *Cryptolestes pusillus*, *Rhyzopertha dominica* and *Trogoderma granarium* (Ahmed *et al.* 1991). Toews and Subramanyam (2004) found that Spinosad applied to stored wheat at 1 ppm was highly toxic to the parasitoids *Habrobracon hebetor* (Say), *Theolax elegans* (Westwood), and *Anisopteromalus calandrae* (Howard), yet not so to the warehouse pirate bug, *X. flavipes* (Reuter), which demonstrated 92% survival and was able to reproduce under these same conditions.

Spinosad will represent a valuable new addition to the limited arsenal of grain protectants and can positively impact global food security (Hertlein *et al.* 2011). Its combination of high efficacy, broad insect pest spectrum, low mammalian toxicity, and sound environmental profile is unique among existing products currently used for stored-grain protection (Thompson *et al.* 2000). In several countries, Spinosad are being widely used to protect stored products against insect pest including *C. pusillus* and *R. dominica* (Hertlein *et al.* 2011). Spinosad is minimally disruptive to beneficial insects and compatible with Integrated Pest Management (IPM) programs in many crops (Miles 2006 and Arthurs *et al.* 2007).

Unmanaged pest problems and unsafe pesticide use practices threaten human health and the environment. Full implementation of IPM is affordable and cost-effective and can reduce pesticide exposure, pesticide use and pest complaints. A coordinated global effort is critically needed to make safe and effective insect pest management the standard for all of stored products including paddy, rice, wheat, wheat flour, pulses, maize and sorghum (Thomas *et al.* 2009).

Keeping these views in mind and considering the merit of using natural pest control agents like predator, bacteria, etc., the research reported here was initiated to investigate the possible combined effects of the predator, *X. flavipes* and the bacterium, Spinosad for the control of two important stored product insect pests *C. pusillus* and *R. dominica*.

### **Test insects, their distribution and damage**

Among the major insect pests causing serious damage to stored products *Cryptolestes pusillus* (Schon) and *Rhyzopertha dominica* (F.) were selected for the present research because they are of great threats to the stored grains and cereals of Bangladesh. These two insects have different feeding habit, the former one is an external feeder of broken grains and cereals, the later one is an internal feeder of whole grain. Both are consumed as prey by the warehouse pirate bug, *X. flavipes*.

***Cryptolestes pusillus*:** *C. pusillus*, flat grain beetle, is a member of the family Cucujidae, order Coleoptera. Granglbour in 1899 described this beetle under family named Laemophloeidae which consists of 500 species worldwide (Thomas and Leschen 2010). Nine pest species of *Cryptolestes* occurring in stored products are *C. capensis* (Waltl), *C. cornutus* (Thomas and Zimmermann), *C. divaricatus* (Grouvelle), *C. ferrugineus* (Stephens), *C. klapperichi* (Lefkovitch), *C. pusilloides* (Steel and Howe), *C. pusillus* (Schonherr), *C. turcicus* (Grouvelle) and *C. ugandae* (Steel and Howe) (Halstead 1993). In spite of Banks (1980) and Halstead (1993) publications, *Cryptolestes* specimens are usually identified to generic level only. *Cryptolestes pusillus* was first proposed by Schoenherr (1817). *C. pusillus* has two synonyms such as *Laemophloeus pusillus* and *Laemophloeus mintus*. The local name of *C. pusillus* is chapta beetle.

**Distribution of *C. pusillus* :** *C. pusillus* is most prevalent in warmer climates and occurs throughout the crop-growing regions of the world. It is particularly common in wet tropical and warmer temperate regions, but unable to survive in unheated premises in cooler temperate regions (CABI Crop Protection Compendium 2008, Halstead 1993). In Canada, *C. pusillus* has been recoded in grain elevators and flour mills feeding on damaged grain, preferably wheat (Bousquet 1990). So far, only cosmopolitan *C. ferrugineus*, *C. pusillus* and *C. pusilloides* have been detected in Australia (Halstead 1993). Adult beetles can fly. Although its origin is unknown, *C. pusillus* has been transported internationally in exported commodities.

**Damage:** The flat grain beetle, *C. pusillus* is one of the smallest and most common destructive major insect pests of stored grains (Davies 1949, Pajni and Bedi 1974, Barker 1976 and Hole *et al.* 1976). This beetle feeds on groundnuts, Coffee, barley, rice, sorghum, cocoa, wheat, flour, oilseeds, cassava root, dried fruits, chilies, maize and other dried stored food commodities (CABI Crop Protection Compendium 2008). In cooler and drier regions of the world, it is found mainly in cereal and cereal products, while in warmer and humid regions it infests a much wider range of products (Hole *et al.* 1976). The most favoured food of this

beetle is cracked cereal grains, which gives insect access to the germ, and provides better harborage and oviposition sites (LeCato 1974). Larvae feed preferentially on the germ of the whole kernels, but they also feed on the endosperm and sometimes hollow out the entire kernel. Growth of mold in the endosperm renders it more suitable as larval food. *Cryptolestes* species are apparently unable to feed on sound grain, but they can feed on kernels with very slight imperfections or injuries.

***Rhyzopertha dominica*:** The lesser grain borer *Rhyzopertha dominica* was first described by Fabricius in 1792 under the name *Synodendron dominicum* from specimens taken from nuts and roots imported from India (Chittenden 1911). Lesne (1896) later recorded the insect as *Rhyzopertha dominica* and published a full description of the insect under this name. *Rhyzopertha dominica* is a member of the family Bostrichidae under the order Coleoptera. There are about 550 bostrichid species in 99 genera of which 77 species in 26 genera occur in North America (Marske and Ivie 2003). Bostrichids are reddish-brown to dark-brown in colour of various in sizes, elongated, cylindrical in cross-section, and their head is invisible when viewed from above. The insects live mainly in dead and dried wood, and are pests of timber also (Potter 1935, Fisher 1950, Mathew 1987, Ivie 2002a, b).

**Distribution:** The origin of *R. dominica* is not known with certainty, but the consensus is that the Indian subcontinent is the native home of the insect because the region is the focus of many species of bostrichid (Chittenden 1911, Schwardt 1933 and Potter 1935). Nowadays, *R. dominica* is widely distributed around the world (Potter 1935 and Chujo 1958) and is a primary pest of stored grain in warmer regions lying in the belt between latitude 40° N and latitude 40° S of the equator (Potter 1935). *R. dominica* is largely distributed during the transport of grain (Doane 1919 and Chujo 1958) and was first noticed in the United States of America (USA) in specimens of wheat distributed from the Patent Office (Leconte 1862) and became established in the country in the early 1920s (Back and Cotton 1922). The establishment of *R. dominica* in the USA is believed to have been

augmented by importation of infested wheat from Australia (Doane 1919), and hence the insect sometimes referred as the “Australian wheat weevil” in early publications (Cotton and Good 1937). *R. dominica* is frequently captured in forest habitats and in grain storage environments, and the adults are likely to fly back and forth between agricultural and non-agricultural landscapes (Edde *et al.* 2005, Jia *et al.* 2008, Mahroof *et al.* 2010 and Mahroof and Phillips 2007).

*R. dominica* achieves its maximum reproductive success on dry grains, specially on wheat (Chittenden 1911, Schwardt 1933, Potter 1935, Bashir 2002 and Edde and Phillips 2006a,b). Published reports have shown that while *R. dominica* can tunnel in many woody plants, reproduction in most of them is generally poor (Wright *et al.* 1990, Edde and Phillips 2006a,b, Jia *et al.* 2008).

**Damage:** *R. dominica* is injurious to cereals; breeds in corn, rice, wheat, and in other substrates containing starch (Chittenden 1911). Grain infestations may result from residual insect populations inside storage structures and mixing of infested and uninfested grain or by *R. dominica* originating from outside sources (Sinclair 1982, Fields and Phillips 1994, Vela-Coiffier *et al.* 1997 and Hagstrum 2001). The flying adults generally enter a grain bin through the headspace, alight on the grain surface, and gradually moves through the grain mass in a slow downward progression (Sharangapani and Pingale 1957, Keever 1983, Vela-Coiffier *et al.* 1997 and Hagstrum 2001). *R. dominica* could move down into the grain mass to a depth of 12 m, which is deeper than observations for other grain beetles (Flinn *et al.* 2010). A wheat consignment containing more than 32 insect damaged kernels (IDK) per 100 g is designated as sample grade (Federal Grain Inspection Service 1997), which cannot be sold for human consumption (Flinn *et al.* 2004). There is a general trend toward a no tolerance for live insects and domestic flour mill contracts specify an upper rejection limit of 7 IDK per 100 g grain sample (Kenkel *et al.* 1993).

Grains infested by *R. dominica* have a characteristic sweetish odor, which is due to the male-produced aggregation pheromones (Khorramshahi and Burkholder 1981).

Adult feeding activities produce large amounts of frass, most of which consists of ovoid granules of apparently undigested endosperm mixed with a finer floury part (Breese 1960). The frass contain larvae exuviae, feces, fragments of immature insects, and other by-products, which could affect the end-use quality of the infested grain (Sanchez-Marinez *et al.* 1997, Seitz and Ram 2004 and Park *et al.* 2008). The larvae and adult *R. dominica* feed on both the germ and endosperm and are capable of reducing wheat kernels to the pericarp (Winterbottom 1922 and Campbell and Sinha 1976). The degree of feeding damage caused by adult *R. dominica* varies with beetle age, greater damage being caused by young adults (Rao and Wilbur 1972).

Several authors (Breese 1960, Campbell and Sinha 1976, Crombie 1944, Gay and Ratcliffe 1941, Golebiowska 1969, Howe 1965b, Rao and Wilbur 1972 and Wilbur and Halazon 1955) have investigated the amount of grain consumed by *R. dominica* under experimental conditions, but the estimate of losses varied among the authors. Campbell and Sinha (1976) reported 17% loss per kernel when *R. dominica* was allowed to develop from egg to pupa in wheat grains, whereas, Rao and Wilbur (1972) and Crombie (1944) reported 10 and 23% weight loss per wheat kernel, respectively.

#### **Alternate insect control methods using at present**

The pest management in stored commodities is facing many obstacles such as restrictions on the use of certain pesticides which caused resistance in pest population, pose possible health hazards and a risk of environmental contamination. Entomologists throughout the world spend a great deal of time and effort in attempt to determine the presence of insect pests in stored grains, check their infestations and design better and safer methods to bring them under control. Control measures of different nature are being adopted at farm, market and public sector storage that consist of use of native soar natural methods of control by plant materials or contact insecticides and fumigants (Maina and Lale 2004, Hussain *et al.* 2005).

Control of stored product insects is best achieved through an integration of physical, chemical and biological methods (Arthur 1996, Hagstrum *et al.* 1999,



Phillips and Throne 2010). However, in practice there is still a strong reliance on the use of chemicals applied to grains at the time of storage. To control an existing infestation, specially in grain that is not treated with a traditional chemical protectant, fumigants like phosphine is used. Promising techniques that have been developed and continues to be refined, is monitoring populations with insect pheromones and/or food attractants for detecting stored-product insects (Abd-El-Aziz 2011). Some chemical control products are under intense scrutiny due to concerns about human safety, insect resistance, environmental impacts and presence of chemical residues in raw and processed foods (Daglish and Wallbank 2002, Nayak *et al.* 2005, Daglish 2006). Alternative chemical control options to protect grain that do not suffer from the concerns outlined above are urgently needed and Spinosad is one such product that fills this void. Spinosad is currently registered in several countries as a grain protectant at a maximum labeled use rate of 1 ppm (1 mg/kg of grain) (Hertlein *et al.* 2011). Spinosad is effective against *R. dominica* (Subramanyam *et al.* 2003, Flinn *et al.* 2004 and Hertlein *et al.* 2011) and other economically important beetle including *C. pusillus* and moth pests associated with stored grain and is also effective against certain psocid species (Hertlein *et al.* 2011).

For a long time the biological control is an over-looked component of integrated pest management of stored product pest (Flinn 1998). Many species of natural enemies of insects occurs in stored product ecosystem (Brower *et al.* 1996). Among these the anthocorid bug, *X. flavipes* is a cosmopolitan predator of different prey (pests) of stored commodities namely *T. castaneum*, *T. confusum*, *C. pusillus*, *R. dominica* and *Trogoderma granarium* (Ahmed *et al.* 1991). Moreover, Computer-based decision support systems that use biological and environmental data to predict population trends and evaluate the need for insecticidal inputs have been developed for stored-product storage systems in several countries (Abd-El-Aziz 2011).

### **Environmental control**

Insects in stored grain can be controlled by manipulating the physical environment or applying physical treatments to the grain and insects (Abd-El-Aziz 2011).

The factors of the physical environment are temperature, relative humidity or grain moisture content and relative composition of atmospheric gases in the intergranular air. Physical treatments include physical removal and physical barriers to prevent the entrance of insects, inert dusts, light and sound. Different types of physical control practices have been reviewed by a number of researchers (Shejhal 1980, Cline *et al.* 1985, Lapp 1986, Armitage 1987, Bell 1987, Lessard 1987, Navarro and Jay 1987, Wilkin and Nelson 1987, Cline and Press 1990, Banks and Field 1995, Golob 1997, Subramanyam and Hagstrum 2000).

In the developing countries of Asia and Africa the harvested grains, paddy, sorghum, millets, pulses or oil seeds are sun-dried before storage to eliminate insects if present (Rajendran and Chayakumari 2003). The eggs of the stored product insects could be eliminated by milling wheat to flour or by sieving flour through 210 $\mu$ m mesh (Yamanouchi and Takano 1980). Cooling of wheat by low volume aeration is used in modern Europe, Canada and United States (Arthur 1996) but cost of the cooling equipments and treatment is high (Longstaff 1999) which could not justify its economic use in developing countries. High temperature fluidized bed have reached a pilot scale for the disinfestations of grains and their products, and short exposures to temperature above 60°C are generally effective for the disinfestations of grains (Evans 1981, 1987a, b). Insects coated in inert dusts dehydrate and die, so inert dusts have been used for centuries by aboriginal people in North America and Africa to control insects in their stored grain. According to Fields and Muir (1996) five types of inert dusts such as i) sands and other soil components are traditional insecticides used by aboriginal peoples as a protective layer on top of stored seed (Golob and Webley 1980); ii) Silica aerogel, produced by drying an aqueous solution of sodium silicate have been reported to control a number of insect species including *C. pusillus* and *R. dominica* (Le Patoural 1986, Desmarchelier and Dives 1987, White and Loschiavo 1989, Aldryhim 1991, 1993, Quarles, 1992); iii) non-silica dusts, such as rock phosphate, have been used in Egypt (Fam *et al.* 1974) and lime (calcium oxide) provides insect control (Golob and Webley 1980); iv) Particle films (Kaolin and bentonite clays) also have potential

for use as a dry dust material in stored-product environments. The particle film M-96-018 was reported to be effective against the *Tribolium* species and appears to have a potential for use in management programs to control beetles within storage facilities (Arthur and Puterka 2002); v) Diatomaceous earth (DE) the fossilized remains of diatoms having low mammalian toxicity regarded as safe by the USA Environmental Protection Agency (Subramanyam and Hagstrum 1995) and (Anonymous 1991). DE also showed efficacy against *R. dominica* on stored wheat (Kavallierator *et al.* 2005, Athansassion and Kavallierator 2005), preventing economic damage of stored rice (Chanbang *et al.* 2008). However, it is difficult to control *R. dominica* within grain using DE alone (Arthur 2004b, Chanbang *et al.* 2007a, b).

Light may be of some use in luring flying insects into traps (Banks and Fields 1995). A 5-min exposure to 1 MHz sound at  $14.5 \text{ Wcm}^{-2}$ , killed all life stages of *S. granarius* at  $26^{\circ}\text{C}$  in wheat but commercial application is unexpected (Banks and Fields 1995). Controlled and modified atmosphere storage practices for protecting grains have also proved to be potential in stored insect pest control (Hyde *et al.* 1973, Anonymous 1984, Evans 1987b, Hulasare *et al.* 2005). Ozone is known as a sterilant of stored product insect pests at levels less than 45ppm (Abd-El-Aziz 2011). Packing materials very often produce barrier against the insect infestation in storage.

*Sitophilus* spp, *R. dominica*, *Plodia interpunctella*, *Lesioderma serricorne*, *Stegobius* are capable of penetrating food packaging but *Tribolium* spp, *C. pusillus*, *C. ferrugineus*, *Oryzophilus* spp cannot penetrate intact packages and must enter through existing holes in the package (Highland 1991). Sabbaur and Abd-El-Aziz (2007) screened the most suitable packaging materials (muslin paper, cheesecloth, wax paper, gunny bags and polypropylene) for prevention of broad bean beetle infestation.

### **Control by radiation control**

Various forms of electromagnetic energy have been considered potentially useful for insect control (Nelson 1967). These include ionizing radiation of extremely high frequency (X- rays and gamma rays) which may be used to cause mortality or to induce sterility. Potentially useful non-ionizing radiations are infrared, visible and

ultraviolet; infrared may be used to kill pests directly whereas visible and ultraviolet may be used to attract pests to traps (Crowdar 1986). Ionizing radiation damages organisms by causing the production of ions or free radicals-charged molecules that are highly reactive and chemical bonds can also be broken. Both types of ionizing irradiation have been used to control insects in grain stores (Fields and Muir 1996) To cause immediate death to stored product insects may require higher doses, sterilization of many species of insects can be accomplished at lower doses, but Rusty grain beetles are sterilized at only 0.6 kGy but saw-toothed grain beetles and red flour beetles require a 2.0 kGy dose (Banks and Fields 1995). The use of irradiation to suppress *T. castaneum* has been widely studied (Fontes *et al.* 1996, Hasan 1995, Khattak and Jilani 1984, Pajni and Virk 1978). To manage the pulse beetles (*Callosobruchus* spp) irradiation has become the major tool (Ghomomu 1989, 1991, Hussain and Imura 1989). A number of reports are present showing that the females coleopterans are more sensitive to gamma radiation than males (Ashraf and Brower 1974, Ahmed *et al.* 1976, Hasan 1995). Microwaves synerise with low temperature could provide an effective and friendly environmental treatment technique in IPM program (Valizadegan *et al.* 2009).

### **Chemical control**

Chemical control of stored product insect pests includes some low risk insecticides, fumigants and the novel insect growth regulators. The developing countries of Asia and Africa still depend on the traditional chemical control method because of their quick positive results against the insect pests in the agriculture and storage system (Ferdous 2006).

### **Insecticides**

Large number of insecticides have been used in the grain storages of the world since the time of World War II However, the after effects of the inorganic insecticides resulted in to develop organic insecticides. A large number of such organic insecticides are used in grain and cereals stores throughout the world. Many of the organic insecticides gave desired level of control against storage pests including *C. pusillus* and *R. domonica* in laboratory and in storages (Khan 1981, Rahman and Yadav 1985, Mondal 1986, Yadav 1987, Mondal 1988,

El-Sayed *et al.* 1988, Islam *et al.* 1989, Rajendran 1990, Ali *et al.* 1991, Collins and Cook 1998). New reduced-risk chemical insecticides are still developing to control the resistant strains of the storage insects.

Relative to other stored grain insect pests, *C. pusillus* and *R. dominica* are the most difficult insect pests to control with insecticidal grain protectants (Zettler and Cuperus 1990, Lorini and Galley 1999, Collins 2006); many of approved insecticides are either not effective against the insect pests including or the insects have developed resistance to them (Parween 1996). *R. dominica* has developed resistance to all approved organo-phosphorus insecticides (Navarro *et al.* 1987, Zettler and Cuperus 1990, Guedes *et al.* 1996, 1997, Lorini and Galley 1999, Collins 2006), and resistance of *R. dominica* to pyrethroid-based grain protectants is widespread (Lorini and Galley 1996, Collins 2006).

**Fumigants:** Vijayanna (2006) mentioned that fumigants are effective in pest control as these gaseous are suffocative or poisonous against the insects. Fumigation plays a major role in insect pest elimination in stored products. Phosphine and methyl bromide are the two common fumigants used for the management of stored-product insect pests worldwide (Rajendran and Sriranjini 2008). Phosphine once was the most important fumigant to control *R. dominica* (Collins 2006 and Dargatzis *et al.* 2010). However, some species including *C. pusillus* and *R. dominica* develop resistance to phosphine which became global issue (Herron 1990, Zettler and Cuperus 1990, Lorini and Collins 2006, Schlipalius *et al.* 2008, Newman 2010) and control failures have been reported in field situations in some countries (Taylor 1989, Collins *et al.* 2002). Methyl bromide, a broad-spectrum fumigant, has been declared an ozone-depleting substance and therefore, is being phased out completely in 2015 (Taylor 1994, Fields and White 2002, Bartholomaeus and Haritos 2005). Chloropicrin and Candorsis have been reported from Italy as easiest alternatives to methyl bromide (Spotti 2004). Recently, the use of sulphuryl fluoride, a structural fumigant for termite and woodborer control, has been expanded to food commodities and food handling establishments (e.g., flourmills) in the USA, Canada and Europe (Prabhakaran 2006). New fumigants such as carbonyl sulphide and ethane dinitrile and the old

fumigant ethyl formate (alone and in mixture with CO<sub>2</sub>) can be as alternatives for food and non-food commodities from the infestation of insect pests including *C. pusillus* and *R. dominica* (Damcevski *et al.* 2003).

**Insect Growth Regulators (IGRs):** The use of insect growth regulators (IGRs) in controlling of stored product insect pests was suggested by Thomas and Bhatnagar Thomas (1968). On the basis of mode of action, IGRs are divided into three categories such as (1) Juvenil hormones (JHs) and their analogues (JHAs) also called as juvenoids e.g. methoprene, hydroprene etc. which control physiological and behavioural activities (Arthir 2004, Collins 2006, Daghli *et al.* 1995, Daghli 2006), (2) ecdyson agonists which regulate the morphogenetic changes during metamorphosis and (3) chitin synthesis inhibitors (CSIs) or moult inhibitors (MIs) e.g. triflumuron, diflubenzuron etc. which interfere with chitin biosynthesis, prevent moulting and produce an imperfect cuticle and are effective suppressors of development for entire life cycle of insect pests (Post and Vincent 1973, Mulder and Gijswitj 1973, Post *et al.* 1974, Wills 1974, Mulder *et al.* 1975, Grosscurt 1978, Reynolds 1987, Wing and Aller 1990, Edwards and Menn 1981, Koolman 1989, Fox 1990, Heller *et al.* 1992, Oberlander *et al.* 1997). IGRs used in stored product systems in the United States and elsewhere include the insect juvenile hormone analogs (Arthur *et al.* 2006). Compared with the conventional insecticides, IGRs do not exhibit quick knock-down in insects or cause mortality, but the long- term exposure to these compounds largely stops the population growth as a result of the effects mentioned in both parents and progeny (Mondal and Parween 2000). Potentiality of IGRs against *Cryptolestes* spp. was studied by Kostyukovsky *et al.* (2000). IGRs affect development of immature insects including *C. pusillus* and *R. dominica*, methoprene affects the egg and larval stages of stored product insects and suppress progeny production of *R. dominica* (Mian and Mulla 1982a, b, Oberlander *et al.* 1997). The efficacy of IGRs against the stored product insects have been reviewed by Parween (1996), Mondal and Parween (2000).

IGRs represent low-risk, biologically based insecticides with potential for more adoption in the food industry in the future. The chemically synthetic nature of IGRs, however, are non-toxic to the environment and its biota (Fox 1990) and are also effective against the insecticides resistant strains of insect pests (Bengston 1987).

### **Botanicals as control measure**

Botanicals are comparatively less expensive and are easy to prepare and use. Traditionally the farmers and stockers used plant materials or botanicals at early periods to protect stored grains against insect pests in many countries of Asia and Africa. Botanical Insecticides are locally available and are widely used to suppress stored product insect pests (Golob and Webley 1980). Specially plant may provide alternative potential to the currently used insect control agents as they constitute a rich source of bioactive molecules (Rajashekar *et al.* 2012), and are also safe for non-target animals, human being and ecofriendly (Srinivasa *et al.* 1993). Since last part of 20<sup>th</sup> Century number of plants have been screened for their insecticidal, repellent and antifeedant activities against the stored product insects, some of the latest reports are (Rajashekar *et al.* 2010, Mandal and Khalequzzaman 2010, Sabbur and Abd-El-Aziz (2007, 2010) Maia and Moore (2011), Khater (2012) and Dimetry (2012).

Plant oils are strong insecticides and effectively control the internal feeders of the grains at storage (Shukla *et al.* 1992, Xu *et al.* 1993, Yadav 1993, Obeng-Ofori 1995, Sanguanpang 1996, Shaaya *et al.* 1997, Liuv and Ho 1999, Keita *et al.* 2001, Haghtalab *et al.* 2009). Powders of different parts of a number of plants showed efficacy as repellent, antifeedant and growth inhibition along with toxicity against the stored product insects including *R. dominica* (Dakshinamurthy and Goel 1992, Tiwari 1994, El-Lakwah *et al.* 1994, Jembere *et al.* 1995, Mahal 2002). Besides that extracts of plant parts have been proved as potent insecticides and suggested to use as grain protectants (Shaaya *et al.* 1997, Sumita 2006, Mondal *et al.* 2012). In this context the neem-based compounds stand for unique position as insecticide in the stored and filled ecosystems (Ahmed and Grainge 1986). Compounds derived from plants continue to be assessed for their potential to

control storage pests (Allotey and Azalekor 2000). Botanical pesticides are always relatively safer for vertebrate animals and environments (Odderskaer *et al.* 2003). Although botanicals are environmentally friendly but they are used in less quantity in Bangladesh due to lack of organized production and marketing (Ali 2004). Furthermore, interest has been shown in plant products i.e., essential oils and their components for fumigant action since it is believed that natural compounds from plant sources may have the advantage over conventional fumigants in terms of low mammalian toxicity (not true in all cases) rapid degradation and local availability (Rajendran and Sriranjini 2008).

### **Biological control**

Biological control is an important component of integrated pest management of stored product pest (Flinn *et al.* 1998) that included various techniques such as use of resistant varieties, pheromones, sterile insects, pathogens, parasitoids, parasites, predators, etc. Biological control is a plausible alternative to chemical management of stored product pests, and a variety of examples of the use of natural enemies to protect stored raw commodities are provided by the literature viz., Brower (1990 and 1991), Brower and Press (1988), Brower and Mullen (1990), Flinn *et al.* (1994), Scholler *et al.* (1996), Flinn 1998, Flinn and Hagstrum 2001). Biological control was begun to be explored as a management strategy in food processing facilities since the last part of 20<sup>th</sup> Century. Many species of insect natural enemies occur in stored product ecosystem (Brower *et al.* 1996) and these species represent potential biological control agents for the desired pests of food processing facilities (Hansen 1998, Prozell and Scholler 1994, 1998, Steidle *et al.* 2001), warehouses, and retail stores (Prozell *et al.* 1996). The anthocorid bug, *Xylocoris flavipes* (Reuter) is a cosmopolitan predator of different prey (pests) of stored commodities namely *T. castaneum*, *T. confusum*, *C. pusillus*, *R. dominica* and *T. granarium* (Ahmed *et al.* 1991, Rahman *et al.* 2009).

Biological control (Smith 1911) was first used in 1911 against the Mediterranean flour moth (Froggatt 1992) as alternative to conventional pesticides (Waage 1991). The theory of biological control was based on natural control which can be



observed in the balance of predator-prey and parasite-host population (Huffaker and Messenger 1976), thus reducing the commodity damage to tolerance levels (De Bach and Rosen 1991). Insect control program one aimed to avoidance, elimination or reduction of the factors which promote excessive multiplication of insects (Nayar *et al.* 1976). Haines (1989), Van Huis *et al.* (1991), Islam and Khan (2000) reviewed the status or research of the role of parasite and predators in the management of the stored pests.

Recently the predatory beetle *Teretriosa nigrescens* (Lewis) has been introduced into West Africa to control *Prostephanus truncatus* (Horn) with moderate success (Markham *et al.* 1994). The impact of pesticides on natural enemies and the resulting outbreaks of secondary arthropod pests have been documented in many field agricultural systems (Croft 1990). Validation studies on the potential of natural enemies as biological controls agents as replacements for insecticidal protectants in storage system are in the focus of IPM programme throughout the world.

It is potential to select for insecticide resistance in certain parasitic and predatory species (Baker 1995, Baker and Arbogast 1995). Integrating the use of predatory/parasitic mites and insecticides for stored-grain pest management requires knowledge of the impact of the insecticides on the natural enemies or, in other words, their selectivity to natural enemies (Baker and Arbogast 1995, Goncalves *et al.* 2002). Goncalves *et al.* (2004) mentioned that the effect of insecticides on the mite species *Acarophenax lacunatus* (Cross and Krantz), an egg parasite of the stored grain pest *R. dominica* (F.). Deltamethrin was less selective in favor of the mite species. Nonetheless the parasitic mite was able to parasitize eggs of *R. dominica* on wheat treated with all the insecticides evaluated.

In some respects the artificial nature of man-made structures may serve to enhance biological control because augmentative natural enemies can be contained within the system and environmental conditions are relatively stable compared with those of natural systems. However, storage systems are also isolated from potential reservoirs of natural enemies, making inoculative or conservation biological control difficult. Thus, an inundative form of augmentative biological control may

be the most appropriate tactic for finished stored products (Scholler and Flinn 2000, Scholler *et al.* 1997). Releases of the warehouse pirate bug, *Xylocoris flavipes*, resulted in a 79-100% suppression of moth populations in small storages of peanuts, up to 99% reduction of sawtoothed grain beetle populations in 35-quart lots of corn and a 90-98% suppression of red flour beetles in a simulated peanut warehouse. Rice weevils in wheat spillage in small rooms were suppressed 96% by the parasitic wasp *Anisopteromalus calandrae*. When the egg parasitoid *Trichogramma pretiosum* and the larval parasitoid *Bracon hebetor* were released together in simulated peanut warehouses, they suppressed Indianmeal moth populations by 84% and almond moth (*Cadra cautella*) populations by 98%, *B. hebetor* alone suppressed almond moth populations by 97.3%. A variety of natural enemies have been evaluated for use against stored product moths, and has also been evaluated as a potential biological control agent for stored product moths and beetles (Press *et al.* 1974, 1982, Keever *et al.* 1986, Krazpulski and Davis 1988). Furthermore, much of the literature concerning biological control of stored product moths involve releases of multiple species of natural enemies, including combinations of egg and larval parasitoids (Brower 1990), *H. hebetor* and *V. canescens* (Press *et al.* 1982), parasitoids and predators (Press *et al.* 1974, 1982, Keever *et al.* 1986, Krazpulski *et al.* 1988). Overall, *Trichogramma* species and *H. hebetor* have been the most frequently used natural enemies for stored product moths.

The advantages of biological control are free of side effects, safe to handle or use, occurs naturally, high degree of host specificity, cost effective, self perpetuation, searching ability and survive at low density. Research is continuing to determine the proper prescriptions for use of natural enemies in stored grain. Behavioral, ecological and physiological data are being collected that will facilitate effective deployment of parasitoids and predators. Storage situations other than grain bins, such as feed mills, food warehouses and food factories may be targeted areas for biological control in the future. As part of an IMP system for stored product management, biological control should help to reduce the use of pesticides on food and provide for high quality food products. Biological control in stored products is being regarded with increasing interest since they are nontoxic and do not damage human health or the environment.

**Parasitoids :** Insects that parasitize or damage other insects and arthropods are most appropriately known as parasitoid. A parasitoid is parasitic in its immature stages but is free living as adult. In all instances, parasitoids kill their host, but in some circumstances, the host may live much of its full time before dying. Hymenoptera and Diptera are the most important parasitoid groups of insects among six parasitoid including order (Pedigo 1996) which play an important role in the management of storage pests. Askew (1971) stated that there are over one lakh species of parasitic hymenoptera, but (Kerrich 1960) reported that there are five lakh hymenopteran parasitoids. Kapil and Chowdhury (1973) described nine hymenopteran parasitoids for *T. granarius*. Parasitoids that have been assessed for the biological control of stored product moths include multiple species of egg parasitoids within the genus *Trichogramma* (Hymenoptera: Trichogrammatidae) (Brower 1990, Keever *et al.* 1986, Prozell and Scholler 1998, Steidle *et al.* 2001), the larval endoparasitoid *Venturia canescens* (Gravenhorst) (Hymenoptera: Ichneumonidae) (Press *et al.* 1982) and the larval ectoparasitoid *Habrobracon hebetor* (Say) (Hymenoptera: Braconidae) (Press *et al.* 1974, 1982, Krazpulski and Davis 1988, Brower 1990, Cline and Press 1990). The bethylid parasitoid *Plastanoxus westwoodi* (Kieffer) generally parasitized the larval and pupal stages of *C. pusillus* (Rahman 2006). The parasitoid *Theocolax elegans* (Westwood) reduced the population of *S. zaemais*, *T. castaneum* and *Cryptolestes* sp in a mixed infestation and synergistically produced better result with avidin maize powder in case of *T. castaneum* (Flinn *et al.* 2006). The parasitoid *Anisopteromalus calandrae* (How) attacks *Sitophilus* sp. *C. chinensis*, *O. surinamensis* and *R. dominica* (Mahal 2002), along with other species (Islam *et al.* 1985). *R. dominica* is parasitized in the larval and pupal stages by the parasitoids *Lariophagus distinguendus* and *Chaetosphila elegans* (Durrant 1921). Pteromalid parasitoids such as *A. calandrae*, *L. distinguendus* and *T. elegans* are expected to suppress population of *Sitophilus* sp. and *R. dominica* (Flinn 1998, Imamura *et al.* 2004, Steidle *et al.* 2000, Williams *et al.* 1971). Sixteen species of Hymenopteran parasitoids were collected from different localities in Greece (2002) on grain, tobacco and dried fruits; eight parasitoids attacked coleopteran hosts, six attacked

lepidopterans and two species attacked the both. According to Elipoulos *et al.* (2002) observed that *S. oryzae* and *R. domonica* were most frequently parasitized by *A. calandrae*, *H. sylvanidis*, *T. elegans*, *Venturia canescens*, *H. hebetor* and *C. tarsalis*; whereas, *Tribolium* spp., *Oryzaephilus* spp. and *Cryptolestes* spp. Were parasitized by *H. sylvanidis* and *C. tarsalis*. The authors also reported that *V. canescens* and *H. hevetor* preferred moth larvae the degree of dominant wasps were in decreasing order as, *H. sylvanidis*>, *A. calandrae*>, *Venturia canescens*> , *C. tarsalis*> *T. elegans*. Seven hymenopteran parasitoids belonging to families Pteromalidae, Braconidae, Bethylidae and Ichneumonidae were recorded from experimental culture of stored Bengal gram (*Cicer arietinum* L) and Masur (*Lens esculentus* L) in the BCSIR laboratories, Rajshahi, Bangladesh during 1982-1983. The parasitoids are *Dinarmus basalis* Rond., *A. calandrae*, *C. elegans*, *B. hebetor*, *Rhabdepyris* spp, *Holepyris* and *Diplazon* spp (Islam *et al.* 1985).

### **Predators**

According to De Back (1964) the potential biocontrol agents either a predator or any other organisms must have the adaptability to the different physical conditions of the stored ecosystem, high host searching capacity, high reproductive rate, high degree of host specificity, good synchronization with the host, maximum host consumption rate, ability to survive in host-free period, changes in behaviour in relation to the density and dispersal of host or its own population. Predatory insects feed on eggs, larvae or nymphs, pupae and adults of host (Khan and Selman 1996). Predators that attack stored product insect pests are typically very small or larger and have a short life cycle with high reproductive capacity as long as hosts available with suitable environmental conditions (Scholer and Flinn 2000). Natural enemies can be released at a single location of the store and they will find and attack pests located deep inside crevices or with grain mass, unlike chemical pesticides (Tyler *et al.* 1983) and insect pathogens (Fuxa 1993). As pest insects have not yet developed resistance to parasitoids and predators (Hokkamen *et al.* 1995), continuous research on the prey-predator relationship of different predator species are going on.

*X. flavipes* is commonly known as the warehouse pirate bug (Hemiptera, Anthocoridae) and is cosmopolitan in distribution (Henry 1988, Gross 1954), commonly reported from storage habitats (Jay *et al.* 1968) in association with its prey, Lepidoptera and Coleoptera (Arbogast 1978). Release of *X. flavipes* resulted in a 79-100% suppression of moth populations in small storages of peanuts, up to 99% reduction of saw-toothed grain beetle populations and 90-98% suppression of red flour beetles in a simulated peanut warehouse. According to a number of entomologists, *X. flavipes* is one of the most efficient predators, which can kill and consume many stored product insect pests (Table 1).

Table 1 Stored product insects prey of *X. flavipes*

| Order/Family       | Species                                | References                          |
|--------------------|--|-------------------------------------|
| <b>Coleoptera</b>  |  |                                     |
| Anobiidae          | <i>Lasioderma serricorne</i> (F.)      | Abdel-Rahman <i>et al.</i> 1978-79  |
| Bostrichidae       | <i>Rhyzopertha dominica</i> (F.)       | Abdel- Rahman <i>et al.</i> 1978-79 |
|                    | <i>Prostophanus truncatus</i> (Horn)   | Helbig 1999                         |
| Bruchidae          | <i>Acanthoscelides obtectus</i> (Say)  | Sing <i>et al.</i> 2008a            |
|                    | <i>Callosobruchus maculatus</i> (F.)   | Sing <i>et al.</i> 2008a            |
| Cucujidae          | <i>Cathartus quadricollis</i> (Guerin) | Press <i>et al.</i> 1979            |
|                    | <i>Cryptolestes minutus</i>            | Wen and Deng 1988                   |
|                    | <i>Cryptolestes pusillus</i> (Schon)   | Brower and Press 1992               |
| Curculionidae      | <i>Sitophilus orzae</i> (L.)           | Abdel-Rahman <i>et al.</i> 1978-79  |
|                    | <i>Sitophilus zeamais</i> (Motsch.)    | Wen and Deng 1988                   |
| Dermestidae        | <i>Anttagenus unicolor</i> (Brahm)     | Lecato 1976                         |
|                    | <i>Trogoderma granarium</i> Everts     | Arbogast 1978                       |
| Mycetophogidae     | <i>Typhaea stercorea</i> (L.)          | Brower and Press 1992               |
| Nitidulidae        | <i>Carpophilus dimidiatus</i> (F.)     | Brower and Press 1992               |
| Silvanidae         | <i>Oryzaephilus mercator</i> (Fauvel)  | Press <i>et al.</i> 1979            |
|                    | <i>Oryzaephilus surinamensis</i> (L.)  | Abdel-Rahman <i>et al.</i> 1978-79  |
|                    | <i>Ahasversus advena</i> (Waitl)       | Brower and Press 1992               |
| Tenebrionidae      | <i>Latheticus orzae</i> (Waterh)       | Tawfik <i>et al.</i> 1982           |
|                    | <i>Tribolium castaneum</i> (Herbst)    | Lecato 1976                         |
|                    | <i>Tribolium confusum</i> (Duval)      | Lecato 1976                         |
|                    | <i>Stegobium paniceum</i> (L.)         | Awadallah <i>et al.</i> 1986        |
|                    | <i>Polorus ratzeburgi</i>              | Wen and Deng 1988                   |
|                    | <i>Zabrotes subfasciatus</i> (B.)      | Sing <i>et al.</i> 2008a            |
| <b>Lepidoptera</b> |  |                                     |
| Gelechiidae        | <i>Sitotroga cerealella</i> (Olivier)  | Lecato and Arbogast 1979            |
| Pyralidae          | <i>Corcyra cephalonica</i> (Staint)    | Tawfik <i>et al.</i> 1982           |
|                    | <i>Cadra cautella</i> (Walker)         | Press <i>et al.</i> 1974            |
|                    | <i>Ephestia kuehniella</i> (Zeller)    | Abdel-Rahman <i>et al.</i> 1978-79  |
|                    | <i>Plodia interpunctella</i> (Hubner)  | Abdel-Rahman <i>et al.</i> 1978-79  |
|                    | <i>Galleria mellonella</i> (L.)        | Arbogast 1978                       |
| <b>Hymenoptera</b> |  |                                     |
| Braconidae         | <i>Bracon hebetor</i> Say              | Press <i>et al.</i> 1974            |

**Bacteria** : Microbial pesticides obtained from insect pathogens or their by-products are especially valuable biocontrol agent because their toxicity to non-target animals and human is extremely low compared to other commonly used insecticides, and are safe for both the pesticide user and consumers of the treated stored products or crops (Abd-El-Aziz 2011).

Currently, many entomopathogens were used for the control of invertebrate pests of agriculture, forestry and food storage (Subramanyam *et al.* 1999, 2002, Lacey *et al.* 2001, Fang *et al.* 2002a,b, Daghli *et al.* 2003, Khashaveh *et al.* 2008, Mahdeshin *et al.* 2009). Microbial agents are useful commercially only if they do not harm other natural organisms at recommended rate of use in the environment (Florence *et al.* 2003).

Among the entomopathogens bacteria is the most effective and dominant in microbial control of insects. *Bacillus thuringiensis* (Bt) is a bacterium when sprayed on or eaten by an insect host, infects the host making it sick and then causing it to die. Bt variety is very host specific and works only on the caterpillar stages of moths and butterflies and to some extents to flies. Another bacterium *Beuveria bassiana* is also found as potent biocontrol agent against the stored product insects. The effect of two microbial bacteria (*B. thuringiensis* and *B. bassiana*) and three plant extracts were studied on three stored product insects, *P. interpunctella*, *E. cautella* and *E. kuehniella*, the combined treatment with extracts *B. thuringiensis* caused significant enhancement of the pathogens, increasing the mortality in almost all insects (Sabbour 2003).

Recently discovered, Spinosad is a fermentation product of actinomycete bacteria, (*Saccharopolyspora spinosa* Mertz and Yao) which showed low mammalian, and avian toxicity, short environmental persistence and prescribed to use for control of stored product insect pests including *C. pusillus* and *R. dominica* (Subramanyam *et al.* 1999, 2002, Fang *et al.* 2002a,b, Daghli *et al.* 2003, Nayak *et al.* 2005, Bonjour *et al.* 2006, Hung *et al.* 2007, Athanassiou *et al.* 2008a, Vayias *et al.* 2010, Hertlein *et al.* 2011) in many integrated pest management programs, as, Spinosad is reported to kills insects relatively more quickly than other microbial pesticides (Bret *et al.* 1997).

**Discovery of Spinosad:** During the late 1950's, companies including The Dow Chemical Company and Eli Lilly and Company began to actively look for naturally occurring pest control products. As a result of these efforts, a scientist from the Natural Products division of Eli Lilly while vacationing in the Caribbean in 1982 visited abandoned rum still and collected several soil samples. These samples were taken to the laboratory to determine the presence of biological activity. Three years later the fermentation products from these samples were shown to have insecticidal activity, and by 1986 Eli Lilly's scientists identified a new actinomycete bacteria producing the biologically active substances, they named it *Saccharopolyspora spinosa*. Scientists identified the most highly active metabolites of *S. spinosa* in 1987. In 1995, because of its favorable environmental and toxicological profile, Spinosad was classified by the U.S. Environmental Protection Agency (EPA) as a reduced risk product and granted an accelerated registration review. During early 1997, the first Spinosad products, Tracer® and Conserve® were approved and launched in the U.S. for use on cotton, and on turf and ornamentals, respectively.

Now a day, *S. spinosa* colonies are grown using natural products such as soybean and cottonseed meal. Computers are used to control temperature, oxygen and nutrient levels to ensure maximum production of Spinosad. In Kenya, Spinosad was first registered for use as a grain protectant in 2003, registration in the United States was achieved in early 2005, with Spinosad's labeled use rate set at 1 ppm (1 mg ai/kg of grain), and its Maximum Residue Limit (MRL) or tolerance established at 1.5 ppm (Subramanyam 2006a,b, Hertlein *et al.* 2011). Spinosad is also currently registered for grain protection in a number of other countries, but widespread commercial launch has been deferred while awaiting final MRL or tolerance approvals in a few remaining key grain-importing countries (Hertlein *et al.* 2011).

**Application of Spinosad:** Spinosad's suitability as a stored grain protectant has been progressively highlighted in a series of scientific publications dating from 1999 (Subramanyam *et al.* 1999a, 2002, Fang *et al.* 2002a and Mutambuki *et al.* 2002).

Since then, Spinosad has been shown to provide highly effective and long-lasting control of important stored product pests on various grains (Toews and Subramanyam 2003, Nayak *et al.* 2005, Maier *et al.* 2006, Subramanyam 2006a, b, Huang and Subramanyam 2007, Huang *et al.* 2007, Subramanyam *et al.* 2007, Daghli *et al.* 2008, Athanassiou *et al.* 2008a,b, Chintzoglou *et al.* 2008a,b, Vayias *et al.* 2010a,b).

Spinosad effectively controls both the adults and immatures of same insect species, some other species are subjected to very high rate of mortality as larvae only. Spinosad also gradually reduce the overall population of many insect pests in storage and provide a satisfactory level of long control, and has already been proved as very effective against a range of stored-grain insect species, even at lower rates than the prescribed application rate, in both laboratories (Fang *et al.* 2002a, Toews and Subramanyam 2003, Nayak *et al.* 2005, Daghli and Nayak 2006) and field tests (Maier *et al.* 2006, Subramanyam *et al.* 2007, Daghli *et al.* 2008). A large number of stored product insect pests are controlled at 1 ppm concentration of Spinosad on various commodities which already were previously determined by many scientists are shown in Appendix table 1.

Toews and Subramanyam (2004) reported that Spinosad applied to stored wheat at 1 ppm was highly toxic to the parasitoids *H. hebetor*, *T. elegans*, and *A. calandria*, but no toxicity was found against *X. flavipes*; survival rate was 92% and the live bugs were able to reproduce under the treated same conditions. Results obtained from this laboratory study were subsequently supported by field bin trials conducted by Parker *et al.* (2004a, b) in stored sorghum and by Parker and Falconer (2004, 2005, 2006 and 2007) in stored corn, where they showed no survival of the parasitoid *A. calandria* and only limited survival of the parasitoid *C. elegans*, over a storage period 10 to 24 months. Long lasting grain protecting potentialities against different specific life stages of different stored product insect pests make Spinosad the best than other synthetic insecticides.



## **Background of the study**

Bangladesh is one of the major rice, wheat, maize and pulse growing country in the world, but large silos, granaries and warehouses are very limited in number. So, a large quantity of grains is stockpiled in small warehouses without following any scientific steps for keeping infestation away. In rural areas grain is still stored according to traditional indigenous methods and the same store or godown is used year after year without being properly cleaned. As a result, stores become quickly infested by insect pests. Warm and humid climate of the country provides more favourable environment for insect pests in storage. Moreover, food commodities are imported to this country almost throughout the year from many other countries, and new pests get the chance to enter the country. People have little knowledge about sanitation and contamination of insect pests in storage. For this cause, heavy loss of grain is occurred in storage situation.

During the storage of grains and cereals or milled products use of insecticide is limited. Even within this limited application scientific methods or processes are not followed, due to lack of proper knowledge, training and skill (Ferdous 2006). Chemical control, in spite of its so many demerits, has been the primary method of pest control in the past and is still in use. As mentioned earlier, pesticide use in Bangladesh started from mid-fifties and gained momentum in late 1960 (Alam 1991). Until 2000, 17 companies (national and international) were involved in pesticide formulation, repacking, distribution and supply through their own sales and distribution network in Bangladesh (Hasanuzzoha 2004).

It is important that the proper knowledge should be present about the toxicological, effects of pesticidal threshold and care (Ali 2004). Prevention of food losses during postharvest storage is of paramount economic importance. Integrated pest management is now a widely accepted strategy in pest control in pre-and systems. Fumigants are used in the food silos, granaries and warehouses, but in the small storages usually the chemical insecticides are used. The ban on methylbromide and phosphine would affect the insect management in this system. Though IPM programmes are running on in both public and private grain stores, but more efficient, safe, eco-friendly and cost-effective agents are needed to be searched out. So, the present work will be add some new methods into the IPM programmes to make it more convenient, cost effective, and safe food to the consumers.

### Objectives of the research

Entomologists, specially insect pest specialists are trying globally to solve the insect pest problems in storage. Many studies have been conducted in different parts of the world for mentioning the predatory abilities of various beneficial insects and for identifying the best bacterium to manage the store insect pests. Predacious bug, *X. flavipes* is a very potential biocontrol agent against the insect pests in storage (Arbogast 1976, 1978, Brower and Mullen 1990, Brower and Press 1992). The bacterium Spinosad obtained the registration for use in the grain stores of USA, Australia and Canada, and from the literature it was found that *X. flavipes* can survive and can produce offsprings in Spinosad treated medium (Towes and Subramanyum 2004). In this study *C. pusillus* and *R. dominica* as a model of external and internal feeder respectively were selected as they caused serious damage and infestation of important stored commodities like paddy, rice, whole wheat, wheat flour, maize, pulses, beans, maize, sorghum in Bangladesh (Alam 1971). Keeping these views in mind, this strategic plan was designed to accomplish this research by facilitating implementation of the potential of the predator, *X. flavipes* and bacterium, Spinosad in controlling the selected insect pests of stored product by treating separately and in combinedly. In this regard, the following specific observations were carried out.

- To detect the host-stage specific effects on biological parameters of *X. flavipes* on *C. pusillus* and *R. dominica*.
- To determine the effects of Spinosad on egg hatchability, 3<sup>rd</sup> instar larvae, pupae and adults of *C. pusillus*.
- To evaluate the effects of Spinosad on egg hatchability, 3<sup>rd</sup> instar larvae, pupae and adults of *R. dominica*
- To observe the effects of Spinosad on egg hatchability, 3<sup>rd</sup> instar nymphs, pupae and adults of *X. flavipes*.
- To find out the effects of *X. flavipes* and Spinosad on the population of *C. pusillus* and *R. dominica* separately and in combinedly.



## **Chapter 2**

### **Review of Literature**

### **Effects of environmental factors on insects**

Environmental factors such as temperature, moisture, humidity, air, light, sound etc. are naturally not remain constant and equal in every parts of the world and throughout the year. These factors can change the development, survivability, progeny production, abundance and behaviour of insects of stored products. Birch (1945a) showed variation in duration of developmental stages of *R. dominica* at different temperature in wheat containing 14% moisture. *R. dominica* can be developed and reproduced even in grain with low moisture content, at a level of 8% (Golebiowska 1969). Light may be of some use in luring flying insects to entrap (Banks and Fields 1995). A 5-min exposure to 1 MHz sounds at 14.5 W cm<sup>-2</sup> killed all stages of *S. granarius* at 26°C in wheat but commercial application is unexpected (Banks and Fields 1995). Arthur and Casada (2010) reported that suction aeration would be more beneficial than pressure aeration for controlling insect pest in wheat stored in the southern plains of the United States. Among the environmental factors temperature and humidity are usually the most influential abiotic factors affecting the population dynamics of insects in storage system (Flinn and Hagstrum 1990).

### **Temperature and humidity**

Insects are poikilothermic and its rate of development varied with temperature and humidity (Andrewartha and Birch 1954, Kitching 1977, Flinn and Hagstrum 1990). The optimum conditions of temperature and humidity for development of stored product pests are between 25-35°C and 50-70% (Howe 1965a, Haines 1991, Banks and Fields 1995, Fields and Muir 1996). A threshold for an adequate air temperature for aeration is 15°C which is the lower temperature limit of development for most stored product insect pests (Howe 1965a, Fields 1992). Burrel (1967) reported that cooling prevented further development of the heavy infestation but since the insects were not killed, this control method should be used as a preventive rather than a cure. Lowering the temperature of commodities to prevent spoilage is an ancient technology. Part of the success of the underground storages used in ancient Egypt compared with above ground stores was due to

cooler temperatures of the underground stores (Banks and Fields 1995). The effectiveness of aeration can be increased in tropical climates or in the summer in temperate climates by cooling the air with refrigeration units. Low temperature and humidity reduce the rates of development, feeding, fecundity and survivability (Longstaff and Evans 1983). Burks *et al.* (1999) reported that low temperature prevents emergence of unparasitized larvae of the rice weevil *S. oryzae* while not affecting emergence of parasitoid *A. calandrae*.

Laboratory studies on the population of a bruchid, *C. maculatus* and its parasitoid *D. basalis* have demonstrated that the fecundity, duration of adult life and developmental time depended on humidity (Owdraogo *et al.* 1996). Okamoto (1972) observed maximum number of progeny of *A. calandrae* emerged from its host, *C. chinensis* at 70% rh and also mentioned that *A. calandrae* completed its life cycle within short period on different developmental stages of *C. chinensis* at 70% rh. Cave and Gaylor (1988) noted that parasitoid development and progeny emergence were higher at 75% rh and also noted that the mean developmental time of *Telenomus reynoldsi* (Hymenoptera:seclionidae) decreased with increasing humidity. *A. calandrae* reared on *Sitophilus zeamais* at 75, 56 and 40% relative humidity and found that developmental time decreased slight but significantly when humidity increased (Smith 1993).

Temperature affected the suppression of *R. dominica* parasitized by *T. elegans*, the life span of the female adults of *R. dominica* decreased with increasing temperature, ranging between a mean value of 219 days at 20°C and 75 days at 35°C (Faroni and Garcia 1992). The developments of *R. dominica* was completed when relative humidity was 55% and above, but the development was inhibited when rh was less than 30% at any temperature (Longstaff 1999). At 30% rh life cycle of *R. dominica* required 30 to 40 days for completion (Potter 1935). Development of *R. dominica* was completed at temperature as low as 18°C (Long staff 1999), the population of *R. dominica* was peaked in July to September and lowest during December to March, when the average temperature was <15°C (Peng 1984). At 30°C temperature the life cycle of *R. dominica* required

30-40 days for completion (Potter 1935). Birch (1945a) reported that *R. dominica* is a high temperature tolerant insect and it develops from egg to adult in shortest time at 34°C. The larvae of *R. dominica* reared on whole meal flour required 29 days to complete their development at 26°C (Howe 1950). Wheat variety also affects development and reproduction of internal grain feeders. Almeida and Amorim (1994) studied the reproduction of *R. diminica* reared on whole and broken wheat grains (Variety OC 854 and IAC 5) at 30°C and 70% rh and found the fecundity was greater on variety OC 854 than on IAC 5 and longevity was greater on broken grain than on whole grain. Most of the larvae of *R. dominica* moult three times but a few larvae moulted four times before developing into pre pupa, pupa and adult, the total developmental time was 44 and 45 days at 26°C and 30°C temperature and 56% rh respectively Elek (1994). At both temperatures the first instar larval period was the longest and most variable and the least variable stages were none feeding egg, pre pupal and pupal stages.

Arbogast (1975) stated that the population growth of *X. flavipes* was greatly influenced by temperature and humidity. Development at 20°C was protracted and characterized by a large variance in the duration of the developmental period, the time required to reach the adult stage ranged from 44 to 74 days, but at temperature increase from 30 to 35°C produced no further change. Thus development was completed in 21-35 days at 25°C, 14-24 days at 30°C and 14-21 days at 35°C. Mortality among the immature stages was highest at 35°C, specially when the humidity was either very low or very high. In fact only 9% eggs were hatched at 35°C and 32% rh though most developed to the point that the red compound eyes of the nymphs were visible through the chorion. Of the 9 nymphs that hatched, 6 died during the intermediate moult, and 3 died before they reached the 2<sup>nd</sup> stadium. Mortality was also relatively high at 20°C when the rh was 35 or 65% and at 30°C when the rh was 96%. The life span and oviposition period were longest at 20°C, but the maximum rate of oviposition occurred at 25 and 30°C. The life span of adult females and the duration of the oviposition period decreased as temperature increased. Life span and oviposition period was shortened at the

temperatures by high humidity (96-98% rh) and usually at a lesser extent by low humidity (33-35% rh). Fecundity was adversely affected by low and high temperature, thus the values of (GRR) were lower at 20 and 35°C. Fecundity was also adversely affected by high humidity at all temperatures but low humidity apparently had an adverse affect only at 20°C.

Abdel-Rahman *et al.* (1977) reported that the optimum temperature for oviposition of *X. flavipes* was 25°C, the survivability rates of the eggs and the nymphs were increased at 35°C. Hatching and survival of *X. flavipes* nymphs were optimum at 25°C, the average number of eggs laid/female/days was found to increase by raising temperature. The eggs were hatched in between 2-7 days depending on temperature, (15 to 35°C), increase of temperature enhanced development of the adult stage of *X. flavipes*.

Faroni and Garcia (1992) observed the incubation period of *R. dominica* at 35, 32, 28, 24 and 18°C temperature respectively and recorded the period to be 6.5, 6.7, 8.7, 11.2, 22.8 and 27.6 days. The incubation period was considerably shorter in summer than in winter in Bangladesh (Alam 1971). Parajulee *et al.* (1995) reported that in case of the predator *L. campestris* 43% rh slightly lowered eclosion rates (70-79%) than the higher rh 58 and 75% respectively. Sex differentiation of the predator was not affected by relative humidity at 30°C (Parajulee and Phillips 1992, 1993).

Hashem (1989) reported the incubation period was 6.5 days at 30°C temperature. Optimal temperature for development of *S. oryzae* is generally in the range of 22°C to 27°C (Howe 1965a, Field 1992) and in controlled laboratory studies; results indicate greater reproduction in *S. oryzae* at 27°C versus 32°C (Arthur and Throne 2003) however the reverse was true for *R. dominica* (Vardeman *et al.* 2006).

Russo *et al.* (2004) reported that the egg survival rate of *X. flavipes* predating on *T. castaneum* was high at 24 and 32°C, and larvae survived longer than the first instar at 19°C. At 21°C the number of the larvae completing the immature stage was extremely low. Developmental time was significantly short at 32°C. Female lived longer but fecundity was greatly reduced at 21°C, and egg production was maximum at 32°C.

The adult *X. flavipes* survived no more than 4-5 days at 19 to 32°C. The developmental time from first instar to adult decreased with the increasing temperature, at 32°C it was 13.7 days.

Khan *et al.* (2004) reported that high temperature (studied temperature 20, 25, 30 and 35°C) shorten the developmental periods and increased the adults eclosion and progeny productions of the pulse beetle *C. chinensis*. The sex -ratio was distorted at higher temperature, but the reproductive potential and percent of fertility of the females were increased. Temperature range 25-30°C has been proved to be the optimum for the development of pulse beetle.

Hasen *et al.* (2004) observed that in pest *S. cerealella* maximum fecundity (124 eggs per female) was obtained at 20°C and 80% rh; and immature survivorship was highest at 80% rh and lowest at 44% rh; and minimum developmental time required at 80% rh at 32°C.

Rees (2004) reported that shortest developmental period of *C. pusillus* is 22 days at 35°C and 90% rh and breeding takes place at 17.5-37.5°C and >50% rh where as the shortes developmental period of *C. pusillus* is 21 days at 35°C and 90% rh breeding takes place at 20-42.5°C and 40-90% rh. Some strains of *C. ferrugineus*, *C. capensis* and *C. turcicus* are highly cold tolerant and able to survive an extended period at or below 0°C temperature. *C. ferrugineus* and *C. capensis* are able to breed under dried conditions than other species. In warmer regions of the world *C. ferrugineus* is frequently found with *C. pusillus*.

Rahman (2006) reported that the life history parameters of *X. flavipes* on *C. pusillus* showed optimum values at 25 and 30°C and 70 and 90% rh. In another study, Rahman *et al.* (2007) observed the effect of temperature on the predator *X. flavipes* feeding on *C. pusillus* and recorded that highest number of eggs laid/female ( $27.27 \pm 2.52$ ) and egg hatching rate ( $88.25 \pm 2.19\%$ ) at 30°C, and the respective lowest value were  $5.43 \pm 1.19$  and  $30.79 \pm 4.63\%$  at 20°C respectively, no eggs were laid at 15°C. Mortality among immature stages was highest ( $51.71 \pm 1.48\%$ ) at 35°C and were lowest ( $24.25 \pm 1.14$ ) at 25°C. Developmental



times decreased with the increased temperature. The sex rates (% female) of *X. flavipes* were 47.04, 56.68, 51.66 and 50.07 for 20, 25, 30 and 35°C respectively, survivorship of ovipositing females was highest at 25°C but lowest at 35°C. Rahman and Islam (2007) observed different parameters of life cycle of *C. pusillus* at 30±1°C and found that oviposition rate, hatching rate, adult emergence and longevity of male and female were 4.89±0.35 egg/female/day, 91.22±1.02%, 88.44%, 156.11±1.37 day and 169.67±2.52 days respectively. *C. pusillus* like warmest areas within the grain bulk and move to the center during fall and winter (Flinn and Hagstrum 1998).

Ferdous *et al.* (2009) observed some biological parameters of *X. flavipes* feeding on *T. castaneum* at 30±1°C temperatures in the laboratory and found the mean duration of developmental period through the five nymphal instars was 20.09 days. The mean incubation and nymphal periods were 3.5 and 16.57 days respectively. The percentage of adult emergence was 68.89 and the number of eggs laid per female per day ranged from 4.38 to 4.39. The mean life span was 6.6 days in males and 20.67 days in females.

Both temperature and relative humidity considerably affect the duration of nymphal stage, longevity and oviposition of *X. flavipes* (Abdel-Rahman *et al.* 1977 and Arbogast 1978). Arbogast *et al.* (1971) and Awadullah and Tawfik (1973) reported that the number of nymphal instars of *X. flavipes* varied from 2-6, but at 30°C there was always five instars. Preying on *P. interpunctela* at 30°C the life cycle of the predator was completed from 14-21 days (Arbogast 1975). At this temperature the incubation period was 4-5 days (Awadullah and Tawfik 1973, Arbogast 1975, 1978). Feeding on *T. castaneum* the longevity of the male and female predator was 5-43 and 8-37 days respectively, at 30°C (Awadullah and Tawfik 1973).

Not only the prey species, but also the diet of the prey insect affected the biology of *X. flavipes*, which was coordinated with temperature and relative humidity (Saha 2007). Optimum developmental temperature was recorded as 30°C and 70% rh when the prey species (*T. castaneum* and *T. confusum*) were reared on agar+flour; the oviposition period was also recorded the maximum at this temperature

rearing on the same prey species feeding the same food. Whereas, mortality (%) of immature stages was recorded at 25°C and maximum mortality was observed at 35°C and 30% rh when the prey were reared on yeast+flour.

Yousefnezhad-Irani and Asghar (2007) evaluated toxicity of Spinosad on adults *T. castaneum* and *S. oryzae* at different temperatures and exposure intervals. A commercial formulation of Spinosad, Tracer was used against 7-14d old adults of *T. castaneum* and *S. oryzae*, at 24, 28 and 32°C and 65±5% RH. Mortality was recorded at 24, 48 and 72h post treatment. A dose dependent response was observed in both species. Similar trend was detected between mortality and time intervals. In both species an inverse relationship between LD<sub>50</sub> values and temperature was detected. Based on LD<sub>50</sub> values and none overlapping of 95% CL *S. oryzae* was more susceptible to Spinosad than *T. castaneum*.

Efficacy of Spinosad against *R. dominica* was not affected by temperature and moisture, during a maximum storage period of four months Fang and Subramanyam (2003). Two field studies provide data on residue levels and efficacy against *R. dominica* on wheat stored on farm in the Midwest of the USA. In one field study, efficacy and residues of Spinosad were found to be stable during 12 months of storage with a grain temperature range from -10 to 32°C and a moisture range from 12.4 to 23% MC (Fang *et al.* 2002a). In the second field study grain temperature ranged from <10 to 35°C and moisture ranged from 10.7 to 22.0% MC, but Spinosad efficacy did not change despite reduces falling by about 19% during 6 months of storage (Flinn *et al.* 2004).

Daglish *et al.* (2006) reported Spinosad applied at 0.5 and 1mg/kg against *R. dominica* was completely effective for 9 months at both 55 and 70% relative humidity with 100% adult mortality after 14 days of exposure and no live F<sub>1</sub> adults were produced. Athanassiou *et al.* (2008 a,b,c) tested the efficacy of Spinosad against adults *R. dominica*, *S. oryzae*, *T. confusum* on wheat and *P. truncatus* on maize at three temperatures 20, 25 and 30°C and two relative humidity levels 55 and 75%. The author recorded mortality of *R. dominica* and *S. oryzae* was high even at 0.01 ppm of Spinosad, reaching 100% at 55% relative humidity and 30°C

after 21 days of exposure. In several conditions tested Spinosad efficacy notably varied according to the temperature and humidity regimes. At 1 ppm, after 7 days of exposure mortality was low <14% but two weeks later >90% of the exposed adults were dead at 30°C. At this exposure, the increase of temperature increased mortality, while no significant differences noted between the two relative humidity levels tested (Athanassiou *et al.* 2008 a,b,c).

### **Biology of *C. pusillus***

Mated female of *C. pusillus* deposits her eggs in crevices in the grain or in loose farinaceous materials. Eggs are small, slender and cylindrical, a typical egg is about 0.56 mm in length and 0.16 mm in width. The egg appears shiny white when first deposited but as development proceeds, it becomes pale yellowish. The incubation period lasts for 3-4 days.

The neonates are Cigar-shaped about 0.7 mm in length, yellowish-white in colour (Alam 1991). There are seven abdominal segments which are uniform in size, a longer eighth segment and the ninth segment which bears the anal hooks. The head and the spine like appendages are reddish brown; eyes are oval, each with three elongated bristles on the inner side. The 1<sup>st</sup> instar larva is active, restless and moves forward by contracting and expanding its body. The 2<sup>nd</sup> and 3<sup>rd</sup> instar larvae are same as the 1<sup>st</sup> instars larvae but the body becomes more elongate in shape. The head is wider than the rest of the body in the first instar, but then becomes narrower than the rest of the body in the later instars. After the first instar, there is a pair of lateral setae on the abdominal segments 1-7.

The mature 4<sup>th</sup> instar larva is about 3-4 mm in length and 0.33 mm in width, the body is milky white except the head and anal region which appear brownish. Two pale brownish longitudinal lines precede mid-dorsally starting from 1<sup>st</sup> thoracic segment ending at the 7<sup>th</sup> abdominal segment. Antennae three jointed, tip of each has an elongated hair and two short bristles. Mouth parts are distinct.

The mature 4<sup>th</sup> instar larva enters a pre-pupae stage, where the body becomes broader and silk glands forms on the prothorax. These glands are used to spin the silk cocoon in which pupation occurs (CABI Crop Protection Compendium 2008).

The pupal stage occurs within a silken cocoon. The cocoon remains attached to the larval food, and food particles may adhere to the surface of the cocoon. The pupa is of the exarate form, in which the legs and wings are free from the body and the abdomen is movable. The newly formed pupa is white, but becomes darker with age. The pupal cocoon is slightly longer than the mature larva (CABI Crop Protection Compendium 2008). Six elongated hairs at the frontal regions and brownish circular eyes are present. The male pupa is smaller in size (1.57 mm in length) and is devoid of the finger-like lobes but female pupa is larger (1.75 mm in length) having characteristic finger-like lobe, the gonapophyses. The pupal stage lasts for 4-5 days. The freshly formed pupa is light yellowish which gradually turns to pale reddish before adult emergence.

Newly emerged adults are minute, flattened, oblong and light-brown in colour, but rapidly become reddish-brown. The body is about 1.5-2 mm long, depressed and elongate. Tarsi are five-segmented, except for the male hind tarsi which are four-segmented. However, as the basal segment is rather small, it may be only possible to count 4 segments on each tarsus or 3 on the male hind tarsus. The female antennae are about half the length of the body, while in the male they are about two thirds of the length of the body. Elytra have five parallel ridges. The biology of *C. pusillus* was observed at  $30\pm 1^{\circ}\text{C}$  temperature and  $70\pm 5\%$  relative humidity (Ahmed *et al.* 1994).

**Sex differences:** Male and female adults of *C. pusillus* can be identified by genitalia dissection under the microscope, the male genitalia is two banned accessory sclerites, curved shaped which middle is expand and both ends are gradually pin like and about 0.08 mm in size; whereas female genitalia is two closed banned accessory sclerites, long tube shaped which one end is spiracle and other end is open and about 0.125 mm in size with sclerotised part of burse (Figure -3) (Andras Szito 2011).

**Biology of *R. dominica***

Mated female of *R. dominica* laid eggs singly or a raft or cluster among the frass or only on the food medium. The frass consists of half chewed or cutting food materials which are produced by *R. dominica*. The egg is opaque, whitish in colour with a waxy appearance when freshly laid, but after a little while takes on a pinkish colour (Kucerova and Stejskal 2008). The egg is about 0.5-0.6 mm in length and 0.2-0.25 mm in diameter (Thompson 1966, LeCato and Flaherty 1974 and Kucerova and Stejskal 2008). The average weight of 10 eggs was determined as  $3 \times 10$  to  $6 \times 10$  mg. The egg surface appears smooth, but scanning electron micrograph (SEM) magnification reveals a distinct granulated microstructure. The chorion, which has two layers, is about 2.7  $\mu\text{m}$  in thickness (Kucerova and Stejskal 2008). The dark rusty tips of the mandibles and the abdominal thorn of the larva are visible through the chorion at the end of egg development (Kucerova and Stejskal 2008).

The mean daily oviposition rate is 10.4 eggs/day with a range of 4-15 eggs when the beetles are reared at 25°C and 70% rh (Howe 1950), the rate was somewhat lower, 6.5 eggs/day, for beetles reared at 29°C and 75% rh (Thompson 1966). The maximum number of eggs laid by female *R. dominica* in a day varies between 33 (Thompson 1966) and 45 eggs (Howe 1950). The pre-oviposition period was found to vary from 6 days (Thompson 1966) to 15 days (Schwardt 1933), and the oviposition period varies from 43 days at 25°C and 70% rh (Howe 1950) to 4 months at 34°C and 70% rh (Birch 1945 b,c).

The first instar larva is campodeiform, white or light yellowish in colour, with mandibulate mouthparts about 0.78 mm long and 0.13 mm wide across the head capsule (Potter 1935). The larva is very active, and moves rapidly about the grains (Winterbottom 1922). A terminal median spine is present in the first instar, (Potter 1935 and Howe 1950) has a short antennae beset with hairs. Thorax was three segmented and abdomen ten segmented. A number of long hairs were present dorsally and laterally on the abdominal segments. The larva often moved with a looping action. The duration of first instar larva was about 6 to 12 day. The 2<sup>nd</sup> instar larva loses the dorsal median spine at the posterior region of the body.

The second instar is similar in shape to the first instar, but larger in size (Winterbottom 1922), being about 1.1 mm long, and 0.17 mm across the head capsule (Potter 1935). The thoracic region is more differentiated from the abdominal region; the last abdominal segment was horse shoe shaped, the two ends of the horse shoe slightly protuberated. The second instar larva lasts for 4-7days.

Third instar larva is recurved but they are able to straighten out. The thorax is somewhat larger in circumference than the abdomen, prothorax markedly enlarged. End of the abdominal segment showed a well-marked anal furrow. In its natural recurved state it has distinct lateral hypoplueral folds. Ventral surface of the body is flattened. The average body length and diameter of the head capsule of the third instar are 2.04 and 0.26 mm, respectively (Potter 1935). The third instars larva moults after 4-6days.

Head of the fourth instar larva is retracted into the thorax and longer than width, antennae are present at the sides of the head. The body is recurved with distinct pleural folds on the sides of the flattened ventral surface. Regularly arranged short hairs are present on body surface. Fifth to eighth segments of the body are much extended. The legs of pro-meso- and meta thoracic segments are equal in size; each leg is three segmented highly curved brown claw. Ventral region is whitish, head is light brown, and mandibles are dark-brown or nearly black (Chittenden 1911 and Winterbottom 1922). Length of the mature fourth instar is approximately 3.2 mm and the head is approximately 0.41 mm in diameter. The fourth instars larva lasts for 4-8 days.

The pre-pupal stage does not involve moulting and can be distinguished from the mature larvae by their more elongated cylindrical shape and extended head as if forced out by the pressure of the fluid in the body (Potter 1935). It is a non-feeding stage, relatively immobile, but is capable of limited wriggling. The average body length is 3.15 mm and diameter of the head capsule is 0.5 mm. The duration of the prepupal stage is very short, lasting about 1½ days. The pupae of *R. dominica* are exarate, i.e., the appendages are not fixed to the body. They are inactive, and body movement is limited to the abdominal segments. Young pupae are whitish in colour, later, brown pigment is laid down in the eye and mouthparts (Winterbottom 1922). Average lengths of the body and head capsule are 3.9 and 0.6 mm respectively. The rate of pupal development is proportional to temperature. At 70% rh, the pupal stage is completed in about 8 days at 25°C and 5-6 days at 28°C (Howe 1950). The optimum conditions for rapid development of the pupal stage are 34 °C and 70% rh in wheat kernels of 14% moisture content (Birch 1953, Birch 1945a,b,c); under these conditions, development of the pupa is completed in 4 days. The pupa exhibits the characteristic depressed head and enlarged thorax of the adult. The pupa lies in a cell excavated by the larva inside the grain. However, a pupal cell is not required for successful completion of the pupal stage (Schwardt 1933). If larvae are reared on flour, pupation occurs in an oval-shaped cavity hollowed out by the larva in the floury material (Winterbottom 1922).

During the pupal stage, it is possible to distinguish between the sexes. Sexual dimorphism is displayed at the tip of the abdomen. The genitalia of the females are divergent, three-segmented, and protuberant, whereas those of the males are convergent, two-segmented, and protuberant (Potter 1935 and Halstead 1963).

The newly formed adults emerge from the kernel by chewing through the outer grain layer and might go without food for about 3-5 days after emergence (Schwardt 1933). The adult beetle is 2-3 mm long and 0.8-1.0 mm in wide. Fresh body weight ranges from 0.99 to 1.38 mg, with a mean about 1.20 mg (Edde and Phillips 2006b). The insect is reddish-brown to dark brown in colour. The anterior margin of the dome-shaped thorax is crenulate, the surface of the thorax and the elytra are pitted. The pits on the elytra are arranged in 10-11 longitudinal punctures, giving them a striated appearance (Winterbottom 1922, Beiriger and Sites 1996). The pits become smaller toward the posterior of the abdomen. Each elytron has short setae that curve backward (Beiriger and Sites 1996). The elytra are slightly convex and there are no carinae or other protuberances to the declivity. The antenna is short, ten-segmented, and has a terminal three-jointed loose club (Chittenden 1911 and Chujo 1958).

Mean longevity of adult male and female *R. dominica* fed on wheat kernels at 28°C and 65% rh is 26 and 17 weeks respectively, about 4% of the male and 3% of female beetles tested in study lived for approximately 52 weeks (Edde and Phillips 2006b). Birch (1953) found that female *R. dominica* reared at 32.3°C and 70% rh on wheat kernels lived for 17.2 weeks on the average. However, mean longevity of male beetles in Birch's experiment was 20 weeks, which is 6 weeks shorter than observed by Edde and Phillips (2006b). This difference may relate to the fact that Birch kept males and females together while Edde and Phillips kept them separately. The extra resources spent in courtship may have shortened the lifespan of the male beetles in Birch (1953). Mean longevity values of starved adult male and female were 5.7 and 4.7 days, respectively (Edde and Phillips 2006b). Negative effects on reproduction and movement of adult *R. dominica* may occur



after 4 days of starvation (Daglish 2006 and Nguyen *et al.* 2008). The effects of starvation are more pronounced on female *R. dominica*, presumably due to the greater energy demand on them for reproduction (Nguyen *et al.* 2008).

**Sex differences:** Adults of both sexes can be reliably separated by using the methods of Crombie (1941). Working under a dissecting microscope, the last three ventral abdominal segments of a live or freshly killed specimen can be gently squeezed until the tips of the genitalia appear. Often, squeezing may not be necessary for sexing female *R. dominica* because the tips of female genitalia are slightly extruded and easily discernible (Halstead 1963). In order to reduce mortality caused by squeezing, the insect can be sexed at the immature stage using the sexual dimorphism as described above for the pupal stage. A major setback to sexing the pupae is that it is found within whole grain kernels, making the collection for sexing difficult. This problem could be minimized by rearing the pupae on ground media of particle size between 1.4 and 2.0 mm diameter, which allows pupae to be removed from the medium easily, get sexed, and held for adult emergence (Cline 1973, Longstaff and Starick 1989). For males pupae, the genital papillae are convergent, 2- segmented and not protuberant while they are divergent, 3-segmented and protuberant while they are in females (Figure 4) (Potter 1933, Halstead 1963)

### **Biology of *X. flavipes***

Mated female of *X. flavipes* lays eggs on the food medium, scattered loosely throughout the habitat. Eggs are translucent, milky, elongate-oval and blackish with yellow spots. The egg ranged from 0.55 mm in length, the posterior end is broader than the anterior end. The anterior end is capped by a nearly circular operculum surrounded by an expanded rim of chorion. As eggs develop, they acquire a pale brownish colour. The egg hatches in 4-6 days at  $30\pm 0.5^{\circ}\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity.

Descriptions of the various life stages of *X. flavipes* is provided by Arbogast *et al* (1971) and Awadallah and Tawfik (1972). The nymph emerges by forcing open the operculum which usually remains attached to the shell by the embryonic cuticle. The 1<sup>st</sup> instar nymph looks pale brownish-yellow, lightly pigmented, with reddish eyes, antennae and legs. The nymph is about 0.60 mm in length and 0.09 mm in head capsule width. The nymph becomes large in size after the first moult and wings are visible. The developing ocelli appear after the second moult as small orange-red spots. Extensive black colouration first appears in the fourth instar, which is darker in the fifth. Fifth instar nymphs are dark brownish-yellow coloured with black tings on head and thorax. Black spots are present on the abdomen, wing pads are developed and extended up to metathorax. The 5<sup>th</sup> instar mature nymphs are about 1.50 mm in length and 0.25 mm in width. The mature nymphs are more predaceous than the immature nymphs.

The most sharply pronounced modifications are concentrated in the last moult of the 5<sup>th</sup> instars nymph to the adult. The adults are shining brownish black with irregularly distributed pale setae. The rostrum, antennae and legs appeared to be brownish yellow. Pronotum is slightly convex, sautellum is raised anteriorly and antennae are four segmented. Setae present on the third and fourth segments of the antennae.

**Sex differences:** Sexes of the adults are distinguished by the shape of the abdomen. The abdomen is bilaterally symmetrical in females, and in males it is notched on the left side of segments 8 and 9. The aedeagus of male arises within

the 9<sup>th</sup> segment and is directed to the left (Arbogast 1978). The piercing aedeagus of a male and abdomen of mated female of *X. flavipes* are shown in figure 5 (Backhouse *et al.* 2012). The females are larger than the males. Total developmental periods from egg to adult emergence of *X. flavipes* are 14-18 days. Both brachypterous and macropterous forms occur in *X. flavipes*, although the short-winged form was found to be most common in a sampled population (Arbogast 1978).

### **Managenemts techniques of *C. pusillus* and *R. dominica***

Insect identification programs can indicate the presence and abundance of particular species (Vela- Coffier *et al.* 1987, Reed *et al.* 1991 and Hagstrum 1998) and can reduce the illegal use of pesticides. In general, losses can be minimized when infestations are quickly identified and appropriate control measures implemented

(Abd-El-Aziz 2011). Many techniques are conducted from the beginning to still now for identification of insect pests in pre and post-harvest cereals and other commodities in storage and fields by many scientists viz., Burkholder and Ma 1985, Campbell *et al.* 2002, Loschiavo and Atkinson 1967, Loschiavo and Smith 1986, Lippert and Hagstrum 1987, Vela Coffier *et al.* 1997, Wakefield and Cogan 1999, Towes *et al.* 2005 Flinn *et al.* 2007, Schatzki and Fine 1988, Shumon *et al.* 1996, Panford 1987, Atui 2006, Magan and Evans 2000, Flinn *et al.* 2009 and recently, Computer based pest management (Abd El Aziz 2011) are used to identify the presence and manage the population of insect species in storages.

### ***Cryptolestes pusillus***

There have been several field trials (Reed and Harner 1998a, b, Casada *et al.* 2002, Arthur and Casada 2005) and modeling simulation studies (Flinn *et al.* 1997, Arthur and Flinn 2000) showing that an initial summer cooling cycle cooling to a level of about 24°C, followed by second cooling to 15°C in early autumn, severely limits population growth of stored product insects including *C. pusillus* in stored wheat.

Oliveira *et al.* (2003) reported that the biocontrol potential of the mite species *Acarophenax lacunatus* was able to parasitize eggs of *C. ferrugineus*. The mite caused significant reduction of 26% in the larval populations of *C. ferrugineus*. *A. lacunatus* can occur on colonies of *C. ferrugineus* (Cross and Krantz 1964, Faroni 1992).

Rahman (2006) observed bionomics of *Plastanoxus westwoodi* (Kieffer) on *C. pusillus* in the laboratory and reported that larval and pupal stages of *C. pusillus* are generally parasitized by beythylid parasitoid *P. westwoodi*. Fifty mated female of *P. westwoodi* suppressed the population of *C. pusillus* up to 81.31±4.54%. This parasitoid can be used as biocontrol agent of *C. pusillus* for easy handling, inexpensive culture techniques and their optimum progeny production. Female parasitoids are more active to suppress *C. pusillus* than male.

Effectiveness of aeration for controlling insect pest populations including *Cryptolestes* spp. in wheat during the summer months in the central and southern plains of the United States had reported (Reed and Harner 1998a, b, Arthur and

Casada 2005) and in rice stored in Arkansas (Ranali *et al.* 2002) and in eastern Texas (Arthur *et al.* 2008).

Arthur *et al.* (2010) conducted field trials in metal wheat storage bins to determine whether pressure aeration, pushing ambient air from the bottom or suction aeration, pulling air down from the top would be more effective at cooling the wheat mass and thereby limiting insect population growth. Aeration was accomplished at an approximate air flow of 0.22 to 0.31 m<sup>3</sup>/min/t and was done by adjusting thermostatic controllers to operate the aeration fans when ambient temperatures fell below specified thresholds. Summer and autumn cooling cycles using suction aeration cooled the warmest part of the bin, the top of the grain mass always remained warmer than with suction aeration. This cooling effect was most pronounced in the upper surface of the grain mass and insect pest populations as measured by pith fall traps were consistently less in bins with suction versus pressure aeration. Results seem to indicate that suction aeration would be more beneficial than pressure aeration for controlling insect pests including *C. pusillus* in wheat stored in the southern plains of the United States.

### ***Rhyzopertha dominica***

The mite species *Acarophenax lacunatus* showed highest rate of parasitism on the egg of *R. dominica* and *T. castaneum*, leading to a significant decrease of populations of both species, and also reduced wheat weight loss (Cross and Krantz 1964) at 28±2°C temperature and 65±5% relative humidity for 40 days (Oliveira *et al.* 2003). The mite caused a significant reduction of 61% in the larval population of *R. dominica*; Faroni (1992) and Faroni *et al.* (2000, 2001) stated that *A. lacunatus* is a potential biocontrol agent to regulate *R. dominica*.

Biocontrol agent used against stored grain insects will have to interact with insecticides used as grain protectants due to their heavy use especially in tropical areas. Therefore, the interaction between the pyrethroid insecticides bifenthrin and deltamethrin and *A. lacunatus* was assessed against *R. dominica* in a range of mite densities and insecticide doses for each compound. Despite the mite species presence on all insecticide doses, the lowest instantaneous rate of increase of

*A. lacunatus* was recorded with the highest doses of insecticides. The presence of the biological control agent at all doses of both insecticides suggests its tolerance to these compounds, which is a positive point for IPM programs. The biology of *A. lacunatus* and its potential as regulatory agent of population of *R. dominica* were reported by Faroni *et al.* (2000, 2001). There are reports of resistance to organophosphates and the pyrethroid deltamethrin in Brazilian populations of *R. dominica* (Guedes *et al.* 1996, 1997, Lorini and Galley 1999, 2000).

Mahal *et al.* (2005) observed potentiality of *A. calandrae* in controlling residual populations of *R. dominica* in wheat grain in bulk at 46 m<sup>2</sup> room and found that 50 pairs of *A. calandrae* suppressed 83% of *R. dominica* in June to July and 74% in August- September.

The interaction between *A. lacunatus* and *A. calandrae* may be the promising tool for the integrated pest management of *R. dominica* (Goncalves *et al.* 2006) The use of *A. calandrae* alone demonstrated a low instantaneous rate of increase of *R. dominica* and a high protection of the wheat grains during 60 days storage. The association of *A. calandrae* with *A. lacunatus* led to the lowest number of immatures of *R. dominica*.

Chanbang *et al.* (2007) conducted laboratory trials to determine the effectiveness of diatomaceous earth (DE) against *R. dominica* on rough rice stored for eight weeks. DE products (Two) were equitoxic to pest insect. Mortality increased from 15.8 to 69.2% depending on the exposure interval. There was extensive progeny production in all treatments (including controls) and more progeny were produced at 32 than at 27°C. Results showed that the two DE products did not completely suppress *R. dominica* on rough rice and combination treatments with another insecticide may be necessary to give complete control.

Efficacy of DE generally declines with increased relative humidity or grain moisture content and although mortality generally increases with temperature, mixed results have been reported for specific insect species and DE products (Arthur 2000, Fields and Korunic 2000, Vayias and Athanassiou 2004, Athanassiou *et al.* 2005). Other studies have repeatedly noted variation in

mortality of *R. dominica* and other stored grain insects exposed to commercial DE formulations, depending on grain type (Subramanyam *et al.* 1994, Arthur and Throne 2003, Arthur 2004, Athanassiou and Kavallieratos 2005). Tests with newer formulations of DE also show efficacy toward *R. dominica* on stored wheat (Kavallieratos *et al.* 2005, Athanassiou and Kavallieratos 2005), and the research is still going on.

The natural enemy of the stored product insects, *C. elegans* was found to be very effective for suppressing *R. dominica* populations with augmentative release (Flinn *et al.* 1994, 1996). Flinn *et al.* (1996) observed 98 and 91% suppression of *R. dominica* compared to the control by *C. elagans* in 1993 and 1994 respectively.

Spinosad remained effective against house flies as well as against its cyclodiene resistant strain (Scott 1998, Scott *et al.* 2000), *R. dominica*, *S. oryzae* (Toews and Subramanyam 2003), *O surinamensis* (Fang *et al.* 2002). *R. dominica* is a leading pest species, which has developed resistance to several registered grain protectants over the years (Champ and Dyte 1976, Herron 1990, Collins *et al.* 1993, Zettler and Cuperus 1990, Collins 1998). Malathion resistant *R. dominica* strains are common in Australia and these insects are also cross-resistant to the organophosphorous compounds. Most of the results revealed that Spinosad was very effective *R. dominica* with an application rate 1mg/kg achieving complete control of all strains of this species (Fang *et al.* 2002a, b, Fang and Subramanyam 2003, Toews and Subramanyam 2003, Nayak *et al.* 2005).

### **Predatory abilities of *X. flavipes***

This predacious bug is considered to be a promising polyphagous candidate for biological control programmes as it has some advantageous characteristics. The minimum prey requirement for complete development is low. A high proportion of nymphae (33%) developed to adulthood with a food supply of only one larva per week (Lecato and Collins 1976). The predator is supposed to be easy to handle, because it uses cannibalism as its strategy for survival in times without prey. Arbogast (1978) found that the first nymphal stage is necessary prey for nymphae and adults in order to achieve complete development. However these

survival strategies are very important for this insect since it can only survive for a very short time without food (Arbogast *et al.* 1977). After a starvation period of 5 days, 95% of adult *X. flavipes* were dead. Brower and Press (1992) reported that the hemipteran predators suppressed 70-100% stored product pest population in the laboratory condition. Predatory hemipteran may invade prey both as immature and adults (Pedigo 1996). *X. flavipes* has shown promise as an effective biological control agent by suppressive growth of stored product insects in small (Jay *et al.* 1968) as well as moderate (Press *et al.* 1975, Arbogast 1976) volumes of commodities. Arbogast (1978) stated that *X. flavipes* has a high capacity to increase in number relative to its prey. Lecato and Collins (1976) mentioned that *X. flavipes* destroys large quantities of prey when prey is abundant. Awadallah *et al.* (1986) reported that *X. flavipes* when preyed only on the larvae of different pest insects, the predator fed on 105 larvae of *Corcyra cephalonica*, 112 larvae of *T. confusum*, 30 larvae of *Stegobium panicerum*, 148 larvae of *Lasioderma serricorni*, during 43 days of life span.

*X. flavipes* had been reported to suppress effectively the population of a number of direct grain feeders and also an efficient predator on different secondary feeders (Arbogast 1978 and Helbig 1999). *X. flavipes* efficiently predate on both coleopteran and lepidopteron pests (Arbogast 1975, Abdel Rahman *et al.* 1978-79, Brower and Mullen 1990, Jay *et al.* 1968, Lecato and Arbogast 1979, Lecato *et al.* 1977). *X. flavipes* developed faster, lived longer as an adult, survived better in the immature stages and laid more eggs when fed coleopteran larvae rather than lepidopteran larvae (Abdel Rahman *et al.* 1978-79). Ahmed *et al.* (2004) reported that a female *X. flavipes* killed  $47.3 \pm 4.88$  larvae of *C. pusillus* and laid  $20.1 \pm 1.66$  eggs during her life time ( $25.4 \pm 1.26$  days).

Arbogast (1976) reported that the Sawtoothed grain beetle *O. surinamensis* population growth reduced 95% (after 16 weeks) when only 5 pairs of *X. flavipes* were introduced. Press *et al.* (1975) observed that *X. flavipes* effectively suppressed *T. castaneum* on 6-bu (ca, 227 liter) lots of farmers stock of peanuts contained in 64 cu-ft (ca 1812 liter) bins. *X. flavipes* suppressed about 97%



population of almond moth, *Cadra cautella* (Press 1989), and 90.4% population of *C. pusillus*, when only 50 pairs of *X. flavipes* were introduced (Brower and Press 1992).

Ishijima *et al.* (2005) studied the suppression effects of two predatory bugs, *X. flavipes* and *Joppeicus paradoxus* on the stored product insect *T. confusum* on whole wheat flour and found that the predators reduced 33% population of *T. confusum* after 25 days.

Lecato and Davis (1973) observed and reported that early and late instar nymphs and adult *X. flavipes* when exposed simultaneously to early or late instar larvae of the Indian meal moth, *P. interpunctella*, the red flour beetle, *T. castaneum*, the sawtoothed grain beetle, *O. surinamensis* and the Cigarette beetle, *L. serricornis*. *X. flavipes* preyed on early and late instars of all species but the number killed depended partly on the size of the prey and source other factors. Press *et al.* (1973) demonstrated that *X. flavipes* can be reared on frozen or irradiated eggs of the Indian meal moth *P. interpunctella*.

Lecato and Davis (1973 cit by Press *et al.* 1974) found that *X. flavipes* preferred small larvae of large species and large larvae of small species.

Donnelly and Phillips (2001) compared the functional responses of *X. flavipes* with different densities of the prey species viz., *T. castaneum*, *O. surinamensis*, *P. interpunctella* and *R. dominica* in two different habitats, empty glass jars and glass jars filled with wheat kernels that were designed to stimulate more natural conditions in stored grain. Differences in the functional response of *X. flavipes* to all combinations of prey densities and grain conditions were compared with the predicted functional response curves from Holling's type 1 and type II models and to Hossell's type III model. The functional response of *X. flavipes* was best described by Holling's type II model, but a type III response occurred with prey that were more difficult to subdue, such as larvae. Numbers of prey attacked by females were greater than those *T. castaneum* attacked by males ( $P < 0.05$ ) in both habitats for some of the prey life stages and species. The maximum attack rates for

the different prey species in empty glass jars over 24h were as follows *T. castaneum* 27.3 small larvae, 1.6 large larvae *O. surinamensis* 24.3 small larvae, 17.4 large larvae, *P. interpunctella* 27.2 eggs, 23.7 small larvae, *R. dominica* 26.4 eggs and 16.6 internally feeding larvae. The maximum number killed for the different prey species in glass jars containing wheat over 48h were as follows *O. surinamensis* 13.7 small larvae, 12.8 large larvae, *P. interpunctella* 41.4 eggs, 14.7 small larvae, *R. dominica* 22.0 eggs and 12.1 internally feeding larvae. Experiments with wheat filled jars showed that single *X. flavipes* could locate and kill 27.1 out of 50 *P. interpunctella* eggs and 8.1 out of 10 *R. dominica* larvae inside kernel mixed into  $\approx$  18000 kernels of wheat in 48h.

Sing (1979) studied the functional response of *X. flavipes* to several different bruchid species infesting legumes. The authors reported that the true bug *X. flavipes* exhibited a type II functional response to the majority of cosmopolitan bruchid species evaluated when data were fit to Holling's disc equation. A negative correlation was detected between mean pest species body weight and rate of predation. The rate of attack on adult prey was quite low but fairly consistent with the large sized female predators generally more effective. The eggs and neonate larvae of *Acanthoscelides obtectus* were only accessible immature stages among all prey species examined. Predation on *A. obtectus* eggs and larvae was higher than on any adult bruchids. Mean predator kill of *A. obtectus* immature stages was 40 first instars or 10-20 eggs per 24h interval.

*X. flavipes* were successful at locating and killing *R. dominica* larvae that were feeding inside wheat kernels. In empty dish trials were observed and found that predators examined infested wheat kernels until the beetle larva's entrance hole was found, then the predator would insert its stylet through the entrance hole to bite and feed on the prey. Predators successfully found and killed nearly half of the *R. dominica* larvae feeding inside the small numbers of kernels dispersed among the 18000 kernels of wheat jar experiments (Donnelly and Phillips 2001).

Murata *et al.* (2007) evaluated the suppression of the confused flour beetle *T. confusum* by the anthocorid bug *X. flavipes* and the reduviid bug *Amphibolus venator*.

After 25 days *X. flavipes* alone showed 96.9% suppression of *T. confusum*, and *A. venator* alone showed 76.2% suppression, and both the predator bugs together showed 95.6% suppression of pest population. The rate of loss of whole wheat flour as an index of damage caused by *T. confusum* were 2.7, 6.4, 3.6 and 11.7% in *X. flavipes* adults, *A. venator* adults, *A. venator* adults + *X. flavipes* adults, and control respectively. Furthermore *A. venator* attacked *X. flavipes* adults but not *X. flavipes* nymph. The author discussed on possibility of using both *X. flavipes* and *A. venator* against *T. confusum*.

*X. flavipes* preys on eggs of *C. cautella* (Brower and Mullen 1990), larvae of *T. castaneum* and *P. truncates* (Helbig 1999, Russo *et al.* 2004) and eggs and larvae of *R. dominica* and *P. interpunctella* (Brower and Press 1992). *X. flavipes* reduced population growth of *O. surinamensis* by 95% (Arbogast 1976), small population of *C. cautella* and *P. interpunctella* by more than 70% (Brower and Mullen 1990) and several species of small beetles including *T. castaneum*, *Typhaea stercorea* and *C. pusillus* by 100% (Brower and Press 1992). *X. flavipes* is one of the most dominant predators of many stored product insect pests including *C. pusillus* (Rahman *et al.* 2007). Although *X. flavipes* is the most successful against small sized externally developing prey particularly accessible eggs and early larval stages those are neither heavily sclerotized nor overly hirsute (Lecato and Davis 1973).

Stimulated *X. flavipes* direct a scent gland exudates thought to be defensive in nature over a wide area (Remold 1963). The consistent rapid liquefaction of large adult bruchid prey after attack by *X. flavipes* suggests that the predator utilizes enzymatic salivary venom for extra oral digestion a common strategy of predaceous arthropods preying on large prey with intractable cuticles (Cohen 1995). The potential of a knockdown or disorientation effect from the scent gland secretion (Phillips *et al.* 1995) combined with the catastrophic disruption of neuromuscular function (Blum 1981) caused by the injection of salivary venom could account for the predators ability to kill the comparatively more difficult adult bruchid prey.

Imamura *et al.* (2008) observed biological aspects and predatory abilities of predatory bugs that prey on stored product insects. Biological controls in stored products are being regarded with increasing interest since they are nontoxic and do not damage human health or the environment. Several species of predatory bugs have been studied as biological control agents. Specifically *X. flavipes* is advantageous because it has high population increase capacity and wide distribution. *X. flavipes* has been reported to suppress population of small insects but it can not predate large insects and internal grain feeding insects. As *A. venator*, *P. biannulipes* and *J. paradoxus* can attack large insects.

Ishijima *et al.* (2005) conducted laboratory experiment to test the suppression effects of *X. flavipes* and another predatory bug *J. paradoxus*, whose adults can attack large prey. The reduction rates of *T. confusum* populations with the release of *X. flavipes* and *J. paradoxus* were 97% and 67% respectively. In the *J. paradoxus* treated groups, *T. confusum* adults were completely eliminated by *J. paradoxus* adults. However, when *X. flavipes* and *J. paradoxus* were released simultaneously the reduction rate was only 35%. Intraguild predation has also been reported between *X. flavipes* and *Bracon hebetor* (Say) which is a parasitoid of pyralid moth larvae (Press *et al.* 1974). The reduction rates of *P. interpunctella* with the release of *B. hebetor* and *X. flavipes* were 74% and 22% respectively. When *B. hebetor* and *X. flavipes* were released simultaneously, the reduction rate was 52.6%. The number of *B. hebetor* was also reduced when *X. flavipes* was present indicating that *X. flavipes* had fed on *B. hebetor* as well.

The biocontrol efficacy of the anthocorids *Lyctocoris campestris* (Parajulee *et al.* 1994) and *X. flavipes* (Lecato 1976, Lecato *et al.* 1977, Brower and Press 1992, Brower *et al.* 1996, Donnelly and Phillips 2001) against stored product pests under a variety of environmental conditions is well documented although evaluations with bruchid prey have been comparatively limited.

Sing (1979) and Sing and Arbogast (2008a,b) evaluated *X. flavipes* predation under highly simplified conditions that excluded assessing the potential for the stored commodity, predator density and the lag between infestation and predator introduction to confound host finding and attack success. Intra specific competition

and prey predator population oscillation as influenced by predator density and the timing of predator introduction to the stored commodity would also play an important role in the development of an effective treatment protocol for any operational use of *X. flavipes* to manage bruchid infestations of stored legumes.

Predative association with either one species feeding on another or both species feeding on each other may occur in grain silos and predation among stored grain beetles on the trophic level has been described extensive in laboratory experiments (Lefkovitch 1968, Sokoloff 1974, Ciesielska 1975, Lecato 1975, Suresh *et al.* 2001, Hulasare *et al.* 2005).

Ferdous *et al.* (2009) studied some biological parameter of *X. flavipes* feeding on *T. castaneum* in the laboratory. A single *X. flavipes* consumed 45 larvae of *T. castaneum* in its 1<sup>st</sup>, 2<sup>nd</sup> and 3<sup>rd</sup> nymphal instars. One predator can consume 135 larvae and 56 pupae on *T. castaneum* in its total life time. A mass culture technique of *X. flavipes* on *T. castaneum* was studied under laboratory conditions. The predator separately produced 1974.67 F<sub>1</sub> progeny from a single release of 50 mated females. The percentage of female predator in the culture was 48.89. A single predator in its five nymphal stages consumed 48-64 prey larvae of *C. pusillus* (Rahman 2006). Saha (2007) reported that the highest fecundity of *X. flavipes* was found to be 39.6 and 39.4 when *T. castaneum* and *T. confusum* fed on agar +flour respectively. Rahman (2006) reported an average of 677.0 adults of *X. flavipes* was mass produced after 45 days feeding on *C. pusillus*. Islam and Kabir (1992) described the mass culture technique of another pteromalid parasitoid *Dinarmus basalis* on *C. chinensis* in the laboratory.

**An ideal bacterium:** Spinosad is a reduced risk broad-spectrum bacterium, commercially available product from Dow Agro Sciences (Indianapolis, Indiana, USA). Spinosad is derived by fermentation from a naturally-occurring soil actinomycete, *Saccharopolyspora spinosa* (Mertz and Yao 1990) (Bacteria: Actinobacteridae) (Boek *et al.* 1994), belongs to a new class of insecticides called the NATURALYTES. As these products are created by biosynthesis of *S. spinosa*, so Spinosad has been classified as a bioinsecticide (Copping and Menn 2000).

Spinosad is active after contact (Spark *et al.* 1999), It affects nicotinic acetylcholine and gamma amino butyric acid (GABA) receptor sites of the insects nervous system and so far has proved non-cross-resistant to any other known insecticide (Salgado and Sparks 2005). In addition, Spinosad exhibits low mammalian toxicity and a high favorable environmental profile (Thompson *et al.* 2000, Cleveland *et al.* 2001), and no adverse effects on predatory insects such as ladybirds, lacewings, big eyed bugs or minute pirate bugs (Dow Elanco 1994, Williams *et al.* 2003, Stark *et al.* 2004). Spinosad's impact on beneficial insect populations under field conditions are typically short lived and followed by rapid recovery (Williams *et al.* 2003, Miles and Eelen 2006). In the environment, Spinosad degrades when exposed to sunlight and is quickly metabolized when washed into soil (Saunders and Bret 1997, Liu *et al.* 1999). Moreover, Spinosad residues are highly stable on grains stored in bins, with a length of protection ranging from 6 months to 2 years (Hertlein *et al.* 2011). All these attributes make Spinosad an ideal bacterium for use in the stored product integrated pest management and insecticide resistance management programs.

### **Chemical description of Spinosad**

The chemical name of Spinosad is Spinosyn A and Spinosyn D. Chemical structures of Spinosad and naturally occurring mixture of Spinosyns A and D are shown below (Figure 4 and 5). When the bacterium *S. spinosa* is allowed to grow aerobically in an aqueous growth medium, it produces a number of biologically active metabolites called Spinosyn, which are large complex molecules containing mostly carbon, hydrogen and oxygen arranged in a unique 4-ringed system, one ring of which is a macrocyclic lactone. The 4-ringed system has two sugar molecules attached. About 24 Spinosyn are produced in the fermentation and there are only minor structural differences, such as the presence or absence of a methyl group in various locations (Crouse *et al.* 1999), Spinosyn D has one more methyl group than Spinosyn A. Extraction of the medium and subsequent recrystallization gives Spinosad, which contains about 90% Spinosyns and 10% impurities from the

growth medium, and the Spinosyn fraction contains about 85% Spinosyn A and 15% Spinosyn D in the final products (Mertz and Yao 1990, Kirst *et al.* 1992 and Sparks *et al.* 1999).




Figure 4 Chemical structure of Spinosad.

Spinosyn A is 2-[(6-deoxy-2,3,4-tri-O-methyl-*alpha*-L-mannopyranosyl)oxy]-13-[(5-dimethylamino)tetrahydro-6-methyl-2H-pyran-2-yl)oxy]-9-ethyl-12, 3, 3a, 5a, 5b, 6, 9, 10, 11, 12, 13, 14, 16a,16b-tetradecahydro-14-methyl-1H-as-indaceno(3,2-d)oxacyclododecin-7,15-dione.

Spinosyn D is 2-[(6-deoxy-2,3,4-tri-O-methyl-*alpha*-L-mannopyranosyl)oxy]-13-[(5-(dimethylamino)tetrahydro-6-methyl-2H-pyran-2-yl)oxy]-9-ethyl-2, 3, 3a, 5a, 5b, 6, 9, 10, 11, 12, 13, 14, 16a,16b-tetradecahydro-4,14-dimethyl-1H-as-indaceno(3,2-d)oxacyclododecin-7,15-dione (Dow 1997, Jachetta 2001).

Molecular formula of Spinosyn A and D are C<sub>41</sub>H<sub>65</sub>NO<sub>16</sub> and C<sub>42</sub>H<sub>67</sub>NO<sub>16</sub> respectively; molecular weight are 731.98 and 745.99 respectively. The trade names of Spinosad are Success® Naturalyte®, Tracer®, Spintor, Spinoace, Boomerang, Laser and Extinosad




Figure 5 Spinosad: A naturally occurring mixture of spinosyns A and D.

**Properties of Spinosad:** Tan or white low melting crystals (m.p.84-99.5°C Spinosyn A, m.p. 161-170°C) Spinosyn D, which have low volatility and an earthy odor. Crystals are soluble in a number of organic solvents, Solubility is higher in polar solvents (acetone, dichloromethane, acetonitrile, and methanol) than in non-polar solvents (hexane). Crystals have low solubility in water, though spinosyn A is more soluble than spinosyn D. Water solubility increases as solutions become more acidic. The aqueous solutions are basic with pH about 8, and the Spinosyn react with acids to form salts that have higher water solubility (Thompson *et al.* 2000). A major degradative pathway for Spinosad is photolysis (Saunders and Bret 1997) and this limits its residual efficacy in crop markets to about 7-14 days. However, in farm bins and other enclosed grain storage environments where sunlight is lacking, Spinosad can be highly stable. A total of eight studies evaluated the stability of Spinosad residues in corn and wheat by using analytical techniques. Six of these were field studies (Fang *et al.* 2002b, Flinn *et al.* 2004, Daghish and Nayak 2006, Maier *et al.* 2006, Subramanyam *et al.* 2007 and Daghish *et al.* 2008), and two were laboratory studies (Blanc *et al.* 2004 and Chintzoglou *et al.* 2008b). In general, Spinosad residues on treated wheat and corn appear to be relatively stable over storage periods ranging from 6 to 12 months, even when subjected to wide fluctuations in temperature (-10–32 °C) and humidity (35–85%). Szabela (2005) indicated that analytical measures of Spinosad residues through time support the conclusion that in some cases Spinosad is capable of adequately protecting grains



in storage for up to two years. Where used, linked bioassays confirmed no loss in biological efficacy over these same time periods. Total Spinosad residue declines in these studies ranged from 39% loss over seven and half months to virtually nil loss over 12 months, with other reported values in-between. Chintzoglou *et al.* (2008b) reported unusually rapid degradation of Spinosad residues on corn – much higher than those observed on wheat or rice in the same study; this is the only study showing degradation of a dry Spinosad formulation.

### **Efficacy of Spinosad**

Spinosad is currently targeted only at Lepidoptera and thrips, spinosyns and spinosoids are inherently broad spectrum, showing activity against insects in the orders coleoptera, diptera, homoptera, hymenoptera, isopteran, orthoptera, Lepidoptera, siphonaptera and thysanoptera as well as mites (Thompson *et al.* 1995).

The efficacy of Spinosad on the insect nervous system is unique and different from that of other insect control products (Salgado 1997). Spinosad is practically non toxic to predator insects and insect pathogen (Bret *et al.* 1997), though it is toxic to insect parasitoids and honey bees but the toxicity is significantly much less than many synthetic insecticides (Schoonover and Larson 1995, Bret *et al.* 1997). Insects that are resistant to known synthetic insecticides do not cross resistant to Spinosad. Spinosad is rapidly absorbed and extensively metabolized in a rat. Within 48h of dosing, 60-80% of Spinosad or its metabolites are excreted through urine or feces (EPA 1997, Dow 1997).

Subramanyam *et al.* (1999b) evaluated the effectiveness of Spinosad applied to 14% moisture wheat grain against adults of *R. dominica*, *S. oryzae*, *O. surinamensis*, *T. castaneum* and larvae of *P. interpunctella*. Spinosad at 1 mg/kg provided complete control of *R. dominica* adults within 8 days, and completely suppressed emergence of *P. interpunctella* adults. No F<sub>1</sub> adults of *R. dominica* were produced after 14 days of exposure. *O. surinamensis* and *T. castaneum* were moderately and least susceptible to Spinosad, respectively,

based on adult mortality. However, significant reductions in the production of F<sub>1</sub> adults of *S. oryzae*, *O. surinamensis* and *T. castaneum* occurred at rates  $\geq 3\text{mg/kg}$ .

Toews *et al.* (2003) evaluated contact toxicity of Spinosad to adults of *R. dominica*, *S. oryzae* and *T. castaneum* after 24 or 48h of exposure. Spinosad at a dose  $>0.05\text{ mg/cm}^2$  affected significantly *R. dominica* at 24 and 48h exposures followed by *S. oryzae* and *T. castaneum*. The 24h LD<sub>50</sub> values were 0.0004, 0.077 and 0.189 mg/cm<sup>2</sup> for *R. dominica*, *S. oryzae* and *T. castaneum* respectively. All *R. dominica* adults were dead following 48h exposure Spinosad where as mortality of *S. oryzae* and *T. castaneum* ranged from 10 to 85% and 12 to 48% respectively.

Sanon *et al.* (2010) reported that a dry Spinosad formulation applied at 0.94 ppm to cowpeas provided up to six months of continuous protection when these treated seeds were bagged in plastic and then stored under typical warehouse conditions in Burkina Faso. Control of *C. maculatus* by Spinosad was better than that provided by the commercial standard pyrethroid, deltamethrin. Ghelani *et al.* (2009) demonstrated that Spinosad controlled key stored grain pests of pearl millet in India (*R. dominica*, *T. castaneum*, and *C. cephalonica*) for up to 12 months of storage. However, this study was conducted under laboratory conditions, and Spinosad was applied at a rate of 2 ppm instead of its anticipated global-wide registered use rate of 1 ppm. Thus, these results cannot be considered directly predictive of future commercial performance. In a laboratory study, Vayias *et al.* (2010a) showed that a Spinosad liquid SC formulation applied to barley at 1 ppm provided nearly complete control of *R. dominica* and *S. oryzae* for six months and adequate control of *C. ferrugineus* for four to six months. Control of *T. confusum* was only moderate in this study.

Spinosad applied to wheat at 0.1 and 1.0 mg/kg resulted in adult mortality and preventing population growth of *R. dominica* (Fang *et al.* 2002a,b, Subramanyam *et al.* 1999), and of 1 mg/kg was necessary for complete control and progeny suppression of *C. ferrugineus*, *C. pusillus* and *T. castaneum* (Subramanyam *et al.* 1999).

Huang *et al.* (2007) also reported more or less similar results from Spinosad treated stored corns. More or less each of the Spinosad formula showed potentialities against almost all the insect pest of stored grains. Number of such successful reports have been published from different countries of the world, specially from USA and Australia. The works of Thompson *et al.* (1997), Nayak *et al.* (2005), Daglish and Nayak (2006), Getchell (2006), Yousefnezhad Irani *et al.* (2007) Athanassiou *et al.* (2008a,b,c), Daglish *et al.* (2008), Hussain *et al.* (2009), Mollaie *et al.* (2011), Mutambuki *et al.* (2012), Subramanyam *et al.* (2012) should be reviewed before introducing Spinosad in any IPM programme.

Toews *et al.* (2003) reported contact toxicity of Spinosad to adults of *R. dominica*, *S. oryzae*, *T. castaneum*, *T. confusum*, *C. ferrugineus* and *O. mercator* on four different surfaces. Aqueous Spinosad suspension was sprayed to concrete, galvanized steel, unwaxed floor tile and waxed floor tile to obtain deposits of 0.05 or 0.1mg/cm<sup>2</sup>. Approximately 24h after application, 30 adult beetles were confined by species to each untreated and Spinosad treated surface, and knockdown for 24h was assessed. Mortality of all other species exposed to Spinosad was 99-100%. *Tribolium* spp. were highly susceptible to Spinosad on concrete (99-100% mortality), however on unwaxed floor tile, steel and waxed floor tile recovery on food after knockdown resulted in only 72-92% mortality. Results suggest that Spinosad has excellent contact activity against adults of stored product insects, especially on concrete and has potential for use as a general surface, spot or crack/crevice spray to control insects in empty bins, warehouses, food processing facilities and retail stores.

More field evaluations of Spinosad are necessary to establish its future performance in commercial stored product environments. Field studies are particularly valuable as predictive tools, because they tend to reflect the combined impact of Spinosad on adults, immatures, and progeny production under conditions of continuous exposure-aspects of which are difficult to simulate under laboratory conditions (Toews and Subramanyam, 2004). Published field studies with Spinosad are comparatively less (Fang *et al.* 2002a, Flinn *et al.* 2004a,b and

Subramanyam *et al.* 2007), and in Bangladesh context published literature on Spinosad efficacy against the stored product insects are very scarce.

Toews *et al.* (2005) investigated the survival of stored product insect natural enemies in wheat treated with Spinosad in laboratory and pilot scale experiments. The predator *X. flavipes* and the parasitoids *H. hebetor*, *T. elegans* and *A. calandreae* when exposed to wheat treated Spinosad at 0.05-1 mg/kg, *X. flavipes* was the only species that survived (92% survival). However, when combined treatments with Spinosad and *X. flavipes* was tried against *T. castaneum*, about 90% inhibition of immature population was achieved, both in laboratory and field trials. There is substantial evidence to show that Spinosad at 1 mg/kg is not effective in killing all exposed adults but this rate is effective in suppressing progeny of *T. castaneum* (Fang *et al.* 2002a,b) thereby limiting any population growth to contamination from external sources or other forms of immigration.

A general lack of survival among hymenopterans exposed to Spinosad was also reported in the literature (Tillman and Mulrooney 2000, Mason *et al.* 2002, Michaud 2003). There is limited evidence to suggest that *X. flavipes* is more pesticide tolerant than parasitoids and pest insects (Baker and Arbogast 1995, Press *et al.* 1978). This is a good sign for storage managers to use both these two natural enemies to control the stored product insects.

Yousefnezhad Irani *et al.* (2007) observed toxicity of Spinosad on adults *T. castaneum* and *S. oryzae* at different temperatures and exposure intervals and reported based on LD<sub>50</sub> values and more overlapping of 95% CL, *S. oryzae* was more susceptible to Spinosad than *T. castaneum*. The trend of species susceptibility to Spinosad was similar to those reported by (Subramanyam *et al.* 2004, Hung *et al.* 2004 and Flinn *et al.* 2004a, b).

Spinosad is primarily a stomach poison with some contact activity and it represents a new class of insecticides acting by a neurotoxin with a novel mode of action and act as against at the post synaptic cholinergic ion channels and GABA gated ion channels (Salgado 1998, Salgado *et al.* 1998, Thompson *et al.* 2000).

Spinosad has an excellent environmental and mammalian toxicological profile (Crouse and Sparks 1998, Sparks *et al.* 1999, Thompson *et al.* 2000). Spinosad exhibits wide margin of safety to many beneficial insects and related organisms (Schoonover and Larson 1995, Elzen *et al.* 2000) and is therefore considered a selective insecticide (Miles and Dutton 2000).

Suppression of the subsequent generation is one of the basic characteristics of a successful grain protectant (Arthur 1996). Spinosad is capable to giving long term protection without a loss in efficacy (Fang *et al.* 2002a, Maier *et al.* 2006), through contact, ingestion and through the nervous system.



## **Chapter 3**

# **General Methodology**

**Selection of the test insects: pests and predator**

**Pests:** The flat grain beetle, *Cryptolestes pusillus* (Schon) is one of the common major pests of stored grains, it is particularly common in wet tropical and warmer temperate regions (Halstead 1993, CABI Crop Protection Compendium 2008). It is an external feeder of the stored cereal and other commodities. Incubation, larval, pre pupal and pupal period of *C. pusillus* are 3-4d, 19-21d, 3-4d and 4-5d respectively and the total developmental period is 30-35d. The eggs, larvae, pre-pupae and pupae are normally visual. Culture of *C. pusillus* in the laboratory is simple and subsequently produces huge population within short time. Both larvae and adults of *C. pusillus* damage a number of stored commodities (Cotton 1963).

The lesser grain borer, *Rhyzopertha dominica* (Fabricus) is another serious damaging pest of stored grains it is an internal feeder and cosmopolitan in distribution. The incubation, larval, pre pupal and pupal periods are 4-6d, 18-33d, 1d and 2-4d respectively. Total developmental time required as 30-41d. Eggs, larvae, pre pupae, pupae and adults are normally visual. Culture of *R. dominica* in the laboratory is easy. By feeding and making circular holes into the cereals *R. dominica* causes heavy weight loss and also affects the nutritional and baking quality as well as germination capacity of the grain (Patel and Valand 1994). So for easy culture techniques, requisite quantity of both the pest species were available within a short time under the laboratory conditions.

**Predator:** Under the laboratory conditions hemipteran predators can suppress about 70-100% stored product insect pest populations under the laboratory conditions (Brower and Press 1992). Among the hemipteran predators, the warehouse pirate bug, *Xylocoris flavipes* (Reuter) is a potent candidate to suppress the coleopteran and lepidopteran stored-product insect pests. It is cosmopolitan in distribution (Gross 1954, Arbogast 1979). The incubation and nymphal periods are 4-5d and 10-16d respectively. The developmental period is required 20d which may vary 14-15d depending on food, temperature and humidity. Adult male and female longevity are 6d and 20d respectively. Culture of *X. flavipes* is easily established in laboratory. *X. flavipes* is commercially available in USA to manage

the stored products insect pests (Mason *et al.* 2001). They are commonly found in grain storage facilities and their presence usually indicates an established infestation of grain pests. *X. flavipes* lives on eggs, larvae and pupae of insect pests.

### **Selection of bacterium**

Spinosad is a reduced-risk commercial bacterial insecticide which belongs to a new class of insecticides called the NATURALYTES. Spinosad provides highly effective and long-lasting (up to two years) control of more or less all species of stored insect pests on various grains (Hertlein *et al.* 2011) and so far has proved non-cross-resistant to other insecticides (Salgado and sparks 2005). In addition, spinosad exhibits low mammalian toxicity and a highly environmental profile (Cleveland *et al.* 2001). Spinosad shows wide margins of safety to many beneficial insects and related organisms (Schoonover and Larson 1995, Elzen *et al.* 2000). It degrades quickly when exposed to sunlight (UV light) (Liu *et al.* 1999), therefore it is considered as a selective insecticide (Miles and Dutton 2000). Spinosad is already registered as a grain protectant in Kenya, USA, South Africa, Canada, European Union, Australia, Japan etc. at the maximum use rate of 1ppm (1mg/kg of grain) and its Maximum Residue Limit (MRL) established at 1.5ppm (Hertlein *et al.* 2011). Moreover, Spinosad's unique and non-cross-resistant mode of action will make it a valuable new tool in stored grain resistance management.

### **Food medium used**

**Food for host:** White wheat, whole wheat flour and Brewer's yeast were collected from the granaries of Shaheb Bazer, Rajshahi, Bangladesh. Wheat grains were cleaned by sieving through 500 micrometer aperture sieve (Wire cloth company, Newark, New Jersey 07104, USA) and sterilized in an oven at 100 °C for 8h. Whole wheat flour and powdered Brewer's yeast ratio was 19:1 (Park and Frank 1948, Park 1962, Zyromska-Rudzka 1996) were mixed. Both wheat flour and yeast were passed previously through 125 micrometer aperture sieve (Wire cloth company, Newark, New Jersey 07104, USA) and were sterilized at 120 °C for 6h in an oven. The sterilized wheat and standard food mixture were kept in separate plastic containers for 15 days to equilibrate its moisture content with that of the



laboratory with the minimum of 13% (Khan 1981, Mondal 1984a) and were used throughout the experiments. New foods wheat and standard food were prepared wherever necessary.

**Food for predator:** Continuous supply of eggs, larvae up to 4<sup>th</sup> instars, pupae of *C. pusillus* and *R. dominica* were provided as food for *X. flavipes* during maintained culture in the laboratory. Culture of beetles was maintained according to Mondal and Parween (1997) in beakers containing food medium.

#### **Culture of *C. pusillus***

**Collection of beetle:** Adults of *C. pusillus* were collected from the rearing culture maintained in the Integrated Pest Management Laboratory (IPM), Institute of Biological Sciences, University of Rajshahi since ten years.

**Collection of eggs:** Six hundred unsexed adults of *C. pusillus* were collected and divided into three groups, each having 200 adults and were introduced to separate glass petri dishes (9cm diame) containing 50g food (whole wheat flour and Brewer's yeast, ratio19:1) and allowed to oviposit. After 24h, the adults were sieved and eggs were collected sieving by 125 micrometer aperture sieve. The collected eggs were cleaned by gently tapering the paper on a piece of black paper and by separating flour particles. Cleaned eggs were identified under compound microscope and transferred to petri dishes with the help of fine camel hair brush. Eggs were kept 3-4d for hatching.

**Collection of larvae, pre-pupae, pupae and adults:** After hatching, 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> instars larvae were obtained from 4-5d, 5-6d, 4-5d and 6-7d respectively. Pre pupae and pupae were seen into the cocoon at 3-4d and 4-5d. The larvae and pupae were confirmed by random examining under a magnifying glass. Pupae emerged as adults at 4-5d. All the cultures were conducted in the Control Temperature (CT) room at 30±0.5°C temperature and 70±0.5% relative humidity to ensure constant and regular supply of different life stages of *C. pusillus* of known age throughout the study period.

**Determination of sex:** The male-female sexes were determined by the following characters

- i) Antennae was about two thirds length of the body in male and half length of the body in female.
- ii) Male hind tarsi were 4 segmented but female hind tarsi were 5 segmented
- iii) Males were normally small in shape-size than females.

### **Culture of *R. dominica***

**Collection of beetle:** Adults of *R. dominica* were collected from the stock culture maintained in Integrated Pest Management Laboratory, Institute of Biological Sciences, University of Rajshahi since ten years.

**Collection of eggs:** Six hundred unsexed adults of *R. dominica* were collected and divided into 3 groups, each having 200 adults and were kept in separate petri dishes (15 cm daime) containing 100g of white wheat and allowed to oviposit. After 24 h, the adults were sieved out and eggs were separated using by 500 and 125 micrometer aperture sieves for adults and eggs respectively. Eggs were examined under compound microscope and transferred to glass petri dishes (15 cm daime) with the help of fine camel hair brush. The collected eggs were kept 4-6d for hatching.

**Collection of larvae, pre pupae, pupae and adults:** After hatching, the 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup> and 4<sup>th</sup> instars larvae, pre pupae and pupae were obtained from 6-12d, 4-7d, 4-6d, 4-8d, 1d and 2-4d respectively and were confirmed by random examining under a magnifying glass. Adults were emerged directly from pupae. All cultures were conducted in the Control Temperature room at 30±0.5°C temperature and 70±0.5 % relative humidity to ensure constant and regular supply of various kinds of life stages of *R. dominica* of known ages.

**Determination of sex:** It is difficult to identify the sex of *R. dominica* in their larval and adult stages. Sex of *R. dominica* was separated in the pupal stage by the microscopic test of exogenital papillae by removed of attached exuvae (Porter 1935). The sexed pupae were then placed in separate petri dishes for the emergence of adults. Survivorship of pupae was reduced by sexing procedure and the degree of reduction varied considerably with the culture media used (Long staff and Starick 1989).

### **Culture of *X. flavipes***

**Collection of the adult bug:** Adults of *X. flavipes* were collected from the stock culture maintained in the Integrated Pest Management laboratory, Institute of Biological Sciences and University of Rajshahi for six years.

**Collection of eggs:** One hundred adults of *X. flavipes* were placed in a beaker (500 ml) containing sufficient food (1<sup>st</sup> and 2<sup>nd</sup> instars larvae and pupae of *C. pusillus* and *R. dominica*). After 24 h, adults were replaced with the help of a fine camel brush. Eggs were found at the bottom of the beaker and examined them under compound microscope. The collected eggs were kept at 4-5d for hatching.

**Collection of nymphs and adults:** The newly hatched nymphs were determined using by magnifying glass and transferred very carefully with the help of fine camel hair brush to a beaker (500 ml) containing 1<sup>st</sup> and 2<sup>nd</sup> instars larvae of *C. pusillus* and *R. dominica* as food. The 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> and 5<sup>th</sup> instars nymphs were obtained from the culture on the 3<sup>rd</sup>, 5<sup>th</sup>, 8<sup>th</sup> and 12<sup>th</sup> d from hatching respectively (Arbogast 1971). The nymphal instars were estimated by counting the exuviae deposited in the petri dish. The 5<sup>th</sup> instars nymphs transferred into adults.

The culture of *X. flavipes* was maintained in beakers (500 ml) containing food medium (wheat flour and whole wheat infested by either *C. pusillus* or *R. dominica*). The mouth of the beaker was covered with fine cloth and tied with rubber band. Beakers were kept in the Control Temperature room at 30±0.5°C and 70±5 % rh.

**Determination of sex:** Sex of *X. flavipes* was separated at the adult stage. Shape of the adult female's abdomen is bilaterally symmetrical and in male it is notched on the left side of the segments 8 and 9.

### **Source of Spinosad**

Spinosad is light gray to white in colour with slight odor stale water. About 500ml of Spinosad (PRN- MAPP-12054, cafno 20012- 019, Lot No–3068404) was obtained from Dow Agro Sciences, UK. Concentration of spinosad was 120g spinosad/Litre.

### **Preparation of concentration**

Using by 3 ml syringe 0.5 ml (equal to 32 drops) of Spinosad were taken in glass vial (5 ml) and using a micropipette 2 ml distilled water were added. The vial was shaken vigorously for equal mixing of Spinosad and water. Filter papers (9 cm diameter) were soaked in the prepared solution and allowed to evaporate at room temperature overnight hanging by strings. This 0.5 ml solution had the concentration equal to  $7.863 \mu\text{l}/\text{cm}^2$ , determined using the formula given by Athanassiou *et al.* 2008. Other concentrations of Spinosad as 3.932, 1.966, 0.983 and  $0.491 \mu\text{l}/\text{cm}^2$  were than prepared by serial dilution, by taking half drops of Spinosad in each step and adding 2 ml distilled water.

### **Precautions**

All experiments were conducted under same laboratory conditions. Frass, spoiled substance, faecal materials, dead beetles, cocoon, etc. gradually accumulate in the culture media and make it dirty, unhealthy and damped. To avoid such unhealthy condition, the original cultures of both predator and prey insects were sieved after every 10-12d and fresh food was added to the culture. All glass wares, equipments and sieves were sterilized at  $180^\circ\text{C}$  for 6h in an oven just before use. Washing detergents were used to clean all the materials. The experimental desks were cleaned everyday.

### **Statistical analysis**

Data were analyzed by factorial ANOVA, Tukey's test, Probit analysis using some statistical software like Minitab (version 14), MS Excel 2003 and Bio stat 2009.



## **Chapter 4**

**Host-stage specific effects on  
biological parameters of *X. flavipes***

## Introduction

Stored commodities are attacked by Lepidoptera, Coleoptera and Acari (Sing and Watters 1985, Khan and Mannan 1991). They consist of many external and internal feeders such as *C. pusillus* and *R. dominica* and are found occasionally infesting grain (Subramanyam 2006a,b). Insect pest management in stored commodities with chemicals is facing many challenges due to concerns about human safety, insect resistance, environmental impacts and presence of residues in raw and processed foods (Hagstrum *et al.* 1999, Phillips *et al.* 2000, Daghli and Wallbank 2002, Nayak *et al.* 2005, Daghli and Nayak 2006). Therefore, there is an urgent need to develop alternative methods for their control. Biological control has been studied as an alternative option (Arbogast 1985, Haines 1984, 1991, Brower *et al.* 1996, Scholler and Flinn 2000) and it is also dependent on the potentiality of biocontrol agents. Among the predatory bugs, the warehouse pirate bug, *X. flavipes* is one of the biological control agents of many stored product insect pests (Brower *et al.* 1996, Scholler *et al.* 1997, Visarathanonth *et al.* 1990, 1994, Imamura *et al.* 2008). Actually, *X. flavipes* showed promise in suppressing populations of stored product insect pests (Jay *et al.* 1968) and preyed on early and late instar of many insect species but the number depending partly on the size of the prey and possibly other factors (Lecato and Davids 1973). Age of the host insect can have a profound effect on development and oviposition of parasitoids/predators (Vinson and Iwantsch 1980) because nutritional status and accessibility of the host may change with age.

Several workers have described the effects of temperature, humidity and host species as foods on the biology of *X. flavipes* (Birch 1945a,b,c, Howe 1953, Arbogast 1975, Press *et al.* 1976, Russo *et al.* 2004, Herra *et al.* 2005, Ferdous 2006, Saha 2007, Rahman *et al.* 2009). Before releasing the predator in the store to control insect pests, a thorough knowledge is needed about their biology. Many parasitoids/predators lay more eggs in certain host instar than the other. However, no specific information has been available concerning host *C. pusillus* and *R. dominica* stage specific effects on the biology of *X. flavipes*. Moreover, it was

important to measure the developmental period, adult longevity, consumption rate, survivability, size and sex ratio of *X. flavipes* on different life stages of host *C. pusillus* and *R. dominica*. This led to the conduct of the test.

### **Materials and Methods**

**Host:** Two hundreds newly emerged healthy and mated females of *C. pusillus* were collected from previous established culture (Chapter 3). They were introduced in a Petri dish (15cm diameter) containing 10g fresh food (wheat flour and yeast ratio, 19:1 in weight). After 24 h, adults were sieved out from Petri dish and kept them in another Petri dish (15cm diameter) with same fresh food. The eggs along with foods were placed in a Petri dish (9cm diameter). The Petri dish was kept within wooden folder for the save from other organisms. The wooden folder was sifted to CT room at  $30\pm 0.5^{\circ}\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity. A series of culture were maintained for regular supply of eggs, larvae up to 4<sup>th</sup> instar and pupae of *C. pusillus*. Through the same procedure as described above eggs, larvae up to 4<sup>th</sup> instar and pupae of *R. dominica* were reared for regular supply. Different life stages of both hosts were used as food in the present tests.

**Predators:** Fifty newly emerged healthy and mated females of *X. flavipes* were collected from earlier established culture (Chapter 3) and introduced in a glass beaker (500 ml) with 1<sup>st</sup> and 2<sup>nd</sup> instar larvae of *C. pusillus* and *R. dominica* as food and allowed to oviposit. Two filter papers were placed at the bottom of the beaker. Mouth of the beaker was covered with the fine cloth and rubber band to prevent moving out of the insects. After 24 h, the adults were removed to another beaker (500 ml) using by a fine camel brush and the deposited eggs were collected in a Petri dish (9 cm diameter) tapping by the filter papers for hatching. The newly hatched nymphs were carefully transferred to Petri dish (9 cm diameter) one by one using by fine camel brush.

**Bioassays:** Newly hatched healthy 70 nymphs of *X. flavipes* were kept in 7 Petri dishes (9 cm diameter) separately (per Petri dish with 10 nymphs) containing with 200 eggs, 25 larvae of each instar and 10 pupae of *C. pusillus* as food. After every 24 h, consumed or killed life stages of *C. pusillus* by *X. flavipes* were observed



and counted. Food were balanced adding by same life stage and were cleaned discarding by dead insects daily. Same procedure was followed as described above for *R. dominica*. The nymphs were regularly observed for ecdysis, number of nymphal ecdysis was recorded along with the duration for each instar. Regular supply of eggs, larvae up to 4<sup>th</sup> instar and pupae of *C. pusillus* and *R. dominica* was maintained until the death of *X. flavipes*. The numbers of adult's emergence as well as total developmental time and longevity of adults were observed. Prey consumption rate and no. of survivability of *X. flavipes* were observed and counted. The length (mm) of male and female adults was measured using by an ocular micrometer and the sexes were differentiated by compound microscope. All the experiments were replicated three times and conducted in CT room at  $30 \pm 0.5^\circ\text{C}$  and  $70 \pm 0.5\%$  relative humidity.

**Data analysis:** The developmental period, adult longevity, prey consumption rate, survivability, size and sex ratio of *X. flavipes* were determined statistically compared to control using by factorial ANOVA. The comparison of mean was done by Tukey's test (1953).

### Results and Observation

***C. pusillus* as prey of *X. flavipes*:** *C. pusillus* were reared on standard food. The mean developmental period from egg hatching to adult emergence of *X. flavipes* on different life stages of *C. pusillus* have shown in Figures 10A and Appendix table 2. Developmental period and its variance depended upon the different life stages of host (Figure 10B). *X. flavipes* was found able to complete development on eggs, larvae up to 4<sup>th</sup> instar and pupae of host but not on adults. On eggs, larvae up to 4<sup>th</sup> instar and pupae the mean developmental durations were recorded as  $15 \pm 2.00$ ,  $20 \pm 0.00$ ,  $22 \pm 0.58$ ,  $18 \pm 1.00$ ,  $14 \pm 1.15$  and  $12 \pm 1.15$  days respectively (Appendix Table 2). The age specific distribution of each nymph up to 5<sup>th</sup> instar varied on different life stages of prey (Figure 10A). The developmental period was maximum on 2<sup>nd</sup> instar larvae and was minimum on the pupae (Appendix table 2). The effects of different life stages of host on the developmental period was highly significant ( $P < 0.001$ ) (Appendix tables 3-7).

Life span of the predator varied with the different life stages of host. Adult of *X. flavipes* were found to be very active on the 2<sup>nd</sup> to 4<sup>th</sup> instar larvae Figure 10A,B). The highest longevity of the females was 31±1.15 days on 2<sup>nd</sup> instar larvae and lowest was 14±1.15 days on pupae (Appendix table 2). The effect of different life stages of prey on adult longevity was highly significant (P<0.001) (Appendix tables 8 and 9).

Average (%) number of daily consumed or killed eggs, larvae up to 4<sup>th</sup> instar and pupae of *C. pusillus* by nymphs up to 5<sup>th</sup> instar and adults of *X. flavipes* were presented in Figure 12A and Appendix table 18. Consumption rate of *X. flavipes* was found to be varied on stages of host (Figure 12B). Effect of different life stages of *C. pusillus* on nymphs and adults of *X. flavipes* was found highly significant (P<0.001) (Appendix tables 19-25). The female predator always consumed more prey than the male. 2<sup>nd</sup> instar larvae of the beetle were found more preferable to the predator compared to other stages. A single *X. flavipes* can consume 3.33±0.33, 4.33±0.33, 5.67±0.33, 6.33±0.33, 8.67±0.33, 12.33±0.33 and 14.33±0.33 2<sup>nd</sup> instar larvae of *C. pusillus* per day in its 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup>, 5<sup>th</sup>, adult male and female stages respectively (Appendix table 18). So an individual *X. flavipes* needs total 164.97, 129.01, 88.33, 66.01, 25.01 and 31 numbers of eggs, larvae up to 4<sup>th</sup> instar and pupae of *C. pusillus* to become adult. Number of eggs, larvae up to 4<sup>th</sup> instar and pupae of prey were consumed by *X. flavipes* as 130.64, 114.64, 98.64, 77.3, 69.36 and 34.64 respectively in adult male and as 413.40, 326.60, 286.66, 226.60, 186.60 and 113.40 respectively in adult female.

Average survivability (%) of *X. flavipes* (nymphs up to 5<sup>th</sup> instar and adults) was recorded as maximum when fed on eggs, larvae up to 2<sup>nd</sup> instar 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae (Figure 14A, Appendix table 34). Survivability of *X. flavipes* was depended upon different life stages of *C. pusillus* (Figure 14B). The effect of host stages on survivability of nymphs up to 5<sup>th</sup> instar and adults of *X. flavipes* was found highly significant (P<0.001) (Appendix tables 35-41).

Normally females are larger in size than males. Size of the adult *X. flavipes* was more when they fed on the larvae up to 4<sup>th</sup> instar of *C. pusillus* than when they fed

on eggs and pupae (Figures 16A, Appendix table 50). The largest the males and females were measured as  $1.80 \pm 0.01$  and  $2.10 \pm 0.01$  mm respectively feeding on 3<sup>rd</sup> instar larvae and shortest sizes were  $1.50 \pm 0.06$  and  $1.70 \pm 0.06$  mm respectively on eggs (Appendix table 50). The effect of different life stages of host on adult size was highly significant ( $P < 0.001$ ) (Figure 16B, Appendix tables 51 and 52).

Sex ratio of the emerged predators differed while feeding different life stages of *C. pusillus* (Figures 18A, Appendix table 56). Sex differentiation of the emerged adults of *X. flavipes* was affected by the life stages of *C. pusillus* which were preyed by the predator. The sex-ratio of *X. flavipes* was found to fluctuated depending on the larval instar and other stages of prey. In all cases more number of female bugs were produced when the immature predators fed in 1<sup>st</sup> instar host larvae, the sex ratio was obtained closer to the normal one, the resulted sex ratio (male:female) was 45:55. Effect of different life stages on sex ratio was highly significant ( $\chi^2 = 13.67$ ,  $df = 5$ ,  $P < 0.001$ ) (Figure 18B, Appendix tables 57 and 58).

***R. dominica* as prey of *X. flavipes*:** *X. flavipes* were successful at locating and killing *R. dominica* larvae and pupae that were feeding inside wheat kernels. The mean developmental period from egg hatching to adult emergence of *X. flavipes* on different life stages of *R. dominica* have been shown in Figures 11A and Appendix table 10. Developmental period and its variance depended upon the different life stages of the prey (Figure 11B). *X. flavipes* was able to complete development on eggs, larvae up to 4<sup>th</sup> instar and pupae of the prey. On eggs, larvae up to 4<sup>th</sup> instar and pupae the mean developmental durations were  $18 \pm 1.00$ ,  $20 \pm 0.58$ ,  $16 \pm 2.00$ ,  $14 \pm 1.15$ ,  $12 \pm 1.15$  and  $13 \pm 0.58$  days respectively (Appendix table 10). The age specific distribution of each nymph up to 5<sup>th</sup> instar varied on different life stages of prey (Figure 11A). The developmental period was maximum on 2<sup>nd</sup> instar larvae but minimum on 4<sup>th</sup> instar larvae (Appendix table 10). The effects of different life stages of prey on the developmental period was highly significant ( $P < 0.001$ ) (Appendix tables 11-15).

Life span of the predator varied with the different life stages of prey. Adult of *X. flavipes* were found to be very active on the 2<sup>nd</sup> to 4<sup>th</sup> instar larvae. The highest

longevity of the females was  $34 \pm 2.31$  days on 2<sup>nd</sup> instar larvae and lowest was  $15 \pm 1.15$  days on pupae of the host (Appendix table 10). The effect of different life stages of prey on adult longevity was highly significant ( $P < 0.001$ ) (Appendix tables 16 and 17).


Mean number of daily consumed eggs, larvae up to 4<sup>th</sup> instar and pupae of *R. dominica* by nymphs up to 5<sup>th</sup> instar and adults of *X. flavipes* were presented in Figure 13A and Appendix table 26. Consumption rate of *X. flavipes* was found to vary on life stages of prey (Figure 13B). Effect of different life stages of *R. dominica* on nymphs and adults of *X. flavipes* was found highly significant ( $P < 0.001$ ) (Appendix tables 27-33). The female predator always consumed more prey than the male. 1<sup>st</sup> instar larvae of prey were found more preferable to the predator comparatively than other stages. One *X. flavipes* consumed  $3.33 \pm 0.88$ ,  $4.67 \pm 1.20$ ,  $5.00 \pm 0.58$ ,  $6.33 \pm 0.88$ ,  $8.67 \pm 1.20$ ,  $10.00 \pm 1.15$  and  $14.00 \pm 1.15$  1<sup>st</sup> instar larvae of *R. dominica* per day in its 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup>, 5<sup>th</sup>, adult male and female stages respectively (Appendix table 26). So an individual *X. flavipes* needs total 260, 104, 86.32, 78.67, 52.30, and 30.99 numbers of eggs, larvae up to 4<sup>th</sup> instar and pupae of *R. dominica* to become adult. Number of eggs, larvae up to 4<sup>th</sup> instar and pupae of prey were consumed by *X. flavipes* as 213.30, 100, 93.30, 86.70, 63.30 and 30 respectively in adult male and 572.74, 528, 271.26, 249.26, 183.26 and 88 respectively in adult female.

Average survivability (%) of *X. flavipes* (nymphs up to 5<sup>th</sup> instar and adults) on eggs, larvae up to 2<sup>nd</sup> instar were found maximum comparatively than that of 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae (Figure 15A, Appendix table 42). Survivability of *X. flavipes* was depended upon different life stages of *R. dominica* (Figure 15B). The effect of host stages on survivability of nymphs up to 5<sup>th</sup> instar and adults of *X. flavipes* was found highly significant ( $P < 0.001$ ) (Appendix tables 43-49).


Normally females are larger than males. Adult male and female size of *X. flavipes* was when the larvae upto 4<sup>th</sup> instar of *R. dominica* was fed by the predator, whereas the adult size was less when it fed on 4<sup>th</sup> instar larvae and pupae (Figures 17A, Appendix table 53). The highest size of the males and females was

1.85±0.01 and 2.15±0.02 mm feeding on 2<sup>nd</sup> instar larvae, and lowest was 1.65±0.04 and 1.90±0.03 mm feeding on pupae (Appendix table 53). The effect of different life stages of prey on adult size was highly significant ( $P < 0.001$ ) (Figure 17B, Appendix tables 54 and 55).

Sex ratio of the emerged predators differed while feeding on different life stages of *R. dominica* (Figures 19A, Appendix table 59). The sex ratio of *X. flavipes* reared on different life stages of *R. dominica* always showed preference to the females, but fluctuation of the male-female ratio was recorded among the stage of the prey insect. Based on ratio 1:1, sex ratio of *X. flavipes* was found the best on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae comparatively than other stages. Effect of different life stages on sex ratio was highly significant ( $\chi^2 = 12.76$ ,  $df = 5$ ,  $P < 0.001$ ) (Figure 19B, Appendix tables 60 and 61).




A




B

**Figure 10A** Mean developmental time and adult longevity of *X. flavipes* on different life stages of *C. pusillus*.

**10B** Relationship between mean developmental time and adult longevity of *X. flavipes* and different life stages of *C. pusillus*.




A




B

**Figure 11A** Mean developmental time and adult longevity of *X. flavipes* on different life stages of *R. dominica*

**11B** Relationship between mean developmental time and adult longevity of *X. flavipes* and different life stages of *R. dominica*



A




B


**Figure 12A** Average (%) no of *C. pusillus* (eggs, larvae up to 4<sup>th</sup> instar and pupae) consumed per day by different life stages of *X. flavipes*

**12B** Relationship between consumption rate of *X. flavipes* and different life stages of *C. pusillus* per day






A




B

**Figure 13A** Average (%) no of *R. dominica* (eggs, larvae up to 4<sup>th</sup> instar and pupae) consumed per day by different life stages of *X. flavipes*

**13B** Relationship between consumption rate of *X. flavipes* and different life stages of *R. dominica* per day




A




B

**Figure 14A** Average (%) no. of survivability of different life stages of *X. flavipes* on different life stages of *C. pusillus*

**14B** Relationship between average no. of survivability of different life stages of *X. flavipes* and different life stages of *C. pusillus*




A




B

**Figure 15A** Average (%) no. of survivability of different life stages of *X. flavipes* on different life stages of *R. dominica*

**15B** Relationship between average no. of survivability of different life stages of *X. flavipes* and different life stages of *R. dominica*




A




B

**Figure 16A** Average size (mm in length) of adult *X. flavipes* fed on different life stages of *C. pusillus*

**16B** Relationship between average size (mm in length) of adult *X. flavipes* and different life stages of *C. pusillus*




**A**




**B**

**Figure 17A** Average size (mm in length) of adult *X. flavipes* fed on different life stages of *R. dominica*

**17B** Relationship between average size (mm in length) of adult *X. flavipes* and different life stages of *R. dominica*




**A**




**B**

**Figure 18A** Average no. of *X. flavipes* male and female fed on different life stages of *C. pusillus*

**18B** Relationship between average sex ratio of *X. flavipes* and different life stages of *C. pusillus*



A



B

**Figure 19A** Average no. of *X. flavipes* male and female fed on different life stages of *R. dominica*

**19B** Relationship between average sex ratio of *X. flavipes* and different life stages of *R. dominica*

## Discussion

Different life stages of hosts *C. pusillus* and *R. dominica* which used as food played an important role in controlling developmental periods, adult longevity, survivability, size and sex ratio of the predator *X. flavipes*. The consumption rate of individual predator varied widely depending on the stage of the prey. The predator developed faster, lived longer as an adult, survived better in the immature stage and laid more eggs when fed on coleopteran larvae rather than lepidopteran larvae (Abdel Rahman *et al.* 1978-79). *C. pusillus* and *R. dominica* were the most suitable prey of *X. flavipes* (Brower and Press 1992, Abdel Rahman *et al.* 1978-79). As intrinsic factors both temperature and relative humidity considerably affect the duration of nymphal and adult stage of *X. flavipes* (Abdel Rahman *et al.* 1977 and Arbogast 1978), similar results was found on different life stages of both *C. pusillus* and *R. dominica* respectively.

W Islam 1993 found that the developmental time of *Anisopteromalus calandrae* How from egg to adult emergence is  $237.6 \pm 1.83$  h for males and  $206.57 \pm 0.78$  h for females at  $30 \pm 0.5^\circ\text{C}$  and  $70 \pm 0.05$  rh. *Dinarmus basalis* Rond was found to attack and successfully complete its development within the larvae, pre-pupae and pupae of *Callosobruchus chinensis* L. and adult parasitoid emerged after complete life cycle within 12-14 days (Islam *et al.* 1985). At  $30^\circ\text{C}$  temperature there are five nymphal instar of *X. flavipes* and the instar number may vary from 2-6 (Arbogast *et al.* 1971, Awadallah and Tawfik 1973). On *P. interpunctella* at  $30^\circ\text{C}$  temperature, life of the predator was found to complete in 14-21 days (Arbogast 1975). In the present study mean developmental periods of nymphal instar was obtained as  $12 \pm 1.15$  -  $22 \pm 0.58$  days and  $12 \pm 1.15$  -  $20 \pm 0.58$  days feeding on different life stages of *C. pusillus* and *R. dominica* respectively.

Awadallah and Tawfik (1973) reported that adult males and females of *X. flavipes* when provided with *T. castaneum*, lived for 5-43 and 4-37 days respectively in average. However, the present study revealed that the adult males lived for  $8 \pm 1.15$ ,  $10 \pm 1.15$ ,  $12 \pm 1.15$ ,  $11 \pm 1.15$ ,  $9 \pm 0.58$ ,  $6 \pm 0.58$  days and  $10 \pm 2.31$ ,  $12 \pm 1.15$ ,  $18 \pm 0.58$ ,  $10 \pm 1.33$ ,  $8 \pm 1.15$ ,  $5 \pm 0.58$  days and females lived for  $20 \pm 1.15$ ,  $25 \pm 2.89$ ,  $31 \pm 1.15$ ,  $28 \pm 1.15$ ,  $26 \pm 0.58$ ,  $14 \pm 1.15$  days and  $22 \pm 3.46$ ,  $26 \pm 0.88$ ,  $34 \pm 2.31$ ,  $24 \pm 2.31$ ,  $20 \pm 1.15$ ,  $15 \pm 1.15$  days in average on eggs, 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae



respectively of *C. pusillus* and *R. dominica*. Abdel Rahman *et al.* (1977) found that raising temperature 15-35°C enhanced development of the eggs and the nymphal stages and shortened the life span of the adult stage of *X. flavipes*.

The female *Dinarmus basalis* Rond fed on body fluids of *Callosobruchus chinensis* L. through the feeding tubes on the way of oviposition like many other Pteromalids and continuously deposited their eggs throughout their adult life (Islam 1991). *X. flavipes* consumption on adult insect pests explained not only by the greater challenge to subdue large prey, but it also correlated with daily ingestion rate and gut capacity, the nutritional resources of large prey generally exceed the daily food requirements of small predators (Peters 1983). *X. flavipes* killed significantly more ‘stimulating’ larval prey than ‘easy’ egg prey (Lecato and Arbogast 1979, Russo *et al.* 2004). Arbogast (1978) stated that *X. flavipes* has a high capacity to increase in number relative to its prey. Lecato and Collins (1976) mentioned that *X. flavipes* destroys large quantities of prey when prey is abundant. It was observed in the present study that when an excess of eggs, 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae of *C. pusillus* and *R. dominica* were provided, each predator killed an average of 300 eggs, 49 larvae and 25 pupae of *C. pusillus* and 400 eggs, 49 larvae and 10 pupae of *R. domonica* during their life time. But when the different life stages of host were provided separately, each predator destroyed an average of 400 eggs, 60 larvae and 28 pupae of *C. pusillus* and 500 eggs, 50 larvae and 20 pupae. The feeding intensity of *X. flavipes* differs depending on the species of the prey and their life stages. Awadallah *et al.* (1986) reported that the predator when preyed only on the larvae of different pest insects, the predator fed on 105 larvae of *Coccyra cephalonica*, 112 larvae of *T. confusum*, 30 larvae of *Stegobium panicerum*, 148 larvae of *Lasioderma serriicorni* during 43 days of life span. The previous reports showed that *X. flvipes* reduced population growth of *Oryzaephilus surinamensis* by 95% (Arbogast 1976), small population of *C. cautella* and *P. interpunctella* by more 70% (Brower and Mullen 1990) and several species of small beetles including *T. castaneum*, *Typhaea sterocorea*, *C. pusillus*, *R. dominica* 70-100% (Brower and Press 1992). Hymenopteran

parasitoid, life time reproductive success is strongly correlated with the number and quality of parasitized hosts (Potting *et al.* 1997). However, during this feeding period, the predator devoured 63 eggs only why such differences occur in feeding activity in relation to the prey species and life stages, the answer lies in the optimal diet theory which assumes that predators are able to rank prey in order of profitability (Charnov 1976). It is an evident from the present and previous studies on the biology of *X. flavipes* for growth and reproduction potentiality the predator needs energy rich food, Hence they feed on less number of pupae than the number of eggs or larvae.

Active feeding period regulates not only oviposition but also duration of egg laying and total life span. A female *X. flavipes* killed  $47.3 \pm 4.88$  larvae of *C. pusillus* and laid  $20.1 \pm 1.66$  eggs during her life time ( $25 \pm 1.26$ ) days on *C. pusillus* larvae (Ahmed *et al.* 2004). It has been reported that an adult *X. flavipes* killed only 1 or 3 late instar larvae of *T. castaneum* in 24 h (Donnelly *et al.* 2001). When can prey on adult *Tribolium*. (Nishi *et al.* 2004) *X. flavipes* does not easily prey on adults. The present study showed that *X. flavipes* can't prey on adults of *C. pusillus* and *R. dominica*. Imamura *et al.* (2008) observed that the population of internal grain feeding insects such as *Sitophilus* and moth such as *C. cautella* and *P. interpunctella* were less affected by the predator compared with small external feeder such as *O. surinamensis* by the predator. The present study indicated the similar results of the above findings.

Survivability of immature stages of predator was maximum on 2<sup>nd</sup> instar larva and 3<sup>rd</sup> instar larvae and was minimum on pupae of *C. pusillus*. But in case of *R. dominica* it was maximum on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae and was minimum on 4<sup>th</sup> instar larvae and pupae. Arbogast (1975) reported that survivability among immature stages of *X. flavipes* was lowest at 35°C temperature.

Lecato and Davis (1973) reported that the early instar nymph, late instar nymph and adult *X. flavipes* length (mean $\pm$ SE) was  $1.09 \pm 0.01$ ,  $1.88 \pm 0.02$  and  $2.22 \pm 0.05$  mm

respectively. In the present study, it was found that adult male size (length) was  $1.50\pm 0.06$ ,  $1.60\pm 0.03$ ,  $1.75\pm 0.03$ ,  $1.80\pm 0.01$ ,  $1.65\pm 0.03$ ,  $1.55\pm 0.04$  mm and  $1.75\pm 0.03$ ,  $1.80\pm 0.02$ ,  $1.85\pm 0.01$ ,  $1.81\pm 0.03$ ,  $1.76\pm 0.03$ ,  $1.65\pm 0.04$  mm and adult female size (length) was  $1.70\pm 0.06$ ,  $1.90\pm 0.03$ ,  $2.00\pm 0.03$ ,  $2.10\pm 0.01$ ,  $1.95\pm 0.03$ ,  $1.85\pm 0.04$  mm and  $2.00\pm 0.03$ ,  $2.20\pm 0.06$ ,  $2.15\pm 0.02$ ,  $2.10\pm 0.01$ ,  $1.98\pm 0.05$ ,  $1.90\pm 0.03$  mm in average on eggs, 1<sup>st</sup>, 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae respectively of *C. pusillus* and *R. dominica*.

The sex ratio (%) of emerging adults of *X. flavipes* ranged from 0.98 to 0.76 at different host stage specific, but it was not significant from 1:1 for any of the life stages. Russo *et al.* (2004) found similar result for *X. flavipes*. Parajulee and Phillips (1993) reported a similar rate of *Lyctocoris carpestris* at 30°C and 60-70% relative humidity.

Taking into account the time of development, adult longevity, consumption rate, survivability, size and sex ratio the most suitable stage of the prey were 2<sup>nd</sup> instar larvae of *C. pusillus* and *R. dominica*, which produced the largest predator individuals in the shortest period of exposure. Overall *X. flavipes* proved itself as an effective predator of insect pest in grain storage and a potential controlling agent against *C. pusillus* and *R. dominica*.



**Chapter 5**  
**Effects of Spinosad**  
**on**  
***C. pusillus* and *R. dominica***

## Introduction

One of the challenges for 21<sup>st</sup> Century is to grow more food for the growing population of the world, and for food security (Pimental *et al.* 1994). For the protection of stored grains and other food commodities needs sustainable insect pest management of stored products, considering the safety of the consumers and the environment, within a cost effective way. *C. pusillus* is one of the serious external feeder and common major pests (Halstead 1993, Ahmed and Khatun 1994) and *R. dominica* is one of the most injurious internal feeder and a major pest (Potter 1935, Crombie 1941), occurring in all areas of the world where grain is produced and stored (Chittenden 1911, Chanbang *et al.* 2007, Jia *et al.* 2008, Edde 2012).

Both pests virtually feed on all kinds of stored grain and milled cereal products and causes immense damage to the tropical and subtropical countries throughout the world including Bangladesh (Dhaliwal 1976, Kirkpatrick and Cagle 1978, Hossain *et al.* 1986). The damage is caused by both the larval and adults stages of *C. pusillus* and *R. donimica* (Cotton 1963, Campbell and Sinha 1976, Arbogast 1991, Jia *et al.* 2008). Due to their high fecundity, polyphagous nature, quick adaptation against insecticides, control of these pests for a long time is quiet difficult and rather impossible.

Chemical control has been the most efficient and effective means for protection of stored product insect pests, but indiscriminate use of the pesticides has led to widespread resistance in insects and other arthropod pests. Continuous and enormous use of same or similar groups of synthetic pesticides causes problem of pesticide residues in foodstuff and other environmental contamination. Moreover, synthetic insecticides are expensive for subsistence farmers and they may pose potential risks owing to the lack of adequate technical knowledge related to their safe use (Keita *et al.* 2001). This has promoted the necessity for the development of new, safe, biodegradable alternate insecticides that could be feasible and effective for insect pest management in the stored ecosystem.

Spinosad appears to be one of the most promising new grain protectant (Thompson *et al.* 1997) and derived from soil bacteria, *S. spinosa*. Spinosad has rapid contact and ingestion activity in insects of fields and stores (Sparks *et al.* 1995, Bret *et al.* 1997, Toews and Subramanyam 2003), causing excitation of the nervous system, leading to cessation of feeding and paralysis (Ghosh *et al.* 2010). Because of its low mammalian toxicity and highly favourable environmental profile (Cleveland *et al.* 2001) Spinosad was screened against the insect pests to determine its effectiveness as a grain protectant (Bret *et al.* 1997, Subramanyam *et al.* 1999, 2002, Fang *et al.* 2002a, Mutambuki *et al.* 2002). Spinosad was found to be highly effective and provide long lasting (6 months to 2 years) control of stored product insect pests on various grains (Toews and Subramanyam 2003, Nayak *et al.* 2005, Maier *et al.* 2006, Subramanyam 2006 a, b, Huang and Subramanyam 2007, Huang *et al.* 2007, Subramanyam *et al.* 2007, 2012, Daglish *et al.* 2008, Chintzoglou *et al.* 2008a, b, Vayias *et al.* 2010a, b, Ghosh *et al.* 2010, Athanassiou *et al.* 2008a, b, 2009a,b, 2010a,b 2011, Hertlein *et al.* 2011). Although Spinosad is registered in the USA at a level rate of 1ppm and its maximum residue limit (MRL) rate of 1.5ppm on stored grains, it is not yet being marketed in the USA (Athanassiou *et al.* 2010, Hertlien *et al.* 2011). Laboratory and field tests on stored wheat showed that Spinosad at 1 mg/kg of grain were effective against several insect pests including the *R. dominica*, *C. ferrugineus*, and *P. interpunctella* (Fang *et al.* 2002a,b, Flinn *et al.* 2004 Huang *et al.* 2004). Spinosad cross resistance to organophosphate pyrethroids and methoprene had not been observed against a number of stored product insects, and it was found highly effective against *R. dominica* adults, killing them within 7 days and completely suppressing the progeny production of the beetle (Subramanyam *et al.* 2012). Previous studies have shown that *R. dominica* is highly susceptible to liquid or dry Spinosad even at low rates (Huang and Subramanyam 2007, Getchell and Subramanyam 2008).

So far the effect of Spinosad on *C. pusillus* and *R. dominica* has been conducted in a very few levels in Bangladesh. The aim of this study was to evaluate the effect of Spinosad on different life stages of *C. pusillus* and *R. dominica* at different exposure periods under laboratory conditions.

## Materials and Methods

**Insects:** 2-d old eggs, 14-19d old larvae, pupae and 2d old adults of *C. pusillus* and 2d old eggs, 26-31d old larvae, pupae and 2d old adults of *R. dominica* were collected from previous established culture (Chapter 3) and were used in different tests of the present study.

**Concentrations:** The concentrations of Spinosad as 0.491, 0.983, 1.966, 3.932 and 7.863  $\mu\text{l}/\text{cm}^2$  were prepared using the method described in Chapter 3 and were used in this experiment.

**Bioassays:** Prepared concentrations treated filter papers were kept in Petri dishes (9 cm diameter) which were cleaned using by cotton with ethyl alcohol and dried immediately.

**Eggs:** Nine hundred 2d old eggs of *C. pusillus* and *R. dominica* were collected separately by sieving the food medium using the methods of Khan and Selmon (1981). Eggs were placed in Petri dishes containing filter paper either treated separately with 0.491, 0.983, 1.966, 3.932 and 7.863  $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad and distilled water only, and all the Petri dishes were covered with lid. These Petri dishes were kept in CT (Controlled Temperature room at  $30\pm 0.5^\circ\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity, without controlling light. Three replications were used for each concentration and control also. Fifty eggs were used in each replicate (N=150). The eggs were observed daily under compound microscope for the hatching of larvae. The numbers of hatched and unhatched eggs were counted every 24h up to 10 days. Egg hatching was confirmed by counting the number of 1<sup>st</sup> instar larvae. The mortality of the eggs was assessed by counting the unhatched eggs after 10 days.

**Larvae:** Three hundred sixty 14-19 d old larvae of *C. pusillus* and 26 – 31d old larvae of *R. dominica* were placed in the Petri dishes containing filter paper either treated separately with the above mentioned concentrations of Spinosad and distilled water only and the Petri dishes were covered with lid. All the Petri dishes kept in CT room at  $30\pm 0.5^\circ\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity.

Three replications were used in each concentration and control. Twenty larvae were used in each replicate (N=60). Mortality was recorded after 24-, 48- and 72h-, after treatment (HAT). Those larvae that did not move when probed or shaken in the light and mild heat considered to be dead (Yousefnezhad-Irani and Asghar 2007).

**Pupae:** The experiment was set with the pupae of *C. pusillus* and *R. dominica* in similar way as set for the egg and larval stages. Three replications were used in each concentration and control. Twenty pupae were used separately for each concentration of Spinosad (as mentioned) and control. Mortality was recorded after 24-, 48- and 72- HAT. Pupae were considered dead when they did not move by any probed and shaken in the light and mild heat (Yousefnezhad-Irani and Asghar 2007).

**Adults:** The experiments were conducted with the same concentrations of Spinosad with a control batch using 2-d old adults of *C. pusillus* and *R. dominica*. Three replications for each of the concentrations and the control were continued. The experiments were conducted in Petri dishes similarly like the eggs, larvae of pupal stages. Mortality was counted after 24-, 48- and 72- HAT. Adults were considered to be dead when probing with a hot needle failed to produce a response (Yousefnezhad-Irani and Asghar 2007).

**Data analysis:** The mortality data were corrected by Abbott's (1925) formula wherever needed, the formula is

$$P_r = \frac{P_o - P_c}{100 - P_c} \times 100$$

Where,  $P_r$  = corrected mortality (%)

$P_o$  = observed mortality (%)

$P_c$  = control mortality (%)

PRC value was calculated according to Mian and Mulla (1982) by the following formula

$$PRC = \frac{C - T}{C} \times 100$$

Where, C = No. of population in control

T = No. of population in treated media



All data were analyzed by Factorial ANOVA to compare mortality percentage as the response variables with concentrations, life stages, exposure periods. For comparison of the means Tukey's test (1953) was used. Lethal concentrations and the associated 95% limit of confidence were calculated by Probit analyses.

### **Results and Observation**

**Effect on egg hatchability:** Spinosad showed a concentration related effects on the average percentage of egg hatchability of *C. pusillus* and *R. dominica* (Figure 20 and 21, Appendix table 62 and 77).

Average percentage of egg hatchability ( $\pm$ SE) was the lowest ( $5.00\pm 1.02$ ) at  $7.863 \mu\text{l}/\text{cm}^2$  concentration and the highest ( $25.00\pm 1.15$ ) at  $0.491 \mu\text{l}/\text{cm}^2$  concentration in *C. pusillus*. At  $7.863$ ,  $3.932$ ,  $1.966$ ,  $0.983$  and  $0.491 \mu\text{l}/\text{cm}^2$  concentrations, the average percent of egg hatchability of *C. pusillus* was less than that of the control and PRC value was the highest  $88.10\%$  at  $7.863 \mu\text{l}/\text{cm}^2$  and the lowest was  $40.48\%$  at  $0.491 \mu\text{l}/\text{cm}^2$  (Appendix Table 62). The effect of different concentrations on egg hatchability was found highly significant ( $P < 0.001$ ) (Appendix table 63).

In case of *R. dominica*, average percentage of egg hatchability ( $\pm$ SE) was lowest  $0.33\pm 1.03$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentrations and highest  $15.00\pm 1.14$  at  $0.491 \mu\text{l}/\text{cm}^2$  concentrations. At  $7.863$ ,  $3.932$ ,  $1.966$ ,  $0.983$  and  $0.491 \mu\text{l}/\text{cm}^2$  concentrations, the average percent of egg hatchability was significantly less than that of the control and PRC value was the highest  $99.13\%$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentrations whereas lowest  $60.53\%$  at  $0.491 \mu\text{l}/\text{cm}^2$  concentrations (Appendix table 77). The effect of different concentrations on egg hatchability was found highly significant ( $P < 0.001$ ) (Appendix table 78).




Figure 20 Average (%) hatchability of *C. pusillus* on different concentrations of Spinosad.




Figure 21 Average (%) hatchability of *R. dominica* on different concentrations of Spinosad.

**Toxicity on larvae:** The larval mortality of *C. pusillus* was observed on prepared concentrations of Spinosad after 24-, 48- and 72 hours after treatment (HAT) and the results of the experiments along with statistical analyses are shown in Figure 22, Table 2 and Appendix table 64-66, 74. All the Spinosad concentrations by contact were found to be toxic to the larvae compare to control. Toxicity of Spinosad was increased with the increase of concentration and exposure time. There were significant differences in the mean mortality of larvae between exposure periods ( $F=58.038$ ,  $df=2$ ,  $P<0.0001$ ) and between concentrations ( $F=38$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure periods and concentration was significant (Appendix table 74).  $LC_{50}$  at 24-h was 18.208, 48-h was 5.912 and 72-h was 0.175  $\mu\text{l}/\text{cm}^2$  Figure 15 (Figure 28, Appendix Table 73).

In case of *R. dominica*, the larval mortality was observed on prepared concentrations of Spinosad after 24, 48 and 72 h of exposure and the results statistical analyses are shown in Figure 23, Table 3 and Appendix tables 79-81, 89. All the concentrations acted as larvicide by contact. Average mortality ( $\pm\text{SE}$ ) was highest  $13.33\pm 0.88$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentration after 72 h and lowest  $4.67\pm 0.33$  at  $0.491 \mu\text{l}/\text{cm}^2$  concentrations after 24 h of exposure (Table 3). There were significant differences in the mean mortality of larvae between exposure times ( $F=57.026$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=56.006$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure time and concentration was significant ( $F=7.795$ ,  $df=10$ ,  $P<0.001$ ) (Appendix table 89).  $LC_{50}$  at 24-h was 9.22978, 48 h was 2.835366 and 72 h was  $0.5433412 \mu\text{l}/\text{cm}^2$  (Figure 28, Appendix table 88).




Figure 22 Average mortality of *C. pusillus* larvae on different concentrations of Spinosad after 24, 48 and 72 h period of exposure




Figure 23 Average mortality of *R. dominica* larvae on different concentrations of Spinosad after 24, 48 and 72 h period of exposure

**Toxicity on pupae:** Pupal mortality of *C. pusillus* at different concentrations of Spinosad 24-, 48- and 72 HAT was observed and the results were shown in Figure 24, Table 2 and Appendix tables 67-69, 75. The concentrations were found to be effective causing pupal mortality by contact action. compare to control. Average mortality ( $\pm$ SE) was highest  $8.33\pm 0.88$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentration after 72 h and lowest was  $1.67\pm 0.33$  at  $0.491 \mu\text{l}/\text{cm}^2$  concentration after 24 h of exposure (Table 2). There were significant differences in the mean mortality between exposure periods ( $F=30.79$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=61.524$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration was significant ( $F=2.558$ ,  $df=10$ ,  $P<0.001$ ) (Appendix table 75).  $LC_{50}$  at 24-h was 568.5706 , 48 h was 1841.139 and 72 h was 35.94058  $\mu\text{l}/\text{cm}^2$  (Figure 28, Appendix Table 73).

Pupal mortality of *R. dominica* at different concentrations of Spinosad after 24, 48 and 72 h of exposure was observed on and the results were shown in Figure 25, Table 3 and Appendix table 82-84,90. The tested concentrations were found to be potential causing pupal mortality by contact compared to control. Average mortality ( $\pm$ SE) was highest  $8.33\pm 1.45$  at  $7.863 \mu\text{l}/\text{cm}^2$  concentration after 72 h and lowest  $1.00\pm 0.58$  at  $0.491 \mu\text{l}/\text{cm}^2$  concentration after 24 h of exposure (Table 3). There were significant differences in the mean mortality between exposure periods ( $F=32.986$ ,  $df=2$ ,  $P<0.001$ ) and as well as between concentrations ( $F=23.986$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure periods and concentration was significant ( $F=4.622$ ,  $df=10$ ,  $P<0.001$ ) (Appendix table 90).  $LC_{50}$  at 24-h was 1138.777, 48 h was 231.1335 and 72 h was 22.0538  $\mu\text{l}/\text{cm}^2$  (Figure 28, Appendix table 88).




Figure 24 Average mortality of *C. pusillus* pupae on different concentrations of Spinosad after 24, 48 and 72 h period of exposure




Figure 25 Average mortality of *R. dominica* pupae on different concentrations of Spinosad after 24, 48 and 72 h period of exposure

**Toxicity on adults:** At all tested concentrations of Spinosad, adult mortality of *C. pusillus* were higher than that of larval and pupal stages (Table 2). Adult mortality of *C. pusillus* on different concentrations of Spinosad after 24-, 48- and 72 HAT was observed and the results with their statistical analyses are presented in Figures 26, Table 2 and Appendix tables 70-72, and 76. The concentrations were found to be potential causing adult mortality based on the contact compare to control. Average mortality ( $\pm$ SE) was highest  $15.33\pm 1.22$  at  $7.863\mu\text{l}/\text{cm}^2$  after 72 h and lowest was  $5.00\pm 0.58$  at  $0.491\mu\text{l}/\text{cm}^2$  after 24 h of exposure (Table 2). There were significant differences in the mean mortality of adults between exposure periods ( $F=202.970$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=42.617$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration was significant ( $F=8.350$ ,  $df=10$ ,  $P<0.001$ ) (Appendix table 76). The  $LC_{50}$  values after 24- h was 7.995, 48- h was 2.145 and 72- h was  $0.839\mu\text{l}/\text{cm}^2$  (Figure 28, Appendix table 73).

The tested concentrations of Spinosad, 2d old adult mortality of *R. dominica* were higher than that of larval and pupal stages (Table 3). Adult mortality of *R. dominica* on different concentrations of Spinosad after 24, 48 and 72 h of exposure was observed and the results with statistical analyses were shown in Figure 27, Table 3 and Appendix table 85-87, 91. Different concentrations were found to be potential causing adult mortality by contact compare to control. Average mortality ( $\pm$ SE) was highest  $17.33\pm 1.20$  at  $7.863\mu\text{l}/\text{cm}^2$  concentrations after 72 h and lowest  $6.67\pm 0.88$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations after 24 h of exposure (Table 3). There were significant differences in the mean mortality of adults between exposure periods ( $F=36.122$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=83.468$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure time and concentration was significant ( $F=2.017$ ,  $df=10$ ,  $P<0.001$ ) (Appendix table 91).  $LC_{50}$  at 24-h was 6.951654, 48 h was 0.9590641 and 72 h was  $0.466328\mu\text{l}/\text{cm}^2$  (Figure 28, Appendix table 88). Spinosad showed a concentration related effects on adult mortality. The potentiality was higher in all treatments with the increase of concentrations and exposure periods.




Figure 26 Average mortality of *C. pusillus* adults on different concentrations of Spinosad after 24, 48 and 72 h period of exposure.




Figure 27 Average mortality of *R. dominica* adult on different concentrations of Spinosad after 24, 48 and 72 h period of exposure



Table 2 Mortality (mean±SE) of 14-19d larvae, pupae and 2d adults of *C. pusillus* at different concentrations of Spinosad after different exposure periods.

| Exposure periods (h) | Concentrations ( $\mu\text{l}/\text{cm}^2$ ) | Mortality (mean $\pm$ SE) |       |             |       |              |       |
|----------------------|--|---------------------------|-------|-------------|-------|--------------|-------|
|                      |  | Larvae                    | PRC   | Pupae       | PRC   | Adults       | PRC   |
| 24                   | Control                                      | 0.00±0.00c                | -     | 0.00±0.00c  | -     | 0.00±0.00d   | -     |
|                      | 0.491  | 3.33±0.88b                | 16.65 | 1.67±0.33bc | 8.35  | 5.00±0.58c   | 25.00 |
|                      | 0.983  | 4.67±0.67b                | 23.35 | 2.33±0.33ab | 11.65 | 6.00±0.58c   | 30.00 |
|                      | 1.966  | 5.67±0.33ab               | 28.35 | 3.00±0.58ab | 15.00 | 6.67±0.67bc  | 33.35 |
|                      | 3.932  | 7.33±0.33a                | 36.65 | 3.33±0.33ab | 16.65 | 9.00±0.58ab  | 45.00 |
|                      | 7.863  | 8.00±0.58a                | 40.00 | 4.00±0.58a  | 20.00 | 10.00±0.058a | 50.00 |
| 48                   | Control                                      | 0.00±0.00b                | -     | 0.00±0.00c  | -     | 0.00±0.00d   | -     |
|                      | 0.491  | 6.67±0.67a                | 33.35 | 3.33±0.67b  | 16.65 | 7.33±0.33c   | 36.65 |
|                      | 0.983  | 8.33±1.33a                | 41.65 | 4.00±0.58b  | 20.00 | 8.33±0.33bc  | 41.65 |
|                      | 1.966  | 9.00±0.58a                | 45.00 | 4.67±0.33ab | 23.35 | 9.33±1.45abc | 46.65 |
|                      | 3.932  | 9.67±0.88a                | 48.35 | 5.33±0.33ab | 26.65 | 11.67±0.88ab | 58.35 |
|                      | 7.863  | 10.00±0.58a               | 50.00 | 6.33±0.33a  | 31.65 | 12.67±1.20a  | 63.35 |
| 72                   | Control                                      | 0.00±0.00b                | -     | 0.00±0.00c  | -     | 0.00±0.00c   | -     |
|                      | 0.491  | 10.67±0.67a               | 53.35 | 5.00±0.58b  | 25.00 | 9.33±0.33b   | 46.65 |
|                      | 0.983  | 12.33±0.33a               | 61.65 | 5.67±0.67ab | 28.35 | 10.00±0.00b  | 50.00 |
|                      | 1.966  | 13.00±1.00a               | 65.00 | 6.33±0.33ab | 31.65 | 10.67±0.88b  | 53.35 |
|                      | 3.932  | 13.33±1.76a               | 66.65 | 7.00±0.58ab | 35.00 | 14.00±0.58a  | 70.00 |
|                      | 7.863  | 14.00±2.00a               | 70.00 | 8.33±0.88a  | 41.65 | 15.33±1.22a  | 76.65 |

Note: Means with same letter do not significantly differed from each other (Tukey's Test)

Table 3 Mortality (mean±SE) of 26-31d larvae, pupae and 2d adults of *R. dominica* at different concentrations of Spinosad after different exposure periods

| Exposure periods (h) | Concentrations ( $\mu\text{l}/\text{cm}^2$ ) | Mortality (mean $\pm$ SE) |       |             |       |              |       |
|----------------------|--|---------------------------|-------|-------------|-------|--------------|-------|
|                      |  | Larvae                    | PRC   | Pupae       | PRC   | Adults       | PRC   |
| 24                   | Control                                      | 0.00±0.00c                | -     | 0.00±0.00a  | -     | 0.00±0.00b   | -     |
|                      | 0.491  | 4.67±0.33b                | 23.35 | 1.00±0.58ab | 5.00  | 6.67±0.88a   | 33.35 |
|                      | 0.983  | 5.00±0.58b                | 25.00 | 2.67±1.20ab | 13.35 | 7.67±0.88a   | 38.35 |
|                      | 1.966  | 6.67±0.88ab               | 33.35 | 2.33±0.33ab | 11.65 | 8.67±0.88a   | 43.35 |
|                      | 3.932  | 9.00±0.58a                | 45.00 | 2.67±0.33ab | 13.35 | 9.33±0.67a   | 46.65 |
|                      | 7.863  | 9.33±0.67a                | 46.65 | 3.00±0.58a  | 15.00 | 10.00±0.58a  | 50.00 |
| 48                   | Control                                      | 0.00±0.00b                | -     | 0.00±0.00b  | -     | 0.00±0.00d   | -     |
|                      | 0.491  | 8.33±0.33a                | 41.65 | 2.67±0.88ab | 13.35 | 9.00±0.58c   | 45.00 |
|                      | 0.983  | 9.00±0.58a                | 45.00 | 3.33±1.20ab | 16.65 | 10.00±0.58bc | 50.00 |
|                      | 1.966  | 9.67±0.88a                | 48.35 | 4.33±0.33a  | 21.65 | 10.33±0.88bc | 51.65 |
|                      | 3.932  | 10.33±0.33a               | 51.65 | 4.67±0.67a  | 23.35 | 13.33±0.88ab | 66.65 |
|                      | 7.863  | 11.00±1.00a               | 55.00 | 5.33±0.67a  | 26.65 | 14.00±1.00a  | 70.00 |
| 72                   | Control                                      | 0.00±0.00c                | -     | 0.00±0.00a  | -     | 0.00±0.00d   | -     |
|                      | 0.491  | 10.00±0.58b               | 50.00 | 4.67±0.88b  | 23.35 | 11.00±0.58c  | 55.00 |
|                      | 0.983  | 10.67±0.67ab              | 53.35 | 6.00±1.55b  | 30.00 | 12.00±0.58c  | 60.00 |
|                      | 1.966  | 11.67±0.88ab              | 58.35 | 6.67±0.33b  | 33.35 | 13.33±0.88bc | 66.65 |
|                      | 3.932  | 12.67±0.33ab              | 63.35 | 7.33±0.67b  | 36.65 | 16.33±0.88ab | 81.65 |
|                      | 7.863  | 13.33±0.88a               | 66.65 | 8.33±1.45b  | 41.65 | 17.33±1.20a  | 86.65 |

Note: Means with same letter do not significantly differed from each other (Tukey's Test)




Figure 28 Regression lines of probit mortality on log concentration of Spinosad on *C. pusillus* (A = larvae, B = pupae and C = adults) and *R. dominica* (D = larvae, E = pupae and F = adult).

## Discussion

Results of the present experiments revealed that there were significant impacts of the contact activity different concentrations of Spinosad and exposure periods against egg hatchability of *C. pusillus* and *R. dominica*. Spinosad concentrations were found to be toxic against 14-19 d old larvae, pupae and 2 d old adults of *C. pusillus* and 2d old eggs, 26-31d old larvae, pupae and 2d old adults of *R. dominica*. Adults were the most susceptible in comparison with that of larvae and pupae at concentration and longest exposure period. Mortality of pupae was found the least number followed by larvae and adults. Egg hatchability was found to be dependent on the concentration. Similar effects of Spinosad have been reported on other stored-product insects by Mutambuki *et al.* (2003), Chintzoglou *et al.* (2008a, b), Aarthi and Murugan (2010), Athanassiou *et al.* (2010a,b), Mollaie *et al.* (2011).

Naturally, eggs of *R. dominica* are laid singly or in groups/clusters on the exterior of the kernel (Potter 1935). Eggs hatch and the active neonate bores inside the kernel, where it completes development up to the adult stage (Howe 1950, Arbogast 1991). Upon reaching the adult stage, *R. dominica* emerges from the kernel and creates a large exit hole (Potter 1935, Rees 1995). Triflumuron caused 100% egg mortality of *O. surinamensis*, *R. dominica* and *T. castaneum* when they were exposed for four weeks (Mian and Mulla 1982a). Similar results were reported by Mazid *et al.* (2006), Eisa *et al.* (1986), Saxena and Mathur (1981 a, b) and Saxena and Kumar (1989).

LC<sub>50</sub> values of Spinosad against the larvae of *C. pusillus* and *R. dominica* 24-, 48-, and 72 HAT were 18.208, 5.912 and 0.1755 and 9.230, 2.835 and 0.543 $\mu$ l/cm<sup>2</sup> respectively, revealed that this bacterial insecticide is quite potent to kill the larvae at very low concentration, but will require a longer exposure (72-h). Mortality of 50 and 70% were achieved after 48- and 72 h. The toxic effect of Spinosad begun during 48-h of exposure. As the treatments were given by contact, probably an oral treatment with Spinosad would be able to produce higher rate of mortality in the larvae at more lower concentrations and shorter exposure periods.

It was reported that *E. kuehniella* larvae were more susceptible to Spinosad compared to *P. interpunctella* larvae. Spinosad at the concentrations of 0.1, 0.25, 0.5, 0.75 and 1 mg/kg completely suppressed larval survival of *E. kuehniella* (Mollaie *et al.* 2011). Spinosad at (1 mg/kg) resulted 95% suppression of larval survival and adult emergence of *P. interpunctella* was achieved. On the contrary, Spinosad at 0.1 mg/kg resulted 100% larval mortality of *E. kuehniella*. Differences in toxicity of Spinosad was recorded on the might be due different commodity used as pest food (Fang *et al.* 2002a, Chintzoglou *et al.* 2008a,b). Fang *et al.* (2002a), Huang *et al.* (2007), Huang and Subramanyam (2007), reported that susceptibility of *P. interpunctella* larvae to Spinosad was dose dependent. Toews and Subramanyam (2003) reported that mortality of *T. castaneum* was increased with increasing the concentrations of Spinosad by contact treatment. In addition, the mortality of adults in all concentrations was dependent to exposure time, and 72 HAT caused the highest mortality. The application rates of 0.1 and 0.5 ppm Spinosad gave 83 and 100% mortality respectively of *Cryptolestes* spp on Spinosad- treated maize (Huang and Subramanyam 2007). Bond *et al.* (2004) reported that the naturally derived insecticide Spinosad is highly toxic to *Aedes* and *Anopheles* mosquito larvae. Cetin *et al.* (2005) worked on the evaluation of the naturally derived insecticide Spinosad against *Culex pipiens* L. (Diptera: Culicidae) larvae in septic tank water in Antalya. Additional studies have reported the larvicidal properties of Spinosad in this and other mosquito species (Liu *et al.* 2004a, b, Cetin *et al.* 2005 b, Darriet *et al.* 2005, Darriet and Corbel 2006 and Romi *et al.* 2006).

As pupa is the non-feeding stage of *C. pusillus* and *R. dominica* only contact treatment is possible to give. As a whole the pupal stage was found to be comparatively tolerant (PRC value was <50% at maximum concentration and longer exposure) to Spinosad treatment. To achieve more toxic effect against the pupae of *C. pusillus* and *R. dominica* more higher concentrations of Spinosad have to be applied. There is a lack of literature reporting the Spinosad

toxicity at the pupal stages of stored product insects, so the present result is quite difficult to compare.

Bonjur *et al.* (2011) conducted field experiments with 0, 25, 50 and 70 ppm concentrations of ozone in steel bins containing wheat against seven stored grain pests after and found that adult pupae of *P. interpunctella* were more susceptible to those concentrations after 1, 2, 3 and 4 d of exposure. Kovendan *et al.* (2012) found that pupal mortality of *Aedes aegypti* was 12% by the treatment of Spinosad at 20 ppm and it has been increased to 64% at 100 ppm after 24 h and the LC<sub>50</sub> value of pupae was 93.44 ppm. The above results are more or less similar to the present findings.

Athanassiou *et al.* (2010a, b) evaluated adult mortality of *Cryptolestes* spp on 0.1 and 0.5 ppm Spinosad treated wheat and recorded 86.7±3.3 and 97.80±2.2 % mortal effect respectively after 14 days, however, the mortality of control adults was 26.70±5.8 %. In the present study the PRC values were 50, 63.35 and 76.65 at the highest concentration of Spinosad (7.863 µl/cm<sup>2</sup>) exposed 72-h. The higher concentrations needed in the present study might be due to the contact treatment and lower exposure (72 h compared to 14d).

Subramanyam *et al.* (1999) carried out an experiment to establish the efficacy of 1, 3, 6, 10, 15 and 20 mg/kg concentrations of Spinosad on wheat after 8 and 14 d of exposure and found that the mortality of *R. dominica* adults was 100%. Fang *et al.* (2002a) found 100% mortality of *R. dominica* adults on wheat treated with 1 ppm of Spinosad after 7 days of exposure. For instance, Toews and Subramanyam (2003) reported that *T. castaneum* was by far more tolerant to Spinosad than *R. dominica* and *S. oryzae*. Similar results have also been reported by other researchers (Huang *et al.* 2004, Nayak *et al.* 2005, Getchell 2006). Daghish and Nayak (2006) reported that Spinosad residues were stable for 9 months on wheat, without loss of insecticidal activity against *R. dominica*. In another study, Daghish *et al.* (2006) found that Spinosad applied at 0.5 or 1mg/kg was completely effective for 9months at both 55 and 70% RH, with 100% adult mortality of *R. dominica* after 14 days of exposure and no live f<sub>1</sub> adults produced.

Arthur (2004a, b) reported mortality of *R. dominica* adults exposed to dust and liquid formulations of methoprene. Athanassiou *et al.* (2008a) found that at 0.01ppm of Spinosad at 30°C temperature and 75% relative humidity after 7, 14 and 21 d of exposure average percent mortality of *R. dominica* ( $\pm$  SE) was achieved  $55.6 \pm 7.0$ ,  $84.5 \pm 8.1$  and  $94.4 \pm 2.2$  respectively. An another experiment, Athanassiou *et al.* (2010a) evaluated the efficacy of 0.1 and 0.5 ppm concentrations of Spinosad against adults of *R. dominica* on wheat after 14 d of exposure and found that average percent mortality of *R. dominica* ( $\pm$  SE) were  $100.0 \pm 0.0$  and  $100.0 \pm 0.0$  respectively whereas  $3.3 \pm 1.7$  mortality was in control. *C. maculatus* appears to be highly susceptible to Spinosad at a low rate of 0.3 ppm (Sanon *et al.* 2010). The present findings are similar to the above results.

The present results indicate that Spinosad is an effective tool to control all the life stages of *C. pusillus* and *R. dominica* the degree of toxicity of Spinosad can be ranked as eggs>adults > larvae> pupae. So, it can be concluded that low concentrations of Spinosad would be potential to control *C. pusillus* and *R. dominica* in storage system.



## **Chapter 6**

### **Effects of Spinosad on *X. flavipes***



## Introduction

Among the predatory bugs, *X. flavipes* is more stout bodied cosmopolitan insect and one of the most challenging efficient predator of many insect pests in storage commodities (Gross 1954, Arbogast 1979, Brower *et al.* 1996 and Imamura *et al.* 2008). This predacious bug successfully controls the population of small insect pests of storage particularly by sucking fluids of eggs and early instar larvae that are neither heavily sclerotized nor overly hirsute (Lecato and Davids 1973, Sing and Arbogast 2008a,b). This bug has already been commercialized in North-America and is marketed for biocontrol of stored product insects (Mason and Hubner 2001).

There is limited evidence to suggest that *X. flavipes* is more pesticide-tolerant than parasitoids and pest insects. Baker and Arbogast (1995) reported *X. flavipes* to be 4-fold and 10-fold more tolerant to malathion than *A. calandreae* and *H. hebetor*, respectively. Press *et al.* (1978) reported that *X. flavipes* generally exhibited greater tolerance to the insecticides permethrin, fenitrothion, pirimiphos-methyl, pyrethrins\_piperonyl butoxide, and malathion than three prey species, including *T. castaneum*, *L. serricornis* and *P. interpunctella*.

Use of synthetic pesticides causes some unfortunate consequences such as environmental pollution, pests/hosts resistance and toxicity to other non-target organisms including human beings, biological pesticides from microbial origin are environmentally safe pesticides. Among microbial insecticides, Spinosad is specially valuable because its non-toxicity to non-target animals and human beings (Aarthi and Murugan 2010). In field crop markets, where it has been sold since 1997, Spinosad is minimally disruptive to beneficial insects and compatible with Integrated Pest Management (IPM) programs in many crops (Miles 2006 and Arthur *et al.* 2007). A portion of Spinosad's selectivity in crop markets derives from its intrinsic toxicity profile relative to beneficial insects, which can vary by taxa, but with Spinosad generally being less toxic to predators than to parasitoids (Michaud 2003 and Williams *et al.* 2003). A second important factor contributing to

Spinosad's favorable selectivity is its relatively transient presence in the environment due to photolytic breakdown. Spinosad's impact on beneficial insect populations under field conditions are typically short lived and followed by rapid recovery (Williams *et al.* 2003 and Miles and Eelen 2006). However, in grain storage environments where sunlight is not present, Spinosad's residual efficacy has been shown to be much longer, on the order of six months to two years. Therefore, Spinosad's impact on beneficial insects can be quite different in grain versus crop environments. In a laboratory study, Toews and Subramanyam (2004) found that Spinosad applied to stored wheat at 1 ppm was highly toxic to the parasitoids *H. hebetor*, *T. elegans* and *A. calandreae* yet not so to *X. flavipes*, which demonstrated 92% survival and was able to reproduce under these same conditions. The findings from this laboratory study were subsequently supported by field bin trials conducted by Parker *et al.* (2004a and 2004b) in stored sorghum and Parker and Falconer (2004, 2005, 2006 and 2007) in stored corn, where they showed no survival of the parasitoid *A. calandreae* and only limited survival of the parasitoid *C. elegans* when grain was treated with Spinosad at 1 ppm and parasitoid populations were monitored over storage periods ranging from 10 to 24 months. However, populations of *X. flavipes* remained relatively unaffected by Spinosad in the similar sorghum bin study. These results suggest *X. flavipes* can survive and reproduce in grains treated with Spinosad at rates up to 1 ppm, whereas parasitoid populations will be markedly reduced due either to the direct toxicity of Spinosad or indirectly through Spinosad's impact on their host species. Spinosad is likely to be no worse than many other grain protectants with respect to its impact on beneficial species.

Spinosad appears to be very compatible with many predatory insects of the crop field like green lacewing (*Chrysoperla carnea*), ladybird beetle (*Hippodamia convergens*), minute pirate bug (*Orius laevigatus*), big-eyed bug (*Geocoris punctipes*), and damsel bug (*Nabis* spp.) (Thompson *et al.* 2000). Moreover, Spinosad is safe to nymphs and adults of many natural enemies including

*X. flavipes* (Ghosh *et al.* 2010). Previous research has focused the effects of Spinosad on many natural enemies or beneficial insects (Schoonover and Larson 1995, Bret *et al.* 1997, Boucher 1999, Tillman and Mulrooney 2000, Thompson *et al.* 2000, Consoli *et al.* 2001, Mason *et al.* 2002, Williams *et al.* 2003, Michaud 2003, Towes and Subramanyam 2004, Wang *et al.* 2005, Subramanyum *et al.* 2007, Daglish *et al.* 2008, Ghosh *et al.* 2010) whereas, very few experiments have yet been conducted to explore the effects of Spinosad on *X. flavipes*. Therefore, the present investigation was undertaken to evaluate the stage specific susceptibility of *X. flavipes* to several concentrations of Spinosad at different exposure periods in the laboratory condition which are likely to be compatible with stored product ecosystems that make the powerful and well Integrated Pest Management strategies.

#### **Materials and Methods:**

**Insects:** 2d old eggs, 4d old nymphs and 2d old adults of *X. flavipes* were collected from the stock culture (Chapter 3) and used in the present experiments.

**Concentrations used:** The concentrations of Spinosad applied to the pests *C. pusillus* and *R. dominica*, were also used in this experiment to observe that the applicable dosages for the pest control is either affect the predator or not.

**Bioassays:** Concentration treated filter papers were kept in Petri dishes (9 cm diameter) which were cleaned by cotton with ethyl alcohol and dried immediately.

**Eggs:** Nine hundred 2d old eggs of *X. flavipes* were collected by sieving the food medium using according to Khan and Selmon (1981). Eggs were placed in Petri dish containing filter paper either treated separately with 0.491, 0.983, 1.966, 3.932 and 7.863 $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad and distilled water only, and Petri dishes were covered with lid. The petri dishes were kept in CT (Controlled temperature) room at  $30\pm 0.5^\circ\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity, Three replications were used for each concentration and control. Fifty eggs were used in each replicate (N=150). The egg was observed daily under compound microscope until hatching. The numbers of hatched and unhatched eggs were

counted every 24h up to 10 days. Eggs hatching were confirmed by counting the number of 1<sup>st</sup> instar nymphs. The mortality of eggs was assessed by counting the unhatched eggs after 10 days.

**Nymphs:** Three hundred sixty 4d old nymphs of *X. flavipes* were placed in the Petri dishes containing filter paper either treated separately with prepared concentrations of Spinosad or distilled water only and the Petri dishes were covered with lid. All Petri dishes kept in CT room at  $30\pm 0.5^{\circ}\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity. Three replications were carried out in each concentration and control. Twenty nymphs were used in each replicate (N=60). Mortality was recorded after 24,- 48 and 72h after post treatment. Those nymphs that did not move when probed or shaken in the light and mild heat considered to be dead (Yousefnezhad-Irani and Asghar 2007).

**Adults:** The experiment was conducted with the same concentrations of Spinosad, with a control batch using 2d old adults in three replication for each of the concentrations and the control. The experiment was conducted in Petri dishes similarly like the egg and nymphal stages. Mortality was counted after 24, 48 and 72 HAT. Adults were considered to be dead when probing with a hot needle failed to produce a response (Yousefnezhad-Irani and Asghar 2007).

**Data analysis:** The mortality data were corrected by Abbott's (1925) formula. The data were analyzed by Factorial ANOVA to compare mortality percentage as the response variable and concentrations, life stages and exposure periods. For the comparison of means the Tukey's test (1953) was used. Lethal concentrations and the associated 95% limit of confidence were calculated by Probit analyses. PRC values were calculated according to the formula of Mian and Mulla (1982a).

## **Results and Observation**

**Effects on egg hatchability:** Spinosad inhibited egg hatchability of *X. flavipes* at all concentrations (Figure 29, Appendix table 92). In average 25-35% eggs of the predator were hatched. The hatchability was higher in all treatments with the increase of concentrations. Egg hatchability was decreased with the increased concentrations, and the PRC values ranged from 2.86-28.57 (Appendix table 92).

The effect of different concentrations on egg hatchability was found significant ( $P < 0.001$ ) (Appendix table 93).

**Toxicity on nymphs:** 4d old nymphs of *X. flavipes* were used and mortality recorded on different concentrations of Spinosad after 24, 48 and 72 h of exposure. The findings with statistical analyses are shown in Figure 30, Table 4, and Appendix tables 94-96 and 101. Different concentrations were found to be potential causing very few nymphal mortality based on the contact treatment compare to control (Table 4). Average percent mortality ( $\pm$ SE) was highest  $6.67 \pm 1.76$  at  $7.863 \mu\text{l}/\text{cm}^2$  after 72 h and lowest was  $1.00 \pm 0.58$  at  $0.491 \mu\text{l}/\text{cm}^2$  after 24 h of exposure (Table 4). At 95% confidence limit lower to upper 24 h  $LC_{50}$  was 432.6535 (2.922949-237196.1), 48 h  $LC_{50}$  was 137.838 (3.740582-5079.244) and 72 h  $LC_{50}$  was  $73.82966 \mu\text{l}/\text{cm}^2$  (3.22157-1691.976) respectively (Figure 32, Appendix table 100). There were significant differences in the mean mortality of larvae between exposure periods ( $F=37.587$ ,  $df=2$ ,  $P < 0.001$ ) and between concentrations ( $F=12.611$ ,  $df=5$ ,  $P < 0.001$ ). In addition, the interaction between exposure periods and concentration was significant ( $F=5.460$ ,  $df=10$ ,  $P < 0.001$ ) (Appendix table 101). Moreover, Nymphal mortality was found higher than that of adults (Table 4).

**Toxicity on adults:** Two day old adult mortality of *X. flavipes* were found less than that of nymphal stages at all tested concentrations of Spinosad (Table 4). Adult mortality of *X. flavipes* on different concentrations of Spinosad after 24, 48 and 72 h of exposure and the statistical analyses were shown in Figure 31, Table 4 and Appendix table 97-99 and 102. The tested concentrations were found to be effective causing adult mortality based on the ingestion and contact compare to control. Average percent mortality ( $\pm$ SE) was highest  $5.00\pm 0.45$  at  $7.863\mu\text{l}/\text{cm}^2$  concentrations after 72 h and lowest  $1.67\pm 0.67$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations after 24 h of exposure (Table 4). At 95% confidence limit lower to upper 24 h  $\text{LC}_{50}$  was 492.8509 (3.859698-62932.93), 48 h  $\text{LC}_{50}$  was 348.9742 (4.223628-28833.73) and 72 h  $\text{LC}_{50}$  was  $331.5098\mu\text{l}/\text{cm}^2$  (2.651994-41440.03) respectively (Figure 32, Appendix table 100). There were significant differences in the mean mortality of adults between exposure periods ( $F=7.386$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=5.219$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration was significant ( $F=2.432$ ,  $df=10$ ,  $P<0.001$ )

(Appendix table 102). Spinosad showed a concentration related effects on adult mortality. The potentiality was higher in all treatments with the increase of concentrations and exposure periods. Moreover, at 0.491, 0.983 and 1.966 $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad, after 24 h to 72 h of exposure survivability of *X. flavipes* adults were found range 94 to 84% respectively (Table 4).

Table 4 Effects of different concentrations of Spinosad on 4d nymphs and 2d adults of *X. flavipes* at different exposure periods.

| Exposure periods (h) | Concentrations ( $\mu\text{l}/\text{cm}^2$ ) | Mortality (mean $\pm$ SE) |       |                   |       |
|----------------------|--|---------------------------|-------|-------------------|-------|
|                      |  | Nymphs                    | PRC   | Adults            | PRC   |
| 24                   | Control                                      | 0.00 $\pm$ 0.00a          | -     | 0.00 $\pm$ 0.00b  | -     |
|                      | 0.491  | 1.00 $\pm$ 0.58ab         | 5.00  | 1.67 $\pm$ 0.67a  | 8.35  |
|                      | 0.983  | 1.33 $\pm$ 0.67ab         | 6.65  | 1.33 $\pm$ 0.33a  | 6.65  |
|                      | 1.966  | 1.67 $\pm$ 0.33ab         | 8.35  | 2.00 $\pm$ 0.05a  | 10.00 |
|                      | 3.932  | 2.33 $\pm$ 0.33a          | 11.65 | 2.67 $\pm$ 0.33a  | 13.35 |
|                      | 7.863  | 3.00 $\pm$ 0.58a          | 15.00 | 3.33 $\pm$ 0.33a  | 16.65 |
| 48                   | Control                                      | 0.00 $\pm$ 0.00c          | -     | 0.00 $\pm$ 0.00d  | -     |
|                      | 0.491  | 2.33 $\pm$ 0.33b          | 11.65 | 1.33 $\pm$ 0.33cd | 6.65  |
|                      | 0.983  | 3.33 $\pm$ 0.67ab         | 16.65 | 2.00 $\pm$ 0.03bc | 10.00 |
|                      | 1.966  | 4.00 $\pm$ 0.08ab         | 20.00 | 2.33 $\pm$ 0.33bc | 11.65 |
|                      | 3.932  | 5.00 $\pm$ 0.03a          | 25.00 | 3.00 $\pm$ 0.03ab | 15.00 |
|                      | 7.863  | 5.33 $\pm$ 0.88a          | 26.65 | 4.00 $\pm$ 0.58a  | 20.00 |
| 72                   | Control                                      | 0.00 $\pm$ 0.00b          | -     | 0.00 $\pm$ 0.00d  | -     |
|                      | 0.491  | 3.33 $\pm$ 0.33ab         | 16.65 | 2.00 $\pm$ 0.05c  | 10.00 |
|                      | 0.983  | 4.00 $\pm$ 0.58a          | 20.00 | 3.00 $\pm$ 0.58bc | 15.00 |
|                      | 1.966  | 5.00 $\pm$ 0.58a          | 25.00 | 3.33 $\pm$ 0.33bc | 16.65 |
|                      | 3.932  | 6.00 $\pm$ 0.04a          | 30.00 | 3.67 $\pm$ 0.33ab | 18.35 |
|                      | 7.863  | 6.67 $\pm$ 1.76a          | 33.35 | 5.00 $\pm$ 0.45a  | 25.00 |

Note: Means with same letter do not significantly differed from each other (Tukey's Test)



**Figure 32** Regression lines of probit mortality on log concentration of Spinosad on *X. flavipes* (A = nymphs and B = adults).

## Discussion

Due to the very low mammalian toxicity (Breslin *et al.* 2000) and rapid breakdown in the environment (Cleveland *et al.* 2002, Thompson *et al.* 2002), there can be little doubt that Spinosad represents an important improvement over conventional synthetic pesticides in terms of safety to farm workers, traders and the consumers of pesticide-treated agricultural post harvest cereal, grain products and other stored commodities. In total, there were 228 observations on the impact of Spinosad on 52 species of natural enemies of which 162 involved predators (27 species) and 66 involved parasitoids (25 species) where as 71% (42/59) of laboratory studies and 79% (81/103) of field-type studies were conducted on predators in which Spinosad was not harmful to predators (Williams *et al.* 2003). As Spinosad appears to have low toxicity to many beneficial insects (Elzen *et al.* 1998), it has potential for use in Integrated Pest Management (IPM) systems. In the present study, it is clear that there is no impact of 0.491, 0.983 and 1.966 $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad on egg hatchability, survivability of nymphs and adults of the predator, *X. flavipes* in comparison with the control. The results showed that egg hatchability of *X. flavipes* was almost similar the control at lower three concentrations of Spinosad after 10 d of exposure. Previous studies suggesting the safety of Spinosad to eggs of Chrysopids employed topical applications and did not assay consumption by active life stages.

Schoonover and Larson (1995) found that  $\text{LC}_{50}$  of the predator, *Orius insidiosus* nymph was 200 ppm, Torres *et al.* (1999) found that  $\text{LC}_{50}$  of the predator, *Podisus nigrispinus* nymph was 45 ppm and Vinuela *et al.* (1998) found that  $\text{LC}_{50}$  of *P. maculiventris* nymph was 33 ppm respectively to moderate concentrations (30-200 ppm) of Spinosad. Toews and Subramanyam (2004) estimated that the mean number of *X. flavipes* nymphs ( $F=4.07$ ,  $df= 1, 11$ ,  $P=0.069$ ) and adults ( $F=1.88$ ,  $df= 1, 11$ ,  $P=0.197$ ) recovered was similar between the control and treatments. Effects of fungus *Beauveria bassiana* strain Bb-RSB on *Orius sauteri* (Hemiptera: Anthocoridae) were examined under laboratory conditions and found that *O. sauteri* nymphs treated with either low or high *B. bassiana* concentrations

were able to complete their life cycle as well as control nymphs, mortality was very low and adult longevity was not affected (Gao *et al.* 2012). These results also supported the present findings.

The lack of lethal infections indicates that *O. sauteri* is not within the physiological host range of this strain of *B. bassiana* (Zimmermann 2007).

Schoonover and Larson (1995) found that LC<sub>50</sub> of *Phytoseiulus persimilis* adult was 200 ppm and Torres *et al.* (1999) found that LC<sub>50</sub> of *Podisus nigrispinus* adult was 53 ppm respectively to moderate concentrations (30-200 ppm) of Spinosad. Ludwig and Oetting (2001) obtained ambiguous results with their two tests of Spinosad for compatibility with *O. insidiosus* for control of thrips on greenhouse chrysanthemums. Miles and Dutton (2000) reported Spinosad as highly toxic to parasitic Hymenoptera in greenhouses, but concluded it was compatible with *O. insidiosus*, *C. rufilabris* and the coccinellids *Hippodamia convergens* and *Coccinella septempunctata*. Tillman and Mulrooney (2000) observed toxicity of Spinosad to three parasitoid species in cotton, *Bracon mellitor*, *Cardiochiles nigriceps* and *Cotesia marginiventris* although the coccinellids *Coleomegilla maculata* and *H. convergens* were unaffected. Similarly, Mason *et al.* (2002) demonstrated toxicity of Spinosad to *Trichogramma inyoense*, an egg parasitoid of *Mamestra configurata*. Toews and Subramanyam (2004) observed that absolute densities derived from sieving all the grain at the end of the study showed differences among treatments in the number of *X. flavipes* adults (F=12.73, df=1,4, P=0.023) but not nymphs (F=2.92, df=1,4, P=0.163). These results are similar to the present study because the adult survivability was ranged 84 to 94% at lower three concentrations of Spinosad after 24 to 72 h of exposure.

Tillman and Mulrooney (2000) found that counts of a hemipteran predator *Geocoris punctipes* (Say) (Hemiptera: Lygaeidae), were not affected by Spinosad in cotton fields. *X. flavipes* is a more stout-bodied insect, and was perhaps, sucking behaviour of body fluids of live soft bodied small insects and also less affected by the sieving. A general lack of survival among hymenopterans exposed to Spinosad was also reported in the literature (Tillman and Mulrooney 2000, Mason *et al.* 2002, Michaud 2003).

A recent review of predator and parasitoid susceptibility to Spinosad concluded that this product represented one of the most judicious insecticides available for the conservation of predator populations (Williams *et al.* 2003). However, the majority of laboratory and field studies in natural and semi-natural conditions report moderately harmful or harmful effects on populations of hymenopteran parasitoids (Bernardo and Viggiani 2000, Hill and Foster 2000, Tillman and Mulrooney 2000, Mason *et al.* 2002).

Assessment of the impact of Spinosad on non-target insects is particularly relevant now that synthetic Spinosyn analogues (Spinosoids) are being developed for increased environmental stability and an altered spectrum of insecticidal activity (Crouse *et al.* 2001, Sparks *et al.* 2001).

Laboratory dose-mortality studies are of limited use in predicting the impact of a toxicant on non-target invertebrate populations in the field (Stark *et al.* 1995, Wright and Verkerk 1995, Longley and Jepson 1997). Species or stage-related differences in biology and behaviour can significantly influence the susceptibility of natural enemies to pesticides (Longley and Jepson 1997, Verkerk *et al.* 1998). This was particularly evident when considering the impact of Spinosad on immature parasitoids developing in *S. frugiperda* eggs and larvae. Similar effects, including an inability to spin a cocoon or pupation or Spinosad-induced mortality at the moment of adult emergence have been observed in parasitoids of other taxa (Suh *et al.* 2000, Gahbiche 2001, Mason *et al.* 2002).

Predators generally suffer insignificant sub-lethal effects following exposure to Spinosad, whereas parasitoids often show sub-lethal effects including loss of reproductive capacity, reduced longevity, etc. All studies agree that Spinosad residues degrade quickly in the field, with little residual toxicity at 3-7 days post application (Williams *et al.* 2003).

Spinosad shows no effects on predatory insects such as ladybirds, lacewings, big-eyed bugs or minute pirate bugs (Copping 2001). Spinosad is slow acting compared to conventional synthetic insecticides, but is more rapid than most entomopathogens (Bret *et al.* 1997).

Clearly, caution is required when making assumptions about pesticide impact on beneficial organisms based exclusively on toxicity data generated in laboratory studies (Stark *et al.* 1995). It is becoming increasingly clear that species or stage-related differences in biology and behaviour and even crop type can significantly influence the susceptibility of non-target invertebrates to pesticides (Longley and Jepson 1997, Verkerk *et al.* 1998). Moreover, the fact that a natural enemy survives exposure to a poison does not necessarily mean that it will perform as well as a non-intoxicated con specific; many of the indirect sub-lethal effects on natural enemy function (foraging, predation, etc.) and/or reproduction cannot be detected by laboratory dose/mortality assays (Wright and Verkerk 1995, Longley and Jepson 1996). In addition, natural enemies subjected to multiple routes of exposure to pesticides may respond in unexpected ways that would be impossible to predict based on single route laboratory toxicity tests (Banken and Stark 1998, Kunkel *et al.* 2001).

The need for accurate assessment of the environmental impact of agrochemicals is an issue of international concern (Croft 1990, Levitan *et al.* 1995, Reus *et al.* 2002). This information is specially relevant now that large areas are being treated with Spinosad, for example to control fruit flies (Peck and McQuate 2000, Prokopy *et al.* 2000, Vargas *et al.* 2001). Toews and Subramanyam (2004) found that the survival of natural enemies, the predator *X. flavipes* was  $87.6 \pm 2.7\%$  in untreated wheat (control) and was  $>90\%$  in wheat treated with 1mg/kg Spinosad.

It can be concluded that there is little impact of 0.491, 0.983 and  $1.966 \mu\text{l}/\text{cm}^2$  concentrations of Spinosad on egg hatchability, survivability of nymphs and adults of *X. flavipes* which is negligible. These concentrations of Spinosad may be used with the predator, *X. flavipes* for the well management of many stored product insect pests.



## **Chapter 7**

**Effects of *X. flavipes* and Spinosad on  
pest population after different  
storage periods**

## Introduction

Control of stored product insects is considered the best achieved through an integration of physical, chemical, and biological methods ( Arthur 1996, Hagstrum *et al.* 1999, Phillips and Throne 2010). In this context in storage facilities, where light is absent the bacterial insecticide Spinosad could be a potential agent; and was found to be remain stable for a long period (up to two years), thus it can provide long-term protection for stored grains (Fang *et al.* 2002b, Fang and Subramanyam 2003, Arthur *et al.* 2006, Hertlein *et al.* 2011). Spinosad has already been proved very effective against a range of stored-grain insect species, even at lower rates than the application rate, in both laboratory (Fang *et al.* 2002a, Toews and Subramanyam 2003, Nayak *et al.* 2005, Daglish and Nayak 2006) and field tests (Maier *et al.* 2006, Subramanyam *et al.* 2007, Daglish *et al.* 2008) and there by The US Environmental Protection Agency approved for its use as a grain protectant in 2005, at the application rate of 1ppm (mg/kg of grain) (Subramanyam 2006a,b).

Bret *et al.* (1997) reported that Spinosad was much less toxic to beneficial insects in field crops than synthetic pesticides. Schoonover and Larson (1995) reported that Spinosad was practically nontoxic to the insidious flower bug, lady beetle, phytoseid mite, and common green lacewing. Boucher (1999) reported that Spinosad applied to bell peppers effectively controlled the pepper maggot but it did not reduce populations of beneficial arthropods, including unspecified species of Coccinellidae, Chrysopidae, Cecidomyiidae, Syrphidae, Nabidae, and hymenopteran-parasitized Aphididae. Mason *et al.* (2002) found that Spinosad was toxic to the parasitoids *Trichogramma inyoense* Pinto and Oatman (Hymenoptera: Trichogrammatidae) and *Microplitis mediator* Haliday (Hymenoptera: Braconidae). Surprisingly, the predacious bug, *X. flavipes* can survive 92% and reproduce at 1ppm Spinosad (Towes and Subramanyam 2004).

Stored grain insects can coexist with other arthropods, which may act as natural enemies, within storage and hence a binary combination of insecticide and predator may give more complete control than the application of a single

insecticide or predator. Many combinations of Spinosad with beneficial insects such as predator, parasitoids and with insecticides as a stored grain protectant have been progressively highlighted in a series of scientific publications (Towes and Subramanyam 2004, Parker *et al.* 2004a, 2004b, Szabela 2005, Williams *et al.* 2003, Miles and Eelen 2006, Miles 2006, Arthurs *et al.* 2007, Bonjour *et al.* 2006, Parker and Falconer 2006, 2007, Nayak and Daghli 2007, Subramanyam *et al.* 2007, Daghli 2008, Daghli *et al.* 2008, Chintzoglou *et al.* 2008a, Huang *et al.* 2009, Ghosh *et al.* 2010, Vayias *et al.* 2010b, Athanassiou *et al.* 2010a,b). Combination is needed, specially when mortality from Spinosad is not complete or progeny production occurs, even when parental adults are killed on different grains (Fang *et al.* 2002a, Athanassiou *et al.* 2008c, Chintzoglou *et al.* 2008). Conversely, *X. flavipes* affects progeny production or immature stages but generally adults are not affected (Lecato and Davids 1973, Arbogast 1979, Brower and Mullen 1990, Brower and Press 1992, Helbig 1999, Donnelly and Phillips 2001, Russo *et al.* 2004, Sing and Arbogast 2007). Hence, a combination of *X. flavipes* and Spinosad may be more effective than the application of each alone. Lower rates of Spinosad were used to determine if even small amounts of Spinosad combined with *X. flavipes* would improve the control of different stored grain species, including those life stages of insect pests that are not controlled by either *X. flavipes* or Spinosad. Considering these, in the present investigation, the potentiality of predator *X. flavipes* and Spinosad (contact treatment) alone and in combination were evaluated to control *C. pusillus* and *R. dominica* supplied with standard food at different storage periods.

### **Materials and Methods**

**Insects:** Unsexed 2d old adults of predator *X. flavipes* and 5d old adults of *C. pusillus* and *R. dominica* were collected from the respective stock culture (Chapter 3) using by aspirator and were used in this experiment.

**Standard food:** White wheat, wheat flour and brewer's yeast were cleaned and sterilized using the methods as described in chapter 3. Firstly, wheat flour and brewer's yeast were mixed (ratio 19:1 in weight) and prepared mixture food.



Secondly, the standard food were prepared with white wheat and mixture food where the ratio was 3:1 between wheat and mixture food. Finally, the standard food 10.5kg was made for the experiments.

**Bioassays:** Thirty six pieces of filter papers (9cm diameter) were soaked in 0.491, 0.983 and 1.966  $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad and 12 pieces of filter papers (9cm diameter) treated with only 2ml distilled water and were dried them at room temperature using the methods as described in chapter 5. 200g of standard food were taken in a cylindrical plastic container (12 cm diameter, 20 cm in height), such 24 containers were prepared for *C. pusillus* and another 24 containers were prepared for *R. dominica*. One hundred adults of *C. pusillus* in 1:1 ratio of male and female were introduced in each of 24 containers. Similarly 100 adults 1:1 male and female *R. dominica* were introduced in another 24 set of containers. The mouths of all containers were covered by the fine clothes with the help of rubber bands and were kept in the CT room at  $30\pm 0.5^\circ\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity without controlling light. After 25 days, each filter paper either treated with distilled water only (control) or treated with different concentrations of Spinosad was divided into 4 pieces and were inserted into standard food of each container at different layers separately. Then 30 unsexed adults of *X. flavipes* were released in the container either treated with distilled water or treated with different concentrations of Spinosad for both species. The mouths of all the containers were covered similarly and were placed in the CT room at same environmental conditions.

After 3, 6, 9 and 12 months the containers were opened, adults were removed sieving by 125 and 500 micrometer aperture sieve. The total numbers of live and dead adults were counted separately, the dead adults were discarded. In case of *C. pusillus*, adult predator were not found after every exposure period, so after each three months 30 unsexed adults of *X. flavipes* were added to the container. Few larvae of *C. pusillus* were found, their numbers were added to the adults. In case of *R. dominica*, always there found adult *X. flavipes*, so there was no need to add new predators in the experiment. Only adults were counted for *R. dominica* as

this species complete larval and pupal development within the wheat kernels. After counting an additional 5g of standard food was added to each container to avoid the conditioning of food medium due to overcrowding or shortage (Mondal 1985).

Another set of experiment was conducted with 30 unsexed adult predators released separately in containers containing either *C. pusillus* or *R. dominica* adults rearing on same quality of standard food and similar experimental conditions, and stored for same periods. For control batch similar numbers of *C. pusillus* and *R. dominica* adults were released in standard food without providing any predator or Spinosad treated filter paper. All the experiments were replicated three times. With each concentrations all the experiment were done under same laboratory conditions.

Data Analyses: All data were analyzed by Factorial ANOVA to compare mortality percentage as the response variable and concentrations, life stages, exposure periods main effects. For the comparison of means the Tukey's test (1953) was used. The percent reduction of population to control (PRC) was calculated according to Mian and Mulla (1982a) by the following formula.

Percentage reduction in population

$$(\text{PRC}) = \frac{\text{No. of population in control} - \text{No. of population in treated media}}{\text{No. of population in control}} \times 100$$

$$\text{or, PRC} = \frac{C - T}{C} \times 100$$

Where, C = No. of population in control

T = No. of population in treated media

## Results and observations

**Effects on adult population of *C. pusillus*:** The data of the present experiment revealed that the combined effects of different concentrations of Spinosad and *X. flavipes* reduced the population growth of *C. pusillus* after different storage periods in comparison with that of control (untreated) and control (treated with 30 unsexed adults *X. flavipes* only) (Figure 33, Table 5). In plastic container within standard food after 3, 6, 9 and 12 months of exposure in control batch (untreated) the initial 100 adults of *C. pusillus* were increased up to  $400 \pm 4.62$ ,  $600 \pm 5.77$ ,

825±2.89 and 1020±5.77 adult individuals respectively where as, the highest number of host population were reduced (PRC 55.25, 48.33, 37.09 and 29.90) in 30 *X. flavipes* +1.966 µl/cm<sup>2</sup> combination, among the different used combinations. The lowest number of host population were suppressed (PRC 85.50, 79.83, 74.79 and 70.20) by only 30 *X. flavipes* at the same periods and conditions. Different used concentrations of Spinosad were found potential to reduce maximum number of *C. pusillus* populations in comparison with control (Table 5). From 3 to 12 months different used concentrations of Spinosad singly or in combination with predator, *X. flavipes* were found effective to suppress *C. pusillus* population (Table 5). Each level of concentrations and combinations were found effective to suppress the population of *C. pusillus* significantly (P<0.001) (Appendix tables 103-106).

Table 5 Effects of 2d unsexed adults of *X. flavipes* with different concentrations of Spinosad separately and in combination against the adult population of *C. pusillus* at different storage periods. [Initial prey population 100 adults, 1:1]

| Predator/<br>Concentration                            | No/Rates<br>(µl/cm <sup>2</sup> ) | Exposure period (months) |       |                     |       |                     |       |                     |       |
|---|-----------------------------------|--------------------------|-------|---------------------|-------|---------------------|-------|---------------------|-------|
|   |                                   | 3                        |       | 6                   |       | 9                   |       | 12                  |       |
|   |                                   | Total<br>population      | PRC   | Total<br>population | PRC   | Total<br>population | PRC   | Total<br>population | PRC   |
| Control<br>(untreated)                                |                                   | 400±4.62a                |       | 600±5.77a           |       | 825±2.89a           |       | 1020±5.77a          |       |
| Control (Adult<br><i>X. flavipes</i><br>treated only) | 30                                | 58±4.62g                 | 85.50 | 121±5.77g           | 79.83 | 208±4.62h           | 74.79 | 304±2.31h           | 70.20 |
| Spinosad  | 0.491                             | 83±1.73f                 | 79.25 | 170±2.89f           | 71.67 | 305±2.89g           | 63.30 | 429±5.20g           | 57.90 |
|   | 0.983                             | 97±4.04ef                | 75.75 | 208±4.62e           | 65.33 | 343±1.73f           | 58.42 | 470±2.89f           | 53.00 |
|   | 1.966                             | 115±2.89de               | 71.25 | 239±5.20d           | 60.17 | 377±4.04e           | 54.30 | 516±3.46e           | 49.40 |
| Adults<br><i>X. flavipes</i> +<br>Spinosad            | 30 +<br>0.491                     | 121±3.46d                | 69.75 | 241±3.46d           | 59.83 | 398±4.62d           | 51.76 | 564±2.31d           | 44.70 |
|   | 30 +<br>0.983                     | 146±3.46c                | 63.50 | 272±1.15c           | 54.67 | 444±2.31c           | 46.18 | 645±2.89c           | 36.70 |
|   | 30 +<br>1.966                     | 179±5.20b                | 55.25 | 310±2.89b           | 98.33 | 519±5.20b           | 37.09 | 715±5.77b           | 29.9  |

Note: Means with same letter do not significantly differed from each other (Tukey's Test)




Figure 33 A, B, C and D showing the effects of unsexed adults *X. flavipes* with Spinosad on the adult population of *C. pusillus* after 3, 6, 9 and 12 months storage periods (Treatment 1 = Control (Untreated), 2 = Control (treated with 30 adult *X. flavipes*), 3 = 0.491  $\mu\text{l}/\text{cm}^2$  Spinosad, 4 = 0.983  $\mu\text{l}/\text{cm}^2$  Spinosad, 5 = 1.9966  $\mu\text{l}/\text{cm}^2$  Spinosad, 6 = 0.491  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*, 7 = 0.983  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*, 8 = 1.966  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*,

**Effects on adult populations of *R. dominica*:** The data of the present experiment revealed that the combined effects of different used concentrations of Spinosad and *X. flavipes* reduced the population growth of *R. dominica* after different storage periods in comparison with that of control (untreated) and control (treated with 30 unsexed adult *X. flavipes*) (Figure 34, Table 6). In plastic container within standard food, after 3, 6, 9 and 12 months of exposure in control batch (untreated) the initial 100 adults of *R. dominica* were increased up to  $735 \pm 2.89$ ,  $1220 \pm 11.55$ ,  $1790 \pm 11.55$  and  $2150 \pm 5.77$  adult individuals respectively where as, the highest number of host population were reduced (PRC 42.86, 27.86, 11.28 and 1.10) in 30 *X. flavipes* +1.966  $\mu\text{l}/\text{cm}^2$  combination, among the different used combinations. The lowest number of host population were suppressed (PRC 81.77, 74.02, 67.49 and 61.21) by only 30 *X. flavipes* at the same periods and conditions. Different concentrations of Spinosad were found effective to reduce more number of host populations in comparison with control (Table 6). From 3 to 12 months different used concentrations of Spinosad singly or in combination with *X. flavipes* were found effective to suppress the host population (Table 6). Each level of concentrations and combinations were found effective to suppress the population of *R. dominica* significantly ( $P < 0.001$ ) (Appendix tables 107-110).

Predator, *X. flavipes* were not found susceptible to used concentrations. But in all used concentrations and combinations *R. dominica* was found more susceptible than *C. pusillus* at the same time and conditions. Used concentrations of Spinosad were found potential during long time singly and in combination with *X. flavipes* to suppress the populations of both hosts (Tables 5 and 6). In case of population suppression of *C. pusillus* and *R. dominica* limited benefits were achieved at all combinations in comparison with singly concentrations of Spinosad or only with *X. flavipes* alone (Tables 5 and 6).

Table 6 Effects of 2d unsexed adults of *X. flavipes* with different concentrations of Spinosad separately and in combination against the adults populations of *R. dominica* at different storage periods. [Initial prey population 100 adults, 1:1]

| Predator/<br>Concentrations                           | No/Rates<br>( $\mu\text{l}/\text{cm}^2$ ) | Exposure period (months) |       |                     |       |                     |       |                     |       |
|---|---|--------------------------|-------|---------------------|-------|---------------------|-------|---------------------|-------|
|   |   | 3                        |       | 6                   |       | 9                   |       | 12                  |       |
|   |   | Total<br>population      | PRC   | Total<br>population | PRC   | Total<br>population | PRC   | Total<br>population | PRC   |
| Control<br>(untreated)                                |   | 735 $\pm$ 2.89a          |       | 1220 $\pm$ 11.55a   |       | 1790 $\pm$ 11.55a   |       | 2150 $\pm$ 5.77a    |       |
| Control (Adult<br><i>X. flavipes</i><br>treated only) | 30  | 134 $\pm$ 2.31h          | 81.77 | 317 $\pm$ 4.04h     | 74.02 | 582 $\pm$ 1.15h     | 67.49 | 834 $\pm$ 2.31g     | 61.21 |
| Spinosad  | 0.491                                     | 249 $\pm$ 5.20g          | 66.12 | 621 $\pm$ 2.89g     | 49.10 | 1032 $\pm$ 6.93g    | 42.35 | 1411 $\pm$ 6.35f    | 34.37 |
|   | 0.983                                     | 279 $\pm$ 6.81f          | 60.68 | 691 $\pm$ 3.46f     | 43.36 | 1134 $\pm$ 2.31f    | 36.65 | 1598 $\pm$ 4.62e    | 25.67 |
|   | 1.966                                     | 311 $\pm$ 5.77e          | 57.69 | 723 $\pm$ 1.73e     | 40.74 | 1208 $\pm$ 4.62e    | 32.51 | 1780 $\pm$ 5.77d    | 17.20 |
| Adults<br><i>X. flavipes</i> +<br>Spinosad            | 30 +<br>0.491                             | 356 $\pm$ 3.46d          | 51.56 | 781 $\pm$ 3.61d     | 36.15 | 1257 $\pm$ 4.04d    | 29.78 | 1978 $\pm$ 4.62c    | 8.00  |
|   | 30 +<br>0.983                             | 389 $\pm$ 4.62c          | 47.07 | 835 $\pm$ 2.89c     | 31.56 | 1354 $\pm$ 2.31c    | 24.36 | 2054 $\pm$ 2.31b    | 4.47  |
|   | 30 +<br>1.966                             | 420 $\pm$ 2.89b          | 42.86 | 880 $\pm$ 5.77b     | 27.86 | 1588 $\pm$ 2.89b    | 11.28 | 2127 $\pm$ 4.04a    | 1.10  |

Note: Means with same letter do not significantly differed from each other (Tukey's Test)




Figure 34 A, B, C and D showing the effects of unsexed adults *X. flavipes* with Spinosad on the adult population of *R. dominica* after 3, 6, 9 and 12 months storage periods (Treatment 1 = Control (Untreated), 2 = Control (treated with 30 adult *X. flavipes*), 3 = 0.491  $\mu\text{l}/\text{cm}^2$  Spinosad, 4 = 0.983  $\mu\text{l}/\text{cm}^2$  Spinosad, 5 = 1.9966  $\mu\text{l}/\text{cm}^2$  Spinosad, 6 = 0.491  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*, 7 = 0.983  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*, 8 = 1.966  $\mu\text{l}/\text{cm}^2$  Spinosad + 30 adults *X. flavipes*,

## Discussion

Combined effects of *X. flavipes* with different concentrations of Spinosad inhibited the population build up of *C. pusillus* and *R. dominica*. The published reports showed that different concentrations of Spinosad (Fang *et al.* 2002a, Toews and Subramanyam 2003, Nayak *et al.* 2005, Daglish and Nayak 2006, Maier *et al.* 2006, Subramanyam *et al.* 2007, Daglish *et al.* 2008) and *X. flavipes* (Arbogast 1984, Haines 1984, Brower 1990, 1991, Brower *et al.* 1996, Nilakhe and Parker 1990, Scholler *et al.* 1997, Adler and Scholler 1998, Scholler and Flinn 2000, Lecato and Collins 1976) separately as potential agents which suppressed *C. pusillus* and *R. dominica* populations effectively.

Toews and Subramanyam (2004) reported that suppression of *T. castaneum* population was achieved in Spinosad or Spinosad +*X. flavipes* treatments and *X. flavipes* survived (92%) and reproduced in Spinosad treated wheat normally which was in agreement with the findings of the present result.

Arbogast (1976) reported that *O. surinamensis* population growth reduced 95% (after 16 wk) when only 5 pairs of *X. flavipes* were introduced. Brower and Press (1992) reported that *X. flavipes* suppressed 90.4% populations of *C. pusillus* when only 50 pairs of *X. flavipes* were introduced.

A single release of 50 pairs of *A. calandreae* suppressed 95.3% of residual populations of *S. oryzae* in wheat (Press *et al.* 1984) but 32.8 and 34.3% of *S. oryzae* and *R. dominica* respectively (Ahmed and Kabir 1995). *C. elegans* was very effective for suppressing *R. dominica* population with augmentative release (Flinn *et al.* 1994, 1996). Flinn *et al.* (1996) observed 98 and 91% suppression of *R. dominica* compared to the control by *C. elegans* in 1993 and 1994 respectively.

Athanassiou *et al.* (2010a,b) evaluated adults of *Cryptolestes* spp. and *R. dominica* on wheat treated with 0.1 and 0.5 ppm concentrations of Spinosad and 1 and 5ppm concentrations of methoprene applied alone or in combination after 14 d of exposure and found that average percent mortality ( $\pm$  SE) were  $86.7 \pm 3.3$ ,  $97.8 \pm 2.2$  in Spinosad alone and  $37.8 \pm 9.7$ ,  $37.8 \pm 9.7$  in methoprene alone,  $80.0 \pm 5.8$  in Spinosad 0.1 ppm + methoprene 1 ppm,



90.0 ± 2.9 in Spinosad 0.1 ppm + methoprene 5 ppm, 98.9 ± 1.1 in Spinosad 0.5 ppm + methoprene 1 ppm and 98.9 ± 1.1a Spinosad 0.5 ppm + methoprene 5 ppm where as 26.7 ± 5.8 was in control for *Cryptolestes* and were 100.0 ± 0.0, 100.0 ± 0.0 in Spinosad alone and 2.2 ± 1.5b, 5.6 ± 3.0 in methoprene alone, 100.0 ± 0.0 in Spinosad 0.1 ppm + methoprene 1 ppm, 100.0 ± 0.0 in Spinosad 0.1 ppm + methoprene 5 ppm, 100.0 ± 0.0 in Spinosad 0.5 ppm + methoprene 1 ppm and 100.0 ± 0.0 Spinosad 0.5 ppm + methoprene 5 ppm where as 3.3 ± 1.7 was in control for *R. dominica*.

Daglish and Nayak (2006) reported that Spinosad residues were stable for 9 months on wheat, without loss of insecticidal activity against *R. dominica* a devastating pest of stored wheat worldwide. Spinosad applied at 0.5 or 1mg/kg was completely effective for 9 months at both 55 and 70% RH, with 100% adult mortality of *R. dominica* after 14 days of exposure and no live  $f_1$  adults produced reported (Daglish *et al.* 2006) in their another study. As Spinosad appears to have low toxicity to many beneficial insects (Elzen *et al.*1998), it has potential for use in Integrated Pest Management (IPM) systems.

Sharififard *et al.* (2011) observed interactions between *Metarhizium anisopliae* and sub lethal doses of Spinosad for control of *M. domestica* and found that average percent (±SE) mortality of adults was 44±4, and 72.4±1.79 for fungus alone, 21±1.24, 32±1.7 and 39±1.7 for Spinosad alone but ranged from 66–87% and 89–95% in combination treatments of 105 and 107 spore/g fungus with 0.5, 1 and 1.5µg/gm doses of Spinosad respectively after 9 d of exposure and concluded that the interaction between *M. anisopliae* and Spinosad indicated a synergetic effect that increased the house fly mortality as well as reduced the lethal time.

Kovendan *et al.* (2012) observed bioefficacy of larvicidal and pupicidal properties of *Carica papaya* (Caricaceae) leaf extract and bacterial insecticide, Spinosad against chikungunya vector, *Aedes aegypti* (Diptera: Culicidae) and found that after 24 h of exposure methanolic leaf extract of *C. papaya* against the first- to fourth-instar larvae and pupae of values  $LC_{50}$ =I instar was 51.76 ppm, II instar was 61.87 ppm, III instar was 74.07 ppm, and IV instar was 82.18 ppm, and pupae was 440.65 ppm, respectively, and bacterial insecticide, Spinosad against the first to

fourth instar larvae and pupae of values  $LC_{50}$ =I instar was 51.76 ppm, II instar was 61.87 ppm, III instar was 74.07 ppm, and IV instar was 82.18 ppm, and pupae was 93.44 ppm, respectively. Moreover, combined treatment of values of  $LC_{50}$ =I instar was 55.77 ppm, II instar was 65.77 ppm, III instar was 76.36 ppm, and IV instar was 92.78 ppm, and pupae was 107.62 ppm, respectively

In a laboratory study, Vayias *et al.* (2010a) showed that a Spinosad liquid SC formulation applied to barley at 1 ppm provided nearly complete control of *R. dominica* and *S. oryzae* for six months and adequate control of *C. ferrugineus* for four to six months. Control of *T. confusum* was only moderate in this study. They reported potential use of *Beauveria bassiana* against the western flower thrips *Frankliniella occidentalis* without reducing the effectiveness of its natural predator *Orius sauteri* (Hemiptera: Anthocoridae) were observed (Gao *et al.* 2012). They found that total nymphal developmental time of *O. sauteri* increased 3-7% and the adult longevity decreased 9-13%. One explanation is that *F. occidentalis* larvae contaminated by *B. bassiana* may be poor quality prey for *O. sauteri* because infection makes the larvae deficient in certain essential nutrients (Simelane, Steinkraus and Kring 2008) or creates a buildup of fungal toxins or metabolites, which may slow development and shorten adult longevity of *O. sauteri* (Leckie *et al.* 2008). Although development of immature *O. sauteri* was slowed by feeding on *B. bassiana*-infected prey, the experiment revealed no significant differences in mortality rates among nymphs given different prey types. This result indicates that *O. sauteri* did not acquire lethal amounts of the pathogen through transmission from the prey (Gao *et al.* 2012). Consequently, the results presented here suggest that the slight negative effects on *O. sauteri* when provided *F. occidentalis* larvae contaminated by *B. bassiana* formulation are most probably prey-quality mediated rather than direct effects of the *B. bassiana* formulation (Sobhy *et al.* 2010). Other strains of *B. bassiana* have been shown to infect Anthocoridae species but with relatively low rates of successful infection (Ludwig and Oetting 2001, Dunkel and Jaronski 2003).

Overall, the findings of the present investigation revealed that *X. flavipes* and Spinosad has good potential properties against *C. pusillus* and *R. dominica* as target species of insect pest control programs.



## **Chapter 8**

# **Summary and Conclusion**

### Summary

The present study was carried out to observe the effects of two stored product insect pests, *C. pusillus* and *R. dominica* as the host on the biology of the predator, *X. flavipes* and also to find out the effects of bacterium, Spinosad on the predator and the host. Moreover, the predator and bacterium separately and in combination were used to suppress the population of the both insect pests.

#### **Host (*C. pusillus* and *R. dominica*) stage-specific effects on biology of *X. flavipes***

The eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instar and pupae of *C. pusillus* and *R. dominica* played significant ( $P < 0.001$ ) role on the biology of *X. flavipes*.

In case of *C. pusillus*, the developmental time from egg hatching to adult emergence of *X. flavipes* were found as  $15 \pm 2.00$ ,  $20 \pm 0.00$ ,  $22 \pm 0.58$ ,  $18 \pm 1.00$ ,  $14 \pm 1.15$  and  $12 \pm 1.15$  days on eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instar and pupae. Duration of each nymph 1<sup>st</sup> up to 5<sup>th</sup> instar was fluctuated on different life stages. The maximum developmental period occurred in 2<sup>nd</sup> instar larvae but it was the minimum on pupae. The developmental period on the different life stages of host was highly significant ( $P < 0.001$ ) which indicated that the developmental periods of *X. flavipes* depended upon different life stages of *C. pusillus*. The highest longevity of the female adult was  $38 \pm 1.15$  days on 3<sup>rd</sup> instar larvae and male adult  $12 \pm 1.15$  days on 2<sup>nd</sup> instar larvae and the lowest  $14 \pm 1.15$  days in female,  $6 \pm 0.58$  days in male on pupae. Life span of the predator varied inversely with host stages. The effect of different life stages of host on adult longevity was highly significant ( $P < 0.001$ ).

Nymphs 1<sup>st</sup> up to 5<sup>th</sup> instar and adults of *X. flavipes* consumed more eggs, 1<sup>st</sup> and 2<sup>nd</sup> instar larvae than those of 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae of *C. pusillus*. One 1<sup>st</sup> instar nymph consumed a few number 4<sup>th</sup> instar larvae ( $1.33 \pm 0.33$ ) and large number eggs ( $7.33 \pm 0.33$ ) per day. The 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> and 5<sup>th</sup> instar nymphs consumed more eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instar and pupae comparatively than 1<sup>st</sup> instar nymphs. The adult female consumed more number of 1<sup>st</sup> instar larvae ( $16.33 \pm 0.33$ ) than the male ( $14.33 \pm 0.33$ ). The adult was found to consume average

number pupae  $4.33 \pm 0.33$  in male and  $5.67 \pm 0.33$  in female daily. No adult of *C. pusillus* was killed or consumed by any life stages of *X. flavipes*.

Average number of survivability of *X. flavipes* (nymphs 1<sup>st</sup> up to 5<sup>th</sup> instar and adult) on eggs, larvae up to 2<sup>nd</sup> instar were found maximum comparatively than that of 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae. Survivability of immature and adult stages of predator was maximum on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae and minimum on pupae of *C. pusillus*. The effect of host stages was found highly significant ( $P < 0.001$ ).

Normally, females were found large size in length than males on eggs, larvae 1<sup>st</sup> up to 4<sup>th</sup> instar and pupae. Larvae 1<sup>st</sup> up to 4<sup>th</sup> instar of *C. pusillus* when fed on, adult male and female size (mm length) of *X. flavipes* were found prolonged than eggs and pupae. The highest size in length of the male and females were  $1.80 \pm 0.01$  mm and  $2.10 \pm 0.01$  mm on 3<sup>rd</sup> instar larvae and the lowest was  $1.50 \pm 1.50$  mm and  $1.70 \pm 0.06$  mm on eggs. Adult size was highly significant ( $P < 0.001$ ) on different life stages of host.

Sex ratio of the emerged predators differed on life stages of *C. pusillus*. Different life stages of *C. pusillus* reared on standard food (Wheat and Yeast; ratio 19:1), when fed on *X. flavipes*, sex of the emergence adults showed preference for more number of female production than the male. The immature stages of *X. flavipes* feeding on eggs, larvae up to 4<sup>th</sup> instar and pupae on the same food, become adult and the ratio between male and female were 1:2.33, 1.12:1.42, 1.27:1.94, 1.27:2.07, 1.17:2.17 and 1.41:3.75 respectively. Based on ratio 1:1, sex ratio was found the best on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae comparatively than other stages.

In case of *R. dominica*, the developmental time from egg hatching to adult emergence of *X. flavipes* were  $18 \pm 1.00$ ,  $20 \pm 0.58$ ,  $16 \pm 2.00$ ,  $14 \pm 1.15$ ,  $12 \pm 1.15$  and  $13 \pm 0.58$  days respectively on eggs, larvae up to 4<sup>th</sup> instar and pupae. Duration of each nymph up to 5<sup>th</sup> instar was found dissimilar on used stages. The maximum developmental period occurred in 2<sup>nd</sup> instar larvae but it was minimum on 4<sup>th</sup> instar larvae. The effects of different life stages of host on the developmental period was highly significant ( $P < 0.001$ ) which indicated that the developmental

periods of *X. flavipes* depended upon different life stages of *R. dominica*. The highest longevity of the adult was  $34 \pm 2.31$  days in female,  $18 \pm 0.58$  days in male on 2<sup>nd</sup> instar larvae and the lowest was  $15 \pm 1.15$  days in female,  $5 \pm 0.58$  days in male on pupae. Life span of the predator varied inversely with host stages. The effect of different life stages of *R. dominica* on adult longevity was highly significant ( $P < 0.001$ ).

Nymphs 1<sup>st</sup> up to 5<sup>th</sup> instar and adults of *X. flavipes* consumed more eggs and 1<sup>st</sup> instar larvae than those of 2<sup>nd</sup> to 4<sup>th</sup> instar larvae and pupae of *R. dominica*. One 1<sup>st</sup> instar nymph consumed a few number 4<sup>th</sup> instar larvae ( $1.33 \pm 0.33$ ) and large number eggs ( $8.00 \pm 0.58$ ) per day. 2<sup>nd</sup>, 3<sup>rd</sup>, 4<sup>th</sup> and 5<sup>th</sup> instar nymphs consumed more eggs, larvae up to 4<sup>th</sup> instar and pupae comparatively than 1<sup>st</sup> instar nymphs. The adult female consumed more 1<sup>st</sup> instar larvae ( $14.00 \pm 1.15$ ) than the male ( $10.00 \pm 1.15$ ). The adult was found to consume average number pupae  $3.00 \pm 0.58$  in male and  $4.00 \pm 0.58$  in female daily. The results noticed that adult *R. dominica* was not killed or consumed by any stage of *X. flavipes*.

Average number of survivability of *X. flavipes* (nymphs up to 5<sup>th</sup> instar and adult) on eggs, larvae up to 2<sup>nd</sup> instar were found maximum comparatively than that of 3<sup>rd</sup>, 4<sup>th</sup> instar larvae and pupae. Survivability of immature and adult stages of predator was maximum on eggs, 1<sup>st</sup> and 2<sup>nd</sup> instar larvae and minimum on pupae of *R. dominica*. The effects of host stages was found highly significant ( $P < 0.001$ ).

Normally, females were found large size in length than males on eggs, larvae up to 4<sup>th</sup> instar and pupae. Larvae up to 4<sup>th</sup> instar of *R. dominica* when fed on, adult male and female size (mm length) of *X. flavipes* was larger comparatively than eggs and pupae. The highest size in length of the male and females was as  $1.85 \pm 0.01$  mm and  $2.15 \pm 0.02$  mm on 2<sup>nd</sup> instar larvae and lowest was  $1.75 \pm 0.03$  mm on egg and  $1.90 \pm 0.03$  mm on pupae. The effect of different life stages of host on adult size was highly significant ( $P < 0.001$ ).

Sex ratio of the emerged predators differed in life stages of *R. dominica*. Different life stages of host reared on standard food (Wheat and Yeast; ratio 19:1), when

were fed on *X. flavipes*, sex of the emergence adults showed preference for more female production than the male. The immature stages of *X. flavipes* feeding on eggs, larvae up to 4<sup>th</sup> instar and pupae on the same food, become adult and the ratio between males and females were found as 1.23:2.10, 1.05:1.45, 1.30:2.03, 1.13:2.20, 1.03:2.18 and 1.35:3.65 respectively. Based on ratio 1:1, sex ratio was found the best on 1<sup>st</sup> and 2<sup>nd</sup> instar larvae comparatively than other stages.

Overall, *X. flavipes* proved itself as an effective predator of insect pests in stored commodities and a potential controlling agent against *C. pusillus* and *R. dominica*.

### **Effects of Spinosad on host and predator**

In case of *C. pusillus*, Spinosad showed a concentration related effects on the percentage of average egg hatchability. Average percentage of egg hatchability ( $\pm$ SE) was lowest  $5.00\pm 1.02$  at  $7.863\mu\text{l}/\text{cm}^2$  but highest  $25.00\pm 1.15$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations. At  $7.863$ ,  $3.932$ ,  $1.966$ ,  $0.983$  and  $0.491\mu\text{l}/\text{cm}^2$  concentrations, the average percent of egg hatchability was less than that of the control medium. PRC value was the highest 88.10% at  $7.863\mu\text{l}/\text{cm}^2$  where as the lowest was 40.48% at  $0.491\mu\text{l}/\text{cm}^2$  concentrations. The effect of different concentrations on egg hatchability was found significant ( $P<0.001$ ).

*C. pusillus* 14-19d old larvae were used and the mortality was observed on different concentrations of Spinosad after 24, 48 and 72h of exposure. The concentrations of  $0.491$ ,  $0.983$ ,  $1.966$ ,  $3.982$  and  $7.863\mu\text{l}/\text{cm}^2$  were found to be potential causing larval mortality based on the ingestion and contact compare to control. Average mortality ( $\pm$ SE) was the highest  $14.00\pm 2.00$  at  $7.863\mu\text{l}/\text{cm}^2$  after 72h and lowest  $3.33\pm 0.88$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95% confidence limit lower to upper 24h  $LC_{50}$  was 18.208 (4.379743-75.69753), 48h  $LC_{50}$  was 5.912 (1.421441-24.59105) and 72h  $LC_{50}$  was  $0.176\mu\text{l}/\text{cm}^2$  (0.01161457-2.651883) respectively. There were significant differences in the mean mortality of larvae between exposure periods ( $F=58.038$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=38.389$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure periods and concentration rates was significant ( $F=12.411$ ,  $df=10$ ,  $P<0.001$ ).



Moreover, Spinosad showed concentration rate and exposure period related effects on larval mortality.

The concentrations were 0.491, 0.983, 1.966, 3.982 and 7.863 $\mu\text{l}/\text{cm}^2$  were found to be potential causing pupal mortality based on the ingestion and contact compare to control. Average mortality ( $\pm\text{SE}$ ) was highest 8.33 $\pm$ 0.88 at 7.863 $\mu\text{l}/\text{cm}^2$  after 72h and lowest 1.67 $\pm$ 0.33 at 0.491 $\mu\text{l}/\text{cm}^2$  Spinosad concentrations after 24h of exposure. At 95% confidence limit lower to upper 24h  $\text{LC}_{50}$  was 568.571 (2.246793-143881.9), 48h  $\text{LC}_{50}$  was 1841.139 (0.09236452-36700190) and 72h  $\text{LC}_{50}$  was 35.941 $\mu\text{l}/\text{cm}^2$  (2.061289-626.6588) respectively. There were significant differences in the mean mortality between exposure periods ( $F=30.791$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=61.524$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration rates was significant ( $F=2.558$ ,  $df=10$ ,  $P<0.001$ ). Moreover, Spinosad showed concentration rate and exposure period related effects on pupal mortality.

The above concentrations were found to be potential causing adult mortality based on the ingestion and contact compare to control. Average mortality ( $\pm\text{SE}$ ) was highest 15.33 $\pm$ 1.22 at 7.863 $\mu\text{l}/\text{cm}^2$  after 72h and lowest 5.00 $\pm$ 0.58 at 0.491 $\mu\text{l}/\text{cm}^2$  Spinosad concentrations after 24h of exposure. At 95% confidence limit lower to upper 24h  $\text{LC}_{50}$  was 7.995 (2.947408-21.68888), 48h  $\text{LC}_{50}$  was 2.145 (1.191995-3.860422) and 72h  $\text{LC}_{50}$  was 0.840 $\mu\text{l}/\text{cm}^2$  (0.446121-1.580054) respectively. There were significant differences in the mean mortality of adults between exposure periods ( $F=202.970$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=42.617$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration was significant ( $F=8.350$ ,  $df=10$ ,  $P<0.001$ ). Spinosad showed a concentration related effects on adult mortality. The potentiality was higher in all treatments with the increase of concentration rate and exposure periods.

In case of *R. dominica*, Spinosad showed a concentration related effects on the percentage of average egg hatchability. Average percentage of egg hatchability ( $\pm\text{SE}$ ) was lowest 0.33 $\pm$ 1.03 at 7.863 $\mu\text{l}/\text{cm}^2$  and highest 15.00 $\pm$ 1.14 at 0.491 $\mu\text{l}/\text{cm}^2$  concentrations. At 7.863, 3.932, 1.966, 0.983 and 0.491 $\mu\text{l}/\text{cm}^2$  concentrations, the

average percent of egg hatchability was significantly lower than that of the control. The PRC value was the highest 99.13% at 7.863 $\mu\text{l}/\text{cm}^2$  concentrations where as lowest 60.53% at 0.491 $\mu\text{l}/\text{cm}^2$  concentrations. The effect of different concentrations on egg hatchability was found highly significant ( $P < 0.001$ ).

*R. dominica* 26-31d old larvae were used and mortality was observed on different concentrations of Spinosad after 24, 48 and 72h of exposure. The observed concentrations 0.491, 0.983, 1.966, 3.982 and 7.863 $\mu\text{l}/\text{cm}^2$  were found to be potential causing larval mortality based on the ingestion and contact compare to control. Average mortality ( $\pm\text{SE}$ ) was highest 13.33 $\pm$ 0.88 at 7.863 $\mu\text{l}/\text{cm}^2$  after 72h and lowest 4.67 $\pm$ 0.33 at 0.491 $\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95% confidence limit lower to upper 24h  $\text{LC}_{50}$  was 9.230 (3.402471-25.03735), 48h  $\text{LC}_{50}$  was 2.835 (0.0683601-10.46294) and 72h  $\text{LC}_{50}$  was 0.543 $\mu\text{l}/\text{cm}^2$  (0.1273662-2.317881) respectively. There were significant differences in the mean mortality of larvae between exposure times ( $F=57.026$ ,  $df=2$ ,  $P < 0.001$ ) and between concentrations ( $F=56.006$ ,  $df=5$ ,  $P < 0.001$ ). In addition, the interaction between exposure time and concentration rates were significant ( $F=7.795$ ,  $df=10$ ,  $P < 0.001$ ).

The pupal mortality of *R. dominica* on different concentrations of Spinosad after 24, 48 and 72h of exposure were observed at 0.491, 0.983, 1.966, 3.982 and 7.863 $\mu\text{l}/\text{cm}^2$  concentrations and found to be potential causing pupal mortality based on the ingestion and contact compare to control. The average mortality ( $\pm\text{SE}$ ) was highest 8.33 $\pm$ 1.45 at 7.863 $\mu\text{l}/\text{cm}^2$  after 72h and lowest 1.00 $\pm$ 0.58 at 0.491 $\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95% confidence limit lower to upper 24h  $\text{LC}_{50}$  was 1138.777 (1.990441-651521.7), 48h  $\text{LC}_{50}$  was 231.134 (2.478723-21552.51) and 72h  $\text{LC}_{50}$  was 22.054  $\mu\text{l}/\text{cm}^2$  (2.711695-179.3602) respectively. There were significant differences in the mean mortality between exposure periods ( $F=32.986$ ,  $df=2$ ,  $P < 0.001$ ) and between concentrations ( $F=23.986$ ,  $df=5$ ,  $P < 0.001$ ). In addition, the interaction between exposure period and concentration rate was significant ( $F=4.622$ ,  $df=10$ ,  $P < 0.001$ ).

The observed concentrations were found to be potential causing adult mortality based on the ingestion and contact compare to control. Average mortality ( $\pm$ SE) was highest  $17.33\pm 1.20$  at  $7.863\mu\text{l}/\text{cm}^2$  after 72h and lowest  $6.67\pm 0.88$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95%, confidence limit lower to upper 24h  $\text{LC}_{50}$  was 6.952 (1.68851-28.62021), 48h  $\text{LC}_{50}$  was 0.959 (0.4546266-2.02328) and 72h  $\text{LC}_{50}$  was  $0.466\mu\text{l}/\text{cm}^2$  (0.2381866-0.912989) respectively. There were significant differences in the mean mortality of adults between exposure periods ( $F=36.112$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=83.468$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure time and concentration was highly significant ( $F=2.017$ ,  $df=10$ ,  $P<0.001$ ). Spinosad showed a concentration related effects on adult mortality. The potentiality was higher in all treatments with the increase of concentration rate and exposure period.

In case of *X. flavipes* the average percentage of egg hatchability ( $\pm$ SE) was lowest  $25.00\pm 2.12$  at  $7.863\mu\text{l}/\text{cm}^2$  and highest  $35\pm 1.73$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations. At 1.966, 0.983 and  $0.491\mu\text{l}/\text{cm}^2$  concentrations, the average percent of egg hatchability of *X. flavipes* was almost similar as in the control (untreated). PRC value was highest 28.57 at  $7.863\mu\text{l}/\text{cm}^2$  where as lowest 2.86% at  $0.491\mu\text{l}/\text{cm}^2$  concentrations. The effect of different concentrations of Spinosad on egg hatchability noted highly significant ( $P<0.001$ ).

Mortality was observed on different concentrations of Spinosad after 24, 48 and 72h of exposure of 4d old nymphs of *X. flavipes*. The noted concentrations were found to be potential causing very few nymphal mortality based on the ingestion and contact compare to control. Average mortality ( $\pm$ SE) was highest  $6.67\pm 1.76$  at  $7.863\mu\text{l}/\text{cm}^2$  after 72h and lowest  $1.00\pm 0.58$  at  $0.491\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95%, confidence limit lower to upper 24h  $\text{LC}_{50}$  was 432.654 (2.922949-237196.1), 48h  $\text{LC}_{50}$  was 137.838 (3.740582-5079.244) and 72h  $\text{LC}_{50}$  was  $73.830\mu\text{l}/\text{cm}^2$  (3.22157-1691.976) respectively. There were significant differences in the mean mortality of larvae between exposure periods ( $F=15.068$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=13.562$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure periods and concentration rates was significant ( $F=3.083$ ,  $df=10$ ,  $P<0.001$ ). Moreover, nymphal mortality was found slightly higher than that of adults.

The 2d old adult mortality of *X. flavipes* on different concentrations 0.491, 0.983, 1.966, 3.982 and 7.863 $\mu\text{l}/\text{cm}^2$  of Spinosad after 24, 48 and 72h of exposure was observed. The average mortality ( $\pm\text{SE}$ ) was the highest  $5.00\pm 0.45$  at 7.863 $\mu\text{l}/\text{cm}^2$  after 72h and the lowest was  $1.67\pm 0.67$  at 0.491 $\mu\text{l}/\text{cm}^2$  concentrations after 24h of exposure. At 95%, confidence limit lower to upper 24h  $\text{LC}_{50}$  was 492.851 (3.859698-62932.93), 48h  $\text{LC}_{50}$  was 348.974 (4.223628-28833.73) and 72h  $\text{LC}_{50}$  was 331.510 $\mu\text{l}/\text{cm}^2$  (2.651994-41440.03) respectively. There were significant differences in the mean mortality of adults between exposure periods ( $F=7.386$ ,  $df=2$ ,  $P<0.001$ ) and between concentrations ( $F=5.219$ ,  $df=5$ ,  $P<0.001$ ). In addition, the interaction between exposure period and concentration was significant ( $F=2.432$ ,  $df=10$ ,  $P<0.001$ ). The potentiality was higher in all treatments with the increase of concentrations and exposure periods. Moreover, at 0.491, 0.983 and 1.966 $\mu\text{l}/\text{cm}^2$  concentrations of Spinosad, after 24h to 72h of exposure survivability of *X. flavipes* adults were found ranging 94 to 84% respectively.

#### **Combined effects of *X. flavipes* and Spinosad on the population of *C. pusillus* and *R. dominica***

The combined effects of different concentrations of Spinosad and *X. flavipes* reduced the population growth of *C. pusillus* after different storage periods in comparison with that of control (untreated) and control (treated with 30 adults *X. flavipes* only). In plastic container within standard food, after 3, 6, 9 and 12 months of exposure in control batch (untreated) the initial 100 adults of *C. pusillus* were increased up to  $400\pm 4.62$ ,  $600\pm 5.77$ ,  $825\pm 2.89$  and  $1020\pm 5.77$  adult individuals respectively where as, the highest number of host population were reduced (PRC 55.25, 48.33, 37.09 and 29.90) in 30 *X. flavipes* +1.966 $\mu\text{l}/\text{cm}^2$  combination, among the different combinations. The lowest number of host population were suppressed (PRC 85.50, 79.83, 74.79 and 70.20) by only 30 *X. flavipes* at the same periods and conditions. Different concentrations of Spinosad were found potential to reduce more number of *C. pusillus* populations in comparison with control. From 3 to 12 months different concentrations of

Spinosad alone or in combination with *X. flavipes* were found effective to suppress the *C. pusillus* population. Each level of concentrations and combinations were found potential to suppress the population of *C. pusillus* significantly ( $P < 0.001$ ).

The combined effects of different concentrations of Spinosad and the predator, *X. flavipes* reduced the population growth of host *R. dominica* after different storage periods in comparison with that of control (untreated) and control (treated with 30 unsexed adult *X. flavipes*). In plastic container within standard food, after 3, 6, 9 and 12 months of exposure in control batch (untreated) the initial 100 adults of *R. dominica* were increased up to  $735 \pm 2.89$ ,  $1220 \pm 11.55$ ,  $1790 \pm 11.55$  and  $2150 \pm 5.77$  adult individuals respectively where as, the highest number of host population were reduced (PRC 42.86, 27.86, 11.28 and 1.10) in 30 *X. flavipes* +  $1.966 \mu\text{l}/\text{cm}^2$  combination, among the different combinations. The lowest number of host population were suppressed (PRC 81.77, 74.02, 67.49 and 61.21) by only 30 *X. flavipes* at the same periods and conditions. Different concentrations of Spinosad were found potential to reduce more number of host populations in comparison with control. From 3 to 12 months different used concentrations of Spinosad alone or in combination with *X. flavipes* were found effective to suppress the host population. Each level of concentrations and combinations were found potential to suppress the population of *R. dominica* significantly ( $P < 0.001$ ).

*X. flavipes* were not found susceptible to used concentrations. But in all used concentrations and combinations, host *R. dominica* was found more susceptible than the host *C. pusillus* at the same time and conditions. Used concentrations of Spinosad were found potential during long time alone and in combination with predator, *X. flavipes* to suppress the populations of both hosts. In case of population suppression of both hosts *C. pusillus* and *R. dominica*, limited benefits were achieved at all combinations in comparison with alone concentrations of Spinosad or only with predator, *X. flavipes*.

## Conclusion

*X. flavipes* a well known challenging predator of many stored products insect pests is already now a day commercially available in the USA as a biological control agent. On the other hand, bacterium, Spinosad provides long term grain protection through the control of adult and immature stages of insect pests in storage. Spinosad is minimally disrupted to beneficial insects and compatible with Integrated Pest Management (IPM) program.

The present investigation revealed nymph up to 5<sup>th</sup> instar and adult *X. flavipes* can kill and consume eggs, larvae up to 4<sup>th</sup> instar and pupae of *C. pusillus* and *R. dominica*. Eggs, larvae up to 4<sup>th</sup> instar and pupae of the both insect pests fluctuated duration of developmental periods of each nymph, adult longevity, consumption rate, survivability rate, size and sex ratio of the predator. *X. flavipes* preferred 1<sup>st</sup>, 2<sup>nd</sup> and 3<sup>rd</sup> instar larvae followed by the 4<sup>th</sup> instar larvae and pupae. The female predator always consumed more prey than the male.

Moreover, the effects of different concentration of Spinosad on egg hatchability and on mortality of larvae, pupae and adult of the both insect pests were found more potential. The concentration rate and exposure period were highly significant in all stages of the both pests. In case of the predator, egg hatchability and mortality rate of nymph and adults showed results almost same as in the control medium. Lower concentrations (0.491, 0.983 and 1.966 $\mu\text{l}/\text{cm}^2$ ) were found not significant on egg, nymph and adult of the predator.

Overall, it was found that the effects of *X. flavipes* and different concentration of Spinosad separately and in combination were highly significant ( $P < 0.001$ ) comparatively than in control to reduce the adult population of *C. pusillus* and *R. dominica* after 3, 6, 9 and 12 months of exposure in storage.

Therefore, the predator, *X. flavipes* and bacterium, Spinosad can be used effectively in the management of *C. pusillus* and *R. dominica* in storage, which is very important from environmental as well as Integrated Pest Management (IPM) and Global Protection Point (GPP) of views.



## References

- Aaron D T 2010. Insects and their chemical weaponry: new potential for drug discovery. *Natural Product Reports* **27**: 1737-1757.
- Aarthi N and Murugan K 2010. Larvicidal and repellent activity of *Vetiveria zizanioides* L, *Ocimum basilicum* Linn and the microbial pesticide Spinosad against malarial vector, *Anopheles stephensi* Liston (Insecta: Diptera: Culicidae). *J. Biopest.* **3**(1):199-204.
- Abbott W S 1925. A method of computing the effectiveness of an insecticide. *J. Econ. Entomol.* **18**: 265-267.
- Abd El-Aziz S E 2011. Control strategies of stored product pests. *J. Entomol.* **8**: 101-122.
- Abd-El-Aziz S E and M A Sherief 2010. Insecticidal effects of modified diatomaceous earth (DE) with different hydroxides (MOH, M=Na, Ca, Al) against *Callosobruchus maculatus* (F.) beetles (Coleoptera: Bruchidae) on stored cowpea grains. *J. Entomol. Res.* **34**: 1-9.
- Abdel-Rahman H A, Shaumar N F, Soliman Z A and El-Agoze M M 1977. Biological studies on the anthocorid bug, *Xylocoris flavipes* (Reuter). *Bulletin de la societe Entomologique d' Egypte* **61**: 45-51.
- Abdel-Rahman H A, Shaumar N F, Soliman Z A and El-Agoze M M 1978-79. Efficiency of the Anthocoridae predator *Xylocoris flavipes* (Reuter). In *Biological Control of stored Grain Insects. Bull. Entomol. Soc. Egypt (Economic)* **11**: 27-34.
- Adler C and Scholler M 1998. Integrated protection of stored products. *IOBC WPRS Bulletin 21 International organization for Biological Control of Noxious Animals and Plants, Dijon, France* 173 pp.
- Ahmed K N and Kabir S M H 1995. Role of the ectoparasite, *Anisopteromalus calandrae*, for control of *Sitophilus oryzae* and *Rhyzopertha dominica*. *Entomon* **20**:175-182.



- Ahmed K N and Khatun M 1994. Effect of temperature and relative humidity on the developmental time and reproductive potential of *Cryptolestes pusillus* Schon, a pest of stored grains. *Bangladesh J. Sci. Ind. Res.* **29**(1): 21-27.
- Ahmed K N, M Khatun and M M Rahman 1991. Biological notes on *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae). *J. Asiat. Soc. Bangladesh Sci.* **17**: 65-67.
- Ahmed M Y Y, Elbadry E A and Salem Y S 1976. Effects of gamma radiation on the reproductive organs of the southern cowpea weevil *Callosobruchus maculatus* F. *Ann. Zool. Ecol. Anim.* **8**(2): 279-284.
- Ahmed S and Grainge M 1986. Potential of the neem tree (*Azadirachta indica*) for pest control and rural development. *Econ. Bot.* **40**(2):201-209.
- Alam M Z 1971. Pests of stored grains and other stored products and their control. *Agric. Inf. Serv.* Dhaka, Bangladesh. pp. 7-10.
- Alam M Z 1991. Review of pesticides regulations: report of *A Report Bangladesh Canada Agricultural team*. Bangladesh Agriculture Research Council, Farmgate, Dhaka. pp. 78.
- Aldryhim Y N 1991. Efficacy of the amorphous silica dust, dryacide, against *Tribolium castaneum* Herbst and *Sitophilus granaris* L. (Coleoptera: Tenebrionidae and Curculionidae). *J. Stored Prod. Res.* **27**: 207-210.
- Aldryhim Y N 1993. Combination of classes of wheat and environmental factors affecting the efficacy of the amorphous silica dust, dryacide, against *Rhyzopertha dominica*. *J. Stored Prod. Res.* **29**: 271-275.
- Ali M M M S 2004. Pesticide uses and food safety. "*The Independent*". January 30 issue. pp.10.
- Ali S H, Hussain M, Rahim A and Mondal K A M S H 1991. Repellent effect of diazinon on *Tribolium castaneum* H. *Bangladesh J. Sci. Ind. Res.* **26** (1-4): 158-162.

- Aller H E and Ramsay J R 1988. RH-5849, a novel insect growth regulator with a new mode of action. *Brighton Crop Proc. Conf. Pest and Diseases* **2**: 511-518.
- Allotey J and W Azlekor 2000. Some aspects of the biology and control using botanicals of the rice moth, *Corcyra cephalonica* on some pulses. *J. Stored Prod. Res.* **36**: 235-244.
- Almeida A A de and Amorim Poy L de F A 1994. Reproduction of *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) in whole and broken grains and on hard and soft varieties of wheat. *Revista Brasileira de Entomologia* **38**(3-4): 599-604.
- Amos T G and Williams P 1977. Insect growth regulators: some effects of methoprene and hydroprene on productivity of several stored grain insects. *Australian J. Zool.* **25**: 201-206
- Andras Szito 2011. Flat grain beetle *Cryptolestes pusillus* Updated on 10/21/2011 12:31:03 PM Available online: PaDIL - <http://www.padil.gov.au>.
- Andrewartha G and Birch L C 1954. *The distribution and abundance of animals*. Chicago, University of Chicago Press, pp. 782.
- Anonymous 1981. Pesticide death: What is the toll? *Ecoforum* **6**: 10.
- Anonymous 1984. Controlled atmospheres and fumigation in gran storage. *Proc. 2nd Ind. Symp. Practical Aspects of CA and fumigation in grain storage*. Perth, 11-12 April 1983. Elsevier, Amsterdam.
- Anonymous 1990. Agro-pesticides: properties and function in Integrated Crop Protection. United Nations Economic and Social commission for Asia and the Pacific. pp. 109-135.
- Anonymous 1991. Report of the Stored Grain Research Laboratory. CSIRO, Canberra. pp.1-32.
- Arbogast R T 1975. Population growth of *Xylocoris flavipes* Reuter: influence of temperature and humidity. *Environ. Entomol.* **4**(5): 825-831.

- Arbogast R T 1976. Suppression of *Oryzaephilus surinamensis* L. (Coleoptera: Cucujidae) on shelled corn by the predator *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae). *J. Ga. Entomol. Soc.* **11**: 67-71.
- Arbogast R T 1978. The biology and impact of the predatory bug *Xylocoris flavipes* Reuter. *Proc. 2<sup>nd</sup> International Conf. Stored Prod. Entomol. Ibadan, Nigeria, September 10-16*. pp. 91-105.
- Arbogast R T 1985. Biological control of stored product insects: status and prospects. In Baur F J (ed.), *Insect Management for food storage and Processing*. American Association of Cereal chemists St. Paul, Minnesota, pp. 225-238.
- Arbogast R T 1991. Beetles: Coleoptera. In: Gorham JR, editor. *Ecology and Management of Food Industry Pests*. Association of Official Analytical Chemists. pp. 131-176.
- Arbogast R T, Carthon M and Roberts J R 1971. Developmental stages of *Xylocoris flavipes* (Hemiptera: Anthocoridae), a predator of stored product insects. *Ann. Entomol. Soc. Am.* **64**: 1131-1134.
- Arbogast R T, Lecato G L and Carthon M 1977. Longevity of fed and starved *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae) under laboratory conditions. *J. Georgia Entomol. Soc.* **12**(1): 58-64.
- Arbogast R T, Flaherty B R and Press J W 1983. Demography of the predaceous bug, *Xylocoris sordidus* Reuter. *The American Midland Naturalist* **109**(2): 398-405.
- Arbogast R T and Mullen M A 1988. Insect succession in a stored-maize ecosystem in southeast Georgia. *J. Econ. Entomol.* **81**: 899-912.
- Armitage D M 1987. Controlling insects by cooling grain. In *stored product pest control* (Lawson T J. ed), British Crop Protection Council, Monograph No. 37. The British Crop Protection Council, Thornton Heath. pp. 219-227.

- Arthur F H 1994. Residual efficacy of cyfluthrin emulsifiable concentrate and wettable powder formulations on porous concrete and on concrete sealed with commercial products prior to insecticide application. *J. Stored Prod. Res.* **30**: 79-86.
- Arthur F H 1996. Grain protectants: current status and prospects for the future. *J. Stored Prod. Res.* **32**(4): 293–302.
- Arthur F H 1997a. Differential effectiveness of deltamethrin dust on plywood, concrete and tile surfaces against three stored-product beetles. *J. Stored Prod. Res.* **33**: 167-173.
- Arthur F H 1997b. Residual susceptibility of *Plodia interpunctella* to deltamethrin dust: effects of concentration and time of exposure. *J. Stored Prod. Res.* **33**: 313-319.
- Arthur F H 1998a. Residual studies with cyfluthrin wettable powder: toxicity toward red flour beetles (Coleoptera: Tenebrionidae) exposed for short intervals on treated concrete. *J. Econ. Entomol.* **91**: 309-319.
- Arthur F H 1998b. Residual toxicity of cyfluthrin wettable powder against *Tribolium confusum* (Coleoptera: Tenebrionidae) exposed for short time intervals on concrete. *J. Stored Prod. Res.* **34**: 19-25.
- Arthur F H 1999a. Survival of red flour beetles (Coleoptera: Tenebrionidae) on concrete partially treated with cyfluthrin. *J. Econ. Entomol.* **92**: 981-987.
- Arthur F H 1999b. Effect of temperature on residual toxicity of cyfluthrin wettable powder. *J. Econ. Entomol.* **92**: 695-699.
- Arthur F H 2000. Toxicity of diatomaceous earth to red flour beetles and confused flour beetles (Coleoptera: Tenebrionidae): effects of temperature and relative humidity. *J. Econ. Entomol.* **93**: 526-532.
- Arthur F H 2004a. Evaluation of a new insecticide formulation (F<sub>2</sub>) as a protectant of stored wheat, maize, and rice. *J. Stored Prod. Res.* **40**: 317-330.

- Arthur F H 2004b. Evaluation of methoprene alone and in combination with diatomaceous earth to control *Rhyzopertha dominica* (Coleoptera: Bostrichidae) on stored wheat. *J. Stored Prod. Res.* **40**: 485-498.
- Arthur F H and Flinn P W 2000. Aeration management for stored hard red winter wheat: simulated impact on rusty grain beetle (Coleoptera: Cucujidae) populations. *J. Econ. Entomol* **93**: 1364–1372.
- Arthur F H and Puterka G J 2002. Evaluation of kaolinite based particle films to control *Tribolium* species (Coleoptera: Tenebrionidae). *J. Stored Prod. Res.* **38**: 341-348.
- Arthur F H and Phillips T W 2003. Stored-product insect pest management and control. Y H Hui, B L Bruinsma, J R Gorham, W K Nip, P S Tong, P Ventresca (eds.), Food Plant Sanitation, Marcel Dekker, Inc., New York, pp. 223–286.
- Arthur F H and Throne J E 2003. Efficacy of diatomaceous earth to control internal infestations of rice weevil and maize weevil (Coleoptera: Curculionidae) *J. Econ. Entomol.* **96**: 510-518.
- Arthur F H and Casada M E 2005. Feasibility of summer aeration for management of wheat stored in Kansas. *Applied Eng. In Agric.* **21**(6): 1027-1038.
- Arthur F H, Hagstrum D W, Flinn P W, Reed C R and Phillips T W 2006. Insect populations in grain residues associated with commercial Kansas grain elevators. *J. Stored Prod. Res.* **42**: 226–239.
- Arthur F H, Yang Y, Wilson L T and Siebenmorgen T J 2008. Feasibility of automatic aeration for insect pest management for rice stored in east Texas. *Applied Eng. in Agric.* **24**(3): 345-350.
- Arthur F H, Johnson J A, Neven L G, Hallman G J, Follett P A 2009. Insect pest management in postharvest ecosystems in the United States of America. *Outlooks on Pest Management* **20**: 279–2842.

- Arthur F H and Casada M E 2010. Directional flow of summer aeration to manage insect pest in stored wheat. American Society of Agricultural and Biological Engineers. *Applied Engineering in Agri.* **26**(1): 115-122.
- Arthur F H, Yang Y and Wilson L T 2011. Use of web-based model for aeration management in stored rough rice. *J. Econ. Entomol.* **104**: 702–708.
- Arthurs S P, Lacey L A and Miliczky E R 2007. Evaluation of the codling moth granulosis virus and spinosad for codling moth control and impact on non-target species in pear orchards. *Biological Control* **41**: 99–109.
- Ashraf M and Brower J H 1974. Histological studies of irradiation effects on the gonads of *Tenebrio molitor* (Coleoptera: Tenebrionidae). *J. Ga. Ent. Soc.* **9**(4): 223-228.
- Askew R R 1971. *Parasitic insects*. Heinemann Educational Books, London. pp 215.
- Athanassiou C G, Papagregoriou A S and Buchelos C T 2004. Insecticidal and residual effect of three pyrethroids against *Sitophilus oryzae* (L.) (Coleoptera: Curculionidae) on stored wheat. *J. Stored Prod. Res.* **40**: 289-297.
- Athanassiou C G, Kavallieratos N G and Andris N S 2004a. Insecticidal effect of three diatomaceous earth formulations against adults of *Sitophilus oryzae* (Coleoptera: Curculionidae) and *Tribolium confusum* (Coleoptera: Tenebrionidae) on oat, rye and triticale. *J. Econ. Entomol.* **97**: 2160-2167.
- Athanassiou C G, Kavallieratos N G, Vayias B J, Dimizas C B, Papagregoriou A S and Buchelos C T 2004b. Residual toxicity of beta cyfluthrin, alpha cypermethrin and deltamethrin against *Tribolium confusum* Jacquelin du Val (Coleoptera: Tenebrionidae) on stored wheat. *Appl. Entomol. Zool.* **39**: 195-202.
- Athanassiou C G and Kavallieratos N G 2005. Insecticidal effect and adherence of PyriSecs in different grain commodities. *Crop Prot.* **24**: 703–710.
- Athanassiou C G, Vayias B J, Dimizas C B, Kavalieratos N G, Papagregoriou A S and Buchelos C T 2005a. Insecticidal efficacy of diatomaceous earth against *Sitophilus oryzae* L. (Coleoptera: Curculionidae) and *Tribolium confusum* Duval (Coleoptera: Tenebrionidae) on stored wheat: influence of dose rate, temperature and exposure interval. *J. Stored Prod. Res.* **41**: 47–55.

- Athanassiou C G, Kavallieratos N G, Peteinatos G G, Petrou S E, Boukouvala M C and Tomanovi C Z 2007. Influence of temperature and humidity on insecticidal effect of three diatomaceous earth formulations against the larger grain borer (Coleoptera: Bostrychidae). *J. Econ. Entomol.* **100**: 599-603.
- Athanassiou C G, Kavallieratos N G, Chintzoglou G J 2008a. Effectiveness of spinosad dust against different European populations of the confused flour beetle, *Tribolium confusum* Jacquelin du Val. *J. Stored Prod. Res.* **44**: 47–51.
- Athanassiou C G, Kavallieratos N G, Chintzoglou G J, Peteinatos G G, Boukouvala M C, Petrou S S and Panoussakis E C 2008b. Effect of temperature and grain on insecticidal efficacy of spinosad dust against *Sitophilus oryzae* (Coleoptera: Curculionidae) and *Rhyzopertha dominica* (Coleoptera: Bostrichidae). *J. Econ. Entomol.* **101**: 976–981.
- Athanassiou C G, Kavallieratos N G, Yiatislis A E, Vayias B J, Mavrotas C S, Tomanovic Z 2008c. Influence of temperature and humidity on the efficacy of spinosad against four stored-grain beetle species. *J. Ins. Sci.* **8**: 1-9.
- Athanassiou C G, Arthur F H and Throne J E 2009a. Efficacy of grain protectants against four psocid species on maize, rice and wheat. *Pest Manage. Sci.* **65**:1140–1146
- Athanassiou C G, Arthur F H and Throne J E 2009b. Efficacy of spinosad in layer-treated wheat against five stored-product insect species. *J. Stored Prod. Res.* **45**: 236–240
- Athanassiou C G, Arthur F H and Throne J E 2010a. Effects of short exposures to spinosad-treated wheat or maize on four stored-grain insects. *J. Econ. Entomol.* **103**:197–202.
- Athanassiou C G, Kavallieratos N G, Menti H and Karanastasi E 2010b. Mortality of four stored product pests in stored wheat when exposed to doses of three entomopathogenic nematodes. *J. Econ. Entomol.* **103**: 977–984.

- Athanassiou C G, Arthur F H, Kavallieratos N G and Throne J E 2011. Efficacy of spinosad and methoprene, applied alone or in combination, against six stored-product insect species. *J. Pestic. Sci.* **84**: 61-67.
- Atui M B, Flinn P W, Lazzaria S M N and Lazzaria F A 2007. Detection of *Rhyzopertha dominica* larvae in stored wheat using ELISA: the impact of myosin degradation following fumigation. *J. Stored Prod. Res.* **43**:156–159.
- Awadallah K T and Tawfik M F S 1972. The biology of *Xylocoris* (*Piezostethus*) *flavipes* Reuter. *Bull. Entomol. Soc. Egypt* **56**: 177-189.
- Awadallah K T and Tawfik M F S 1973. The biology of *Xylocoris flavipes* Reuter. (Hemiptera: Anthocoridae). *Bulletin de la Societe Entomologique d' Egypte* **56**:177-189.
- Awadallah K T, Tawfik M F S and El-Husseini M M 1986. Bio-cycle of the anthocorid predator *Xylocoris flavipes* Reuter in association with rearing on major pests of stored drug materials. *Bulletin de la Societe Entomologique d' Egypte* **66**: 27-33.
- Back E A and Cotton R T 1922. US Department of Agriculture. Farmers' Bulletin. **1260**: 46.
- Backhouse A, Sait S M and Cameron T C 2012. Multiple mating in the traumatically inseminating warehouse pirate bug, *Xylocoris flavipes*: effects on fecundity and longevity. *Biological Letters* 9 May 2012 doi:10.1098/rsbi. 2012. 0091
- Bahgat I M, Kady G A E L, Temerak S A and Lysaandrou M 2007. The natural bio-insecticide spinosad and its toxicity to combat some mosquito species in Ismailia Governorate. *Egypt World J. Agri. Sci.* **3(4)**: 396-400.
- Baker J E 1995. Stability of malathion resistance in two hymenopterous parasitoids. *J. Econ. Entomol.* **88**: 232-236.



- Baker J E and Arbogast R T 1995. Malathion resistance in field strains of the warehouse pirate bug (Heteroptera: Anthocoridae) and a prey species *Tribolium castaneum* (Coleoptera: Tenebrionidae). *J. Econ. Entomol.* **88**: 241-245.
- Banken J A O and Stark J D 1998. Multiple routes of pesticide exposure and the risk of pesticides to biological controls: a study of neem and the seven spotted lady beetle (Coleoptera: Coccinellidae). *J. Econ. Entomol.* **91**: 1- 6.
- Banks H J 1980. Identification of stored product *Cryptolestes* spp. (Coleoptera: Cucujidae) a rapid technique for preparation of suitable mounts. *J. Aust. Ent. Soc.* **18**: 217-222.
- Banks H J and Fields J B 1995. Physical methods for insect control in stored-grain ecosystem. In *Stored Grain Ecosystem*, Jayas D S, White N D G and Muir W E (Eds.). Marcel Dekker, New York. pp.353-409.
- Barker P S 1976. Sex-related tolerance to 1, 2-dibromomethane in *Cryptolestes ferrugineus* Stephens. *J. Stored Prod. Res.* **12**: 59-61.
- Bartholomaeus A R and Haritos V S 2005. Review of the toxicology of carbonyl sulfide, a new grain fumigant. *Food. Chem. Toxicol.* **43**: 1687-1701.
- Bashir T 2002. Reproduction of *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) on different host-grains. *Pakistan J. Biol. Sci.* **5**: 91–93.
- Beiriger R L and Sites R W 1996. The Bostrichidae (Coleoptera) of *Missouri*. *J. Kansas Entomol. Soc.* **69**: 45–68.
- Bell C H 1987. Effect of grain moisture content on the establishment and maintenance of a low oxygen atmosphere containing carbon dioxide. In *Stored Prod. Pest Control* (Lawson T J, ed), *British Crop Prot. Monogr.* **37**: 237-246.
- Bell C H, Savvidou N and Wontnersmith T J 1999. The toxicity of fluoride (Vikane) to eggs of insect pests of flour mills. *Proc. 7th Int. Work. Conf. Stored Prod. Prot. Beijing, PR China*, October 14-16, 1988(Zuxun J, Quan L, Yongsheng L, Xianchang T and Lianghua G, eds). **1**: 1345-350.

- Bengston M 1987. Insect growth regulators. *Proc. 4th Int. Work. Conf. on stored prod. Entomol.* Tel Aviv, Israel (E. Donahaye and S. Navarro, eds). pp 34-46.
- Bernardo U and Viggiani G 2000. Effects of spinosad, a new insect control agent naturally derived on the mealy bug parasitoid *Leptomastix dactylopii* Howard (Hymenoptera: Encyrtidae). *Bulletin BC / WPRS*. **23**: 81-84.
- Birch L C 1945a. The mortality of the immature stages of *Calandra oryzae* L. (small strain) and *Rhizopertha dominica* F. in wheat of different moisture contents. *Australian J. Experi. Biology and Medical Sci.* **23**: 141–145.
- Birch L C 1945b. The influence of temperature on the development of the different stages of *Calandra oryzae* L. and *Rhizopertha dominica* F. (Coleoptera). *Australian J. Experi. Biology and Medical Sci.* **23**: 29–35.
- Birch L C 1945c. The influence of temperature, humidity and density on the oviposition of the small strain of *Calandra oryzae* L. and *Rhizopertha dominica* Fab (Coleoptera). *Australian J. Experi. Biology and Medical Sci.* **23**: 197–203.
- Birch L C 1953. Experimental background to the study of the distribution and abundance of insects-I: the influence of temperature, moisture and food on the innate capacity for increase of three grain-beetles. *Eco.* **34**: 698–711.
- Blanc M P, Panighini C, Gadani F and Rossi L 2004. Activity of spinosad on stored-tobacco pests and persistence on cured tobacco strips. *Pest Manage. Sci.* **60**: 1091–1098.
- Blum M S 1981. *Chemical Defenses of Arthropods*. Academic Press, New York, USA.
- Boek L D, Hang C, Eaton T E, Godfrey O W, Michel K H, Nakatsukasa W M and Yak R C 1994. Process for producing A83543 compounds. US Patent No. 5,362,634. Assigned to Dow Elanco.
- Bond J G, Marina C F and Willams T 2004. The naturally derived insecticide spinosad is highly toxic to *Aedes* and *Anopheles* mosquito larvae. *Medical and Veterinary Entomol.* **18**: 50-56.

- Bonjour E L, Phillips T W and Pitts J T 2006. Spinosad provides long-term protection for stored wheat. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolini O F L de, Sartori M R, Elias M C, Guedes R N C, Fonseca R G da, Scussel V M (eds.), *Proc. 9th Int. Work. Conf. for Stored Prod. Protec.* 15–18 October 2006, ABRAPOS, Campinas, São Paulo, Brazil (2006). pp.1189–1193.
- Bonjour E L, Opit G P, Hardin J, Jones C L, Payton M E and Beeby R L 2011. Efficacy of ozone fumigation against the major grain pests in stored wheat. *J. Econ. Entomol.* **104**(1): 308-316.
- Boucher J 1999. Effect of Spinosad on bell peppers pests and beneficial arthropods 1998. *Arthropod Manage. Test* **24**: 144.
- Bousquet Y 1990. Beetles associated with stored products in Canada: an identification guide Agriculture and Agri-Food Canada.
- Breese M H 1960. The infestibility of stored paddy by *Sitophilus sasakii* T. and *Rhyzopertha dominica* F. *Bull. Ent. Res.* **51**: 599–630.
- Bret B L, Larson L L, Schoonover J R, Sparks T C and Thompson G D 1997. Biological properties of spinosad. *Down to Earth* **52**: 6-13.
- Brower J H 1990. Pests of stored products. In Habeck D H, Bennett F D and Frank J H [eds], *Classical Biological Control in the Southern United States. Southern Cooperative Series Bull.* **355**: 113-122.
- Brower J H 1991. Biologicals: insect diseases, insect parasites and predators. In Krischik V, Cuperus G and Galliard D (eds.), *Management of Grain. Bulk Commodities and Bagged Products.* USDA and Oklahoma State University Cooperative Extension Service, *Circular E.* **912**: 195-200.
- Brower J H and Press J W 1988. Interaction between the egg parasite *Trichogramma pretiosum* (Hymenoptera: Trichogrammatidae) and a predator, *Xylocoris flavipes* (Hemiptera: Anthocoridae) of the almond moth, *Cadra cautella*, (Lepidoptera: Pyralidae). *J. Entomol. Sci.* **23**: 342-349.

- Brower J H and Press J W 1992. Suppression of residual populations of stored product pests in empty corn bins by releasing the predator *Xylocoris flavipes* Reuter. *Biological Control* **2**(1): 66-72.
- Brower J and Mullen M A 1990. Effects of *Xylocoris flavipes* (Hemiptera: Anthocoridae) release on moth population in experiment peanut storages. *J. Entomol. Sci.* **25**: 268-276.
- Brower J L, Smith L, Vail P V and Flinn P F 1995. Biological control. Bh Subramanyam, D W Hagstrum (Eds.). *Integrated Management of Insects in Stored Products* Marcel Dekker Inc. New York. pp. 223–286.
- Brower J H, Smith L, Vail P V and Flinn P W 1996. Biological Control. In *Management of Insects in Stored Products*, Hagstrum D W and Subramanyam Bh (Eds.). Marcel Dekker, New York. pp. 223-286.
- Bryne P J, Bacon J R, and Toensmeyer U C 1994. Pesticide residue concerns and shopping locations. *Agribusiness* **10**: 41-50.
- Burkholder W E 1981. Biological suppression of stored-product insect pests. In G C Papavizas [ed], *Biological control in crop production*. Beltsville *Symp. Agri. Res. (BARC)* 5, Allanheld, Osmun, Totowa, pp. 391-399.
- Burkholder W E and Ma M 1985. Pheromones for monitoring and control of stored-product insect. *Ann. Rev. Entomol.* **30**: 257-272.
- Burkholder W E and Faustini D L 1991. Biological methods of survey and control. In *Ecology and Management of Food Industry Pests* (J R Gorham ed), AOAC press. pp. 361-372.
- Burks C S, Hagstrum D W and Beker J E 1999. Selection of cold injury treatments to facilitate release of the parasitoid *Anisopteromalus calandrae* (Hymenoptera: Pteromalidae) reared on the rice weevil (Coleoptera : Curculionidae). *J. Econ. Entomol.* **92**: 473- 479.

- Burrell N J 1967. Grain cooling studies-II: Effect of aeration on infested grain bulks. *J. Stored Prod. Res.* **3**: 145-154.
- CABI Crop Protection Compendium 2008. *Cryptolestes pusillus*. CABI, Wallingford, UK.
- Campbell A and Sinha R N 1976. Damage of wheat by feeding of some stored product beetles. *J. Econ. Entomol.* **69**: 11-13.
- Campbell J F, Mullen M A and Dowdy A K 2002. Monitoring stored-product pests in food processing plants with pheromone trapping, contour mapping and mark-recapture. *J. Econ. Entomol.* **95**: 1089-1101.
- Casada M E, Arthur F H and Akdogan H 2002. Temperature monitoring and aeration strategies for stored wheat in the central plains. A S A E paper No. 026116, St. Joseph, Mich.
- Cetin H, Yanikoglu A and Cilek J E 2005a. Evaluation of the naturally-derived insecticide spinosad against *Culex pipiens* L. (Diptera: Culicidae) larvae in septic tank water in Antalya, Turkey. *J. Vector Ecol.* **30**: 151-154.
- Cetin H, Yanikoglu A and Cilek J E 2005b. Evaluation of the naturally-derived insecticide spinosad against *Culex pipiens* L. (Diptera: Culicidae) larvae in septic tank water in Antalya, Turkey. *J. Vector Eco.* **30**: 151-154.
- Champ B R 1986. Occurrence of resistance to pesticides in grain storage pests. In *Pesticides and humid tropical grain storage systems* (Champ B R and Highly E Eds). *Australian Centre for Int. Agri. Res.* Canberra. pp.229-225.
- Champ B R 1979. Pesticide resistance and its current significance in control of pests of stored products. *Proc. Second Int. Work. Conf. Stored Prod. Ent.* September 10-16,1978, Ibadan, Nigeria. pp.159-181.
- Champ B R and Dyte C E 1976. Report of the FAO Global Survey of Pesticide Susceptibility of Stored Grain Pests (FAO Plant Production and Protection Series No. 5). FAO, Rome pp. 297.

- Chanbang Y, Arthur F H, Wilde G E and Throne J E 2007. Efficacy of diatomaceous earth to control *Rhyzopertha dominica* (F.) (Coleoptera: Bostrichidae) in rough rice: impacts of temperature and relative humidity. *Crop Protect.* **26** (7): 923-929.
- Chanbang Y, Arthur F H, Wilde G E and Throne J E 2007a. Efficacy of diatomaceous earth to control *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) in rough rice: impacts of temperature and relative humidity. *Crop Protec.* **26**: 923-929.
- Chanbang Y, Arthur F H, Wilde G E and Throne J E 2007b. Diatomaceous earth plus methoprene for control of the lesser grain borer, *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) in rough rice. *J. Stored Prod. Res.* **43**: 396-401.
- Chanbang Y, Arthur F H, Wilde G E and Throne J E 2008. Hull characteristics as related to susceptibility of different varieties of rough rice to *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *J. Stored Prod. Res.* **44**: 205-212.
- Chao Y, Simkover H G, Telford H S and Stallcop P 1953. Field infestation of stored grain insects in eastern Washington. *J. Econ. Entomol.* **46**: 905-907.
- Chapman A D 2006. Numbers of living species in Australia and the World. Canberra. *Australian Biological Resources Study*.60.
- Charnov E L 1976. Optimal foraging: attack strategy of a mantid. *Ann. Nat.* **110**: 141-151.
- Chintzoglou G J, Athanassiou C G and Arthur F H 2008a. Insecticidal effect of spinosad dust, in combination with diatomaceous earth, against two stored-grain beetle species. *J. Stored Prod. Res.* **44**: 347-353.
- Chintzoglou G J, Athanassiou C G, Markoglou A N and Kavallieratos N G 2008b. Influence of commodity on the effect of spinosad dust against *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) and *Sitophilus oryzae* L. (Coleoptera: Curculionidae). *Int. J. Pest Manage.* **54**: 277-285.

- Chittenden F H 1911. The lesser grain borer and the larger grain borer *Bull. United State Bureau Entomol.* **96**: pp. 29-47.
- Chujo M 1958. Coleoptera: Bostrychidae. *Insects of Micronesia.* **16**: 85–104.
- Ciesielska Z 1975. Studies of interspecific competition at early growth stages of a population of granary beetles (*Oryzaephilus surinamensis* L., *Sitophilus granarius* L. and *Rhyzopertha dominica* F.). *Ecologia Polska* **23**: 163-183.
- Cleveland C B, Bormett G A, Saunders D G, Powers F L, McGibbon A S, Reeves G L, Rutherford L, and Balcer J L 2002. Environmental fate of spinosad. 1. Dissipation and degradation in aqueous systems. *J. Agric. Food Chem.* **50**(11): 3244-3256.
- Cleveland C B, Mayes M A and Cryer S A 2001. An ecological risk assessment for spinosad use on cotton. *Pest Manage. Sci.* **58**: 70–84.
- Cline D L 1973. Rearing the lesser grain borer on ground dog biscuits to obtain mature larvae and pupae. *Ann. Entomol. Soc. Am.* **66**: 551-552.
- Cline I D, Press J W and Flaherty B R 1985. Suppression of the rice weevil, *Sitophilus oryzae* (Coleoptera: Curculionidae), inside and outside of burlap, woven polypropylene and cotton bags by the parasitic wasp, *Anisopteromalus calandrae* (Hymenoptera: Pteromalidae). *J. Econ. Entomol.* **78**: 835-838.
- Cline L B and Press J W 1990. Reduction in almond moth (Lepidoptera: Pyralidae) infestations using commercial packaging of foods in combination with the parasitic waps, *Bracon hebetor* (Hymenoptera: Braconidae). *J. Econ. Entomol.* **83**: 1110-1113.
- Cochran D G 1982. Cockroaches. Biology and Control. WHO/VBC/82. **856**. 1-53.
- Cohen A C 1995. Extra-oral digestion in predaceous terrestrial Arthropoda. *Ann. Rev. Entomol.* **40**: 85–103.

- Collins P J 1998. Resistance to grain protectants and fumigants in insect pests of stored products in Australia. H J Banks, E J Wright, K A Damcevski (eds.), *Stored Grain in Australia. Proc. First Australian Postharvest Technical Conf.* 26–29 May, 1998. Canberra, Australia. pp 55-57.
- Collins P J 2006. Resistance to chemical treatments in insect pests of stored grain and its management. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolini O F L de, Sartori M R, Elias M C, Guedes N R C, Fonseca R G da, Scussel V M (Eds.), *Proc. 9<sup>th</sup> Int. Work. Conf. Stored Prod. Protect.* 15–18 October 2006, ABRAPOS, Campinas, São Paulo, Brazil, pp. 277-282.
- Collins P J, Lambkin T M, Bridgeman B W and Pulvirenti C 1993. Resistance to grain protectant insecticides in coleopterous pests of stored cereals in Queensland, Australia. *J. Econ. Entomol.* **86**: 239-245.
- Collins D A and Cook D A 1998. Periods of protection provided by different formulations of pirimiphos-methyl and etrimfos, when admixed with wheat, against four susceptible storage beetle pests. *Crop. Protect.* **17**(6): 521-528.
- Collins P J, Darglish G J, Bengston M, Lambkin T M and Pavic H 2002. Genetics of resistance to phosphine in *Rhyzopertha dominica* (Coleoptera: Bostrichidae). *J. Econ Entomol.* **95**: 862–869.
- Consili F L, Botelho P S M and Parra J R P 2001. Selectivity of insecticides to the egg parasitoid *Trichogramma galloi* Zucchi (Hymenoptera: Trichogrammatidae). *J. Appl. Entomol.* **125**: 37- 43.
- Copping L G 2001. *The biopesticide manual: a world compendium.* 2<sup>nd</sup> Ed. British Crop Protection Council, Farnham, UK
- Copping L G and Menn J J 2000. Biopesticides: a review of their action, applications and efficacy. *Pest Manage. Sci.* **56**: 651–676.



- Cotton R T 1963. *Pests of stored grain and grain products*. Burgess Co. pp. 333.
- Cotton R T and Good N E 1937. Annotated list of the insects and mites associated with stored grain and cereal products and of their arthropod parasites and predators. USDA Miscellaneous Publication **258**: 80.
- Cox P D, Fleming D A, Atkinson J E, Bannon K L and Whitfield J M 1997. The effect of behaviour on the survival of *Cryptolestes ferrugineus* in an insecticide treated laboratory environment. *J. Stored Prod. Res.* **33**: 257-269.
- Croft B A 1990. *Arthropod Biological Control Agents and Pesticides*. 1st ed., John Wiley and Sons, New York.
- Crombie A C 1941. On oviposition, olfactory conditioning and host selection in *Rhyzopertha dominica* F. (Coleoptera). *J. Exp. Biol.* **18**: 62-79.
- Crombie A C 1944. On intraspecific and interspecific competition in larvae of graminivorous insects. *J. Exp. Bio.* **20**: 135-151.
- Cross E A and Krantz W G 1964. Two new species of the genus *Acarophenax* Newstead and Duvall (Acarina: Pyemotidae). *Acarologia* **6**: 287-295.
- Crouse G D and T C Sparks 1998. Naturally derived materials as products and leads for insect control: the spinosyns. *Rev. Toxicol.* **2**:133-46.
- Crouse G D, Sparks T C, Schoonover J, Gifford J, Dripps J, Bruch T, Larson L L, Gaglich J, Hatton C, Hill R L, Worden T V and Martynow J G 2001. Recent advances in the chemistry of spinosyns. *Pest Manage. Sci.* **57**: 177-185.
- Crowder I D 1986. *The use of microwaves to control pests of stored products*. Ph D Thesis, University of Newcastle upon Tyne, UK 111pp.
- Daglish G J 1998. Efficacy of six grain protectants applied alone or in combination against three species of Coleoptera. *J. Stored Prod. Res.* **34**: 263-268.

- Daglish G J 2006. Opportunities and barriers to the adoption of potential new grain protectants and fumigants. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolini O F L de, Sartori M R, Elias M C, Guedes R N C, Fonseca R G da, Scussel V M (Eds.), *Proc. 9th Int. Work. Conf. Stored Prod. Protect.* ABRAPOS, Campinas, Sao Paulo, Brazil, pp. 209–216.
- Daglish G J 2008. Impact of resistance on the efficacy of binary combinations of spinosad, chlorpyrifos-methyl, and s-methoprene against five stored-grain beetles *J. Stored Prod. Res.* **44**: 71–76.
- Daglish G J, Eelkema M and Harrison L M 1995. Chlorpyrifos-methyl plus either methoprene or synergized phenothrin for control of coleopteran in maize on Queensland, Australia. *J. Stored Prod. Res.* **31**: 235-241.
- Daglish G J and Wallbank B E 2002. Searching for candidate insecticides for disinfestation and protection of grain. Wright E J, Banks H J, Highley E (Eds.), *Stored Grain in Australia 2000*, CSIRO Stored Grain Research Laboratory, Canberra, pp. 169-173.
- Daglish G J, Nayak M K and Byrne V S 2003. Is there a role for spinosad in protecting Australian grain from insects. Wright E J, Webb M C, Highley E (Eds.), *Stored Grain in Australia. Proc. Australian Postharvest Technical Conf.* CSIRO Stored Grain Research Laboratory, Canberra, pp. 78-81.
- Daglish G J and Nayak M K 2006. Long-term persistence and efficacy of spinosad against *Rhyzopertha dominica* (Coleoptera: Bostrychidae) in wheat. *Pest Manage. Sci.* **62**: 148-152.
- Daglish G J, Head M B and Hughes P B 2008. Field evaluation of spinosad as a grain protectant for stored wheat in Australia: efficacy against *Rhyzopertha dominica* F. and fate of residues in whole wheat and milling fractions. *Aust. J. Entomol.* **47**: 70-74.

- Daglish G J, Ridley A W and Walter G H 2010. Resistance management and the ecology of *Rhyzopertha dominica* (F.) and *Tribolium castaneum* (Herbst) in subtropical Australia. Carvalho M O, Fields P G, Adler C S, Arthur F H, Athanassiou C G, Campbell J F, Fleurat-Lessard F, Flinn P W, Hodges R J, Isikber A A, Navarro Noyes R T, Riudavets J, Sinha K K, Thorpe G R, Timlick B H, Trematerra P, White N D G (eds.), *Proc. 10th Int. Work. Conf. Stored Prod. Protect.* Estoril, Portugal. pp.104–109.
- Dakshinamurthy A and Goel S C 1992. Insect management in grain and seed storage of wheat using non-hazardous materials. *Proc. Nat. Symp. Growth Development and Control Tech. Insect Pests, Nabibagh, Vopal, India.* pp. 265-268.
- Damcevski K, Dojchinov G and Haritos V S 2003. VAPORMATETM, a formulation of ethyl formate with CO<sub>2</sub>, for disinfestation of grain. *Proc. Australian Postharvest Technical Conf. On Stored Grain in Australia 2003, June 25-27,CSIRO,Canberra,* pp. 199-204.
- Darriet F, Duchon S and Hougard J M 2005. Spinosad: a new larvicide against insecticide-resistant mosquito larvae. *J. American Mosquito Control Associa.* **21**: 495-496.
- Darriet F and Corbel V 2006. Laboratory evaluation of pyriproxyfen and spinosad, alone and in combination, against *Aedes aegypti* larvae. *J. Medical Entomol.* **43**: 1190-1194.
- Daule A H 2005. Effect of temperature and relative humidity on the biology of the stem borer parasitoid *Pediobius furvus* Gahan (Hymenoptera: Eulophidae) for the management of stem borers. *Environ. Entomol.* **34**(1): 1-5.
- Davies R G 1949. The biology of *Laemophloeus minutus* Oliv. (Col: Cucujidae). *Bull. Ent. Res.* **40**: 63-82.
- De Bach P and Rosen D 1991. *Biological control by natural enemies.* 2<sup>nd</sup> Ed. Cambridge University Press, Cambridge.

- De Bach P H 1964. *Biological control of insect pests and weeds*. Reinhold, New York. pp. 844.
- Delestal P 1998. Spinosad y azadiractina: efectos de dos plaguicidas de origen natural en el chinche depredador *Podisus maculiventris* Say (Hemiptera: Pentatomidae). *Boletín Vinuela E, Adan A, Gonzalez M, Budia F, Smagghe G, De Clercq P, Vogt H and Sanidad Vegetal Plagas* **24**: 57-66.
- Desmarchelier J M and Dives J C 1987. Dryacide treatment of stored wheat, its efficacy against insects and after processing . *Australian J. Exp. Agri.* **27**: 309-312.
- DeVrise D H and Georghiou G P 1979. Influence of temperature on toxicity of insecticides to susceptible and resistant houseflies. *J. Econ. Entomol.* **72**: 48-50.
- Dhaliwal G S 1976. Intensity of insect infestation under rural storage conditions in Punjab. *Entomologist newsletter* **6**: 40-50.
- Dimetry N Z 2012. Prospects of botanical pesticides for the future in integrated pest management programme (IPM) with special reference to neem uses in Egypt. *Archives of Phytopathology and Plant Protect.* **45**(10): 1138–1161.
- Dimetry N Z Hafez M and M H Abbass M H 2002. Efficiency of some oils and neem formulations against the cowpea beetle, *Callosobrohus maculatus* F. (Coleoptera: Bruchidae). In *Biopesticide and Pest Management* Koul O, Dhaliwal G S, Marwaha S S and Arora J K (eds.). Vol.2. International Campus Books, NewDelhi, pp. 1-10.
- Doane R W 1919. Weevils in Australian wheat in California. *J. Econ. Entomol.* **12**: 308–312.
- Donnelly B E and Phillips T W 2001. Functional response of *Xylocoris flavipes* (Hemiptera: Anthocoridae) effects of prey species and habitat. *Environ. Entomol.* **30**: 617- 624.
- Dow Elanco 1994. *Spinosad Technical Guide*. Dow Elanco, Indianapolis, IN, USA.

- Dow Agro Sciences. 1997. *Spinosad Technical Bulletin*. Dow AgroSciences. 15 pp.
- Dowdy A K and Mc Gaughey W H 1994. Seasonal activity of stored-product insects in and around farm-stored wheat. *J. Econ. Entomol.* **87**: 1351–1358.
- Dowdy A K and Mc Gaughey W H 1998. Stored-product insect activity outside of grain masses in commercial grain elevators in the Midwestern United States. *J. Stored Prod. Res.* **34**: 129–140.
- Dowell F E, Throne J E and Baker J E 1998. Automated nondestructive detection of internal insect infestation of wheat kernels using near-infrared reflectance spectroscopy. *J. Econ. Entomol.* **91**: 899-904.
- Dunkel F V and Jaronski S T 2003. Development of a bioassay system for the predator, *Xylocoris flavipes* (Heteroptera: Anthocoridae), and its use in subchronic toxicity/pathogenicity studies of *Beauveria bassiana* Strain GHA. *J. Econ. Entomol.* **96**: 1045-1053.
- Durrant J E 1921. Insect associated with grain etc. Rep Grain Pests (war) Committee. **9**: 33, 35, 37, 38, 46-48.
- Dyson T 1999. World food trends and prospects to 2025. *Proc. National Academy Sci. USA*, **96**: 1–13.
- Edde P A 2012. A review of the biology and control of the lesser grain borer, *Rhyzopertha dominica*. *J. Stored Prod. Res.* **48**: 1-8.
- Edde P A and Phillips T W 2006a. Potential host affinities for the lesser grain borer, *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae): behavioral responses to host odors and pheromones and reproductive ability on non-grain hosts. *Entomologia Experimentalis et Applicata* **119**: 255-263.
- Edde P A and Phillips T W 2006b. Longevity and pheromone output in stored product Bostrichidae. *Bull. Entomol. Res.* **96**: 547-554.

- Edde P A, Phillips T W and Toews M D 2005. Responses of *Rhyzopertha dominica* (Coleoptera: Bostrichidae) to its aggregation pheromones as influenced by trap design, trap height and habitat. *Environ. Entomol.* **34**: 1549-1557.
- Edwards J P and Menn J J 1981. The use of juvenoid in insect pest management. In *Chemic der Pflanzenschutz and Schadlingsbecamfungsmittel* (R Wegler ed) Springer- Verlag, Berlin **6**: 185-214.
- Eisa A A, Ammar I M A and El-Sheikh A E A 1986. Effect of the two insect growth regulators and the ovicide isoxathion on the red flour beetle, *Tribolium castaneum* when admixed with wheat flour as egg treatment. *Ann. Agri. Sci. Moshtohor* **24**(3): 1689-1696.
- Elek J A 1994. Methods of controlling eggs and monitoring egg-hatch and immature development of *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *J. Stored Prod. Res.* **30**(4): 261-265.
- Eliopoulos P A , Athanassiou C G and Buchelos C H 2002. Occurrence of Hymenopteran parasitoids of stored product pests in Greece. *IOBC Bulletin* **25**(3): 127-135.
- El-Lakwah F A, Mohamed R A and Khaled O M 1994. Toxic effects of Chinaberry tree *Melia azedarach*, Meliaceae on *Rhyzopertha dominica* F. *Ann. Agric. Sci. (Moshtohor)* **32**(4): 2195-2204.
- El-Sayed F M A 1988. Biological activity of the synthetic insect growth regulator hydroprene against stored Product coleopterans. *Agric. Rev.* **66**: 63-69.
- Elzen G W, Elzen P J and King E G 1998. Laboratory toxicity of insecticide residues to *Orius insidiosus*, *Geocoris punctipes*, *Hippodamia convergens* and *Chrysoperla carnea*. *Southwestern Entomol.* **23**: 335-342.
- Elzen G W, Maldonado S N and Rojas M G 2000. Lethal and sublethal effects of selected insecticides and an insect growth regulator on the boll weevil (Coleoptera: Curculionidae) ectoparasitoid *Catolaccus grandis* (Hymenoptera: Pteromalidae). *J. Econ. Entomol.* **93**: 300–303.

- EPA 1997. *Spinosad Pesticide Fact Sheet No. HJ 501C*. EPA, Office of Pesticides and Toxic Substances.
- Evans D E 1981. Thermal acclimation in several species of stored grain beetles. *Aust. J. Zool.* **29**: 483-492.
- Evans D E 1987a. The survival of immature grain beetles at low temperatures. *J. Stored Prod. Res.* **23**: 79-83.
- Evans D E 1987b. The influence of heating on the mortality of *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *J. Stored Prod. Res.* **23**: 73-77.
- Fam E Z, El-Nahal A K M and Fahmy H S M 1974. Influence of grain moisture on the efficiency of silica aerogel and katelsous used as grain protectants. *Bull. Entomol. Soc. Egypt Econ. Ser.* **8**: 105-114.
- Fang L, Subramanyam Bh and Arthur F H 2002a. Effectiveness of spinosad on four classes of wheat against five stored-product insects. *J. Econ. Entomol.* **95**: 640-650.
- Fang L, Subramanyam Bh and Dolder S 2002b. Fate and efficacy of spinosad residues in farm-stored wheat. *J. Econ. Entomol.* **95**: 1102-1109.
- Fang L and Subramanyam Bh 2003. Activity of spinosad against adults of *Rhyzopertha dominica* (F) (Coleoptera: Bostrychidae) is not affected by wheat temperature and moisture. *J. Kansas Entomol. Soc.* **76**: 529-532.
- Fargo W S, Epperly D G, Cuperus G W, Clary B C and Noyes R 1989. Effects of temperature and duration of trapping on four stored grain insect species. *J. Econ. Entomol.* **82**: 970-973.
- Faroni L R D A. 1992. Biología y Control del Gorgojo de los Granos *Rhyzopertha dominica* F. DSc, Universidad Politecnica de Valencia, Valencia, Spain.

- Faroni L R A and Garcia- Mari F 1992. Influence of temperature on biological parameters of *Rhyzopertha dominica* F. *Boletin de Sanidad Vegetal, Plagas*. **18**(2): 455- 467.
- Faroni L R D A, Guedes R N C and Matioli A L 2000. Potential of *Acarophenax lacunatus* (Prostigmata: Acarophenacidae) as a biological control agent of *Rhyzopertha dominica* (Coleoptera: Bostrichidae). *J. Stored Prod. Res.* **36**: 55-63.
- Faroni L R D A Guedes R N C and Matioli A L 2001. Effect of temperature on development and population growth of *Acarophenax lacunatus* Cross and Krantz (Prostigmata: Acarophenacidae) on *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *Biocon. Sci. Tech.* **11**: 7–14.
- Federal Grain Inspection Service (FGIS) 1997. Wheat, Grain Inspection Handbook, Book II, Grain Grading Procedure, USDA-GIPSA-FIGS, Washington, DC.
- Ferdous J 2006. *Effect of the predator Xylocoris flavipes Reuter and the insect growth regulators triflumuron and diflumuron on Tribolium castaneum* Herbst. Ph D Thesis, Rajshahi University, Rajshahi, Bangladesh. 168 pp.
- Ferdous J, Islam W and Parween S 2009. Biology and mass culture of the warehouse pirate bug *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae). *Bangladesh J. Zool.* **37**(2): 273-280.
- Fields P G 1992. The control of stored-product insects and mites with extreme temperatures. *J. Stored Prod. Res.* **28**: 89-118.
- Fields P G, Van Loon J, Dolinski M G, Harris J L, Burkholder W E 1993. The distribution of *Rhyzopertha dominica* F. in Western Canada. *The Canadian Entomol.* **125**: 317-328.
- Fields P G and Phillips T W 1994. The distribution and PCR-based fingerprints of *Rhyzopertha dominica* F. in Canada. *Proc. 6th Int. Work. Conf. on Stored Prod. Protect.* Canberra, Australia. pp. 517–522.



- Fields P G and Muir W E 1996. Physical Control. In *Integrated Management of Insects in Stored Prod.* Subramanyam Bh and Hagstrum D W (Eds.). Marcel DekkerInc. NewYork. pp. 195-221.
- Fields P and Korunic Z 2000. The effects of grain moisture content and temperature on the efficacy of diatomaceous earths from different geographical locations against stored product beetles. *J. Stored Prod. Res.* **36** (1): 1-13.
- Fields P G and White N D G 2002. Alternatives to methyl-bromide treatments for stored- product and quarantine insects. *Annu. Rev. Entomol.* **47**: 331-359.
- Fisher W S 1950. A Revision of the North America Species of Beetles Belonging to the Family Bostrichidae. Miscellaneous Publication, vol. 698USDA, Washington, DC.
- Flinn P W 1998. Temperature effects on efficacy of *Choetospila elegans* (Hymenoptera: Pteromalidae) to suppress *Rhyzopertha dominica* (Coleoptera: Bostrichidae) in stored wheat. *J. Econ. Entomol.* **91**: 320-323.
- Flinn P W and Hagstrum W D 1990. Simulations comparing the effectiveness of various stored grain management practices used to control *Rhyzopertha dominica*. *Environ. Entomol.* **19**: 725-729.
- Flinn P W, Hagstrum D W and Mc Gaughey W H 1994. Suppression of beetles in stored wheat by augmentative releases of parasitic wasps. *Proc. 6<sup>th</sup> Int. Work. Conf. Stored-Prod. Protect.* 17-23 April 1994, Australia (Highly E, Wright E J, Banks H J and Champ B R eds) **2**: 1103-1105.
- Flinn P W, Hagstrum D W and Mc Gaughey W H 1996. Suppression of beetles in stored wheat by augmentative releases of parasitic wasps. *Environ. Entomol.* **25**: 505-511.

- Flinn P W, Hagstrum D W and Muir W E 1997. Effects of time of aeration, bin size, and latitude on insect populations in stored wheat: a simulation study. *J. Econ. Entomol.* **90**: 646-651.
- Flinn P W and Hagstrum D W 1998. Distribution of *Cryptolestes ferrugineus* (Coleoptera: Cucujidae) in response to temperature gradients in stored wheat. *J. Stored Prod. Res.* **34**: 107-112.
- Flinn P W and Hagstrum D W 2001. Augmentative releases of parasitoid wasps in stored wheat reduces insect fragments in flour. *J. Stored Prod. Res.* **37**: 179-186.
- Flinn P W, Subramanyam Bh and Arthur F H 2004a. Comparison of aeration and spinosad for suppressing insects in stored wheat. *J. Econ. Entomol.* **97**: 1465-1473.
- Flinn P W, Hagstrum D W and Phillips T W 2004b. Stimulation model for *Rhyzopertha dominica* population dynamics in concrete grain bins. *J. Stored Prod. Res.* **40**: 39-45.
- Flinn P W, Kramer K J, Throne J E and Morgan T D 2006. Protection of stored maize from insect pests using a two-component biological control method consisting of a hymenopteran parasitoids, *Theocolax elegans* and transgenic avidin maize powder. *J. Stored Prod. Res.* **42**:218-225.
- Flinn P W, Hagstrum D W, Reed C and Phillips T W 2007a. Stored Grain Advisor Pro: decision support system for insect management in commercial grain elevators. *J. Stored Prod. Res.* **43**: 375-383.
- Flinn P W, Hagstrum D W, Reed C R and Phillips T W 2007b. Stored Grain Advisor Pro: decision support system for insect management in commercial grain elevators. *J. Stored Prod. Res.* **43**: 375-83.
- Flinn P W, Opit G P and Throne J E 2009. Predicting stored grain insect population densities using an electronic probe trap. *J. Econ. Entomol.* **102**(4): 1696 -1704.

- Flinn P W, Hagstrum D W, Reed C and Phillips T W 2010. Insect population dynamics in commercial grain elevators. *J. Stored Prod. Res.* **46**: 43–47.
- Florence V, Dunkel D, Stefan T and Jaronski A 2003. Development of a bioassay system for the predator, *Xylocoris flavipes* (Heteroptera: Anthocoridae) and its use in subchronic toxicity/pathogenicity studies of *Beauveria bassiana* Strain GHA. *J. Econ. Entomol.* **96(4)**: 1045-1053.
- Fontes L S, Arthur V, Wiend T A and Wiend F M 1996. Gamma radiation effects on pupae of *Tribolium castaneum* Herbst. *J. Nuclear Agric. Biol.* **25(3)**: 176-179.
- Forrester N W 1990. Designing, implementing and servicing on insecticide resistance management strategy. *Pestic. Sci.* **28**: 167-180.
- Fox D 1990. Insect Growth Regulators. P J B Publ. Ltd. Richmond, UK pp.102.
- Freeman J A 1980. *Common Insect Pest of Stored Food Products*. 6th edition. British Museum (Natural History). London.
- Froggatt W 1992. Parasitic enemies of the Mediterranean flour moth *Ephestia kuchniella* Zeller. *Agric. Gaz. N. S. W.* **23**: 307-311.
- Fuxa J R 1993. Insect resistance to viruses. In *Parasites and Pathogens of Insects*. (Beekage N E, Thomson S N and Federici B A eds), Pathogens, Academic Press, San Diego **2**: 197-209.
- Gahbiche H 2001. Lutte contre un ravageur des cultures le`gumie`res. *Phytoma* **538**: 34-36.
- Gandhi N and S Pillai 2011. Control of *Rhyzopertha dominica* (Coleoptera: Bostrichidae) by pulverized leaves of *Punica granatum* (Lythraceae) and *Murraya koenigii* (Rutaceae). *Int. J. Agric. Biol.* **13**: 535-540.

- Gao Y, Reitz S R, Wang J and Lei Z 2012. Potential of a Strain of the Entomopathogenic Fungus *Beauveria bassiana* (Hypocreales: Cordycipitaceae) as a Biological Control Agent against Western Flower Thrips, *Frankliniella occidentalis* (Thysanoptera: Thripidae). *Biocontrol Sci. Tech.* **22**: 491-495.
- Gates M W 1995. Population dynamics of lesser grain borer, rusty grain beetle, and *Cephalonomia waterstoni* in commercial elevators. M S Thesis, Oklahoma State University, Stillwater.
- Gay F G and Ratcliffe F N 1941. The importance of *Rhyzopertha dominica* as a pest of wheat under wartime storage conditions. Australia. *J. Council Sci. Indust. Res.* **14**: 173-180.
- Georghiou G P and Mellon 1983. Pesticide resistance in time and space. In *Pest Resistance to pesticide*. (Georghion G P and Saito T, eds). Plenum Press, New York, pp. 1- 46.
- Getchell A I 2006. Efficacy of two spinosad formulations on various commodities against stored-product insects. M S Thesis. Department of Grain Science and Industry, College of Agriculture, Kansas State University, Manhattan, Kansas, 76 pp.
- Getchell A I and Subramanyam Bh 2008. Immediate and delayed mortality of *Rhyzopertha dominica* (Coleoptera: Bostrychidae) and *Sitophilus oryzae* (Coleoptera: Curculionidae) adults exposed to spinosad treated grain. *J. Econ. Entomol.* **101**: 1022-1027.
- Ghelani Y H, Dhedhi K K, Joshi H J, Raghvani K L and Dangaria C J 2009. Effect of insecticidal seed treatment on viability of pearl millet during storage in Karnataka. *J. Agri. Sci.* **3**: 633–634.
- Ghomomu T R 1989. Some observation on the reproduction of adults of the cowpea weevil, *Callosobruchus maculatus* F. resulting from irradiation immature stages. *Parasitica* **45**(4): 99-104.

- Ghomomu T R 1991. The effect of gamma radiation on the reproduction of the cowpea weevil, *Callosobruchus maculatus* F. (Coleoptera: Bruchidae). *Tropicaultura* **9**(3): 111-113.
- Ghosh Amalendu, Chatterjee1 Monilal and Roy Agamananda 2010. Bio-efficacy of spinosad against tomato fruit borer *Helicoverpa armigera* Hub. (Lepidoptera: Noctuidae) and its natural enemies. *J. Horti. Fores.* **2**(5): 108-111.
- Giga D P and Canhou Sr J 1991. Relative toxicity and persistence of pyrethroid deposits on different surfaces for the control of *Prostephanus truncatus* (Horn) and *Sitophilus zeamais* (Motsch.). *J. Stored Prod. Res.* **27**: 153-160.
- Girish G K, Arora K K and Jain S K 1988. Post harvest technology of food grains in India. *Bull. Grain Tech.* **28**(1): 66-68.
- Golebiowska Z 1969. The feeding and fecundity of *Sitophilus granarius* (L.) *Sitophilus oryzae* (L.) and *Rhyzopertha dominica* (F.) in wheat grain. *J. Stored Prod. Res.* **5**: 143-155.
- Golob P 1997. Current status and future perspective for inert dusts for the control of stored products insects. *J. Stored Prod. Res.* **33** (1): 69-79.
- Golob P and Webley D J 1980. The use of plants and minerals as traditional protectants of stored products. *Tropical Products Institute G*, pp. 138.
- Goncalves J R, Faroni L R and Guedes R N 2002. Pyrethroid-*Acarophenax lacunatus* interaction in suppressing the beetle *Rhyzopertha dominica* on stored wheat. *Exp. Applied Acarol* **26**: 231-242.
- Gonçalves J R, Faroni L R D A, Guedes R N C, Oliveira De C R F 2004. Insecticide selectivity to the parasitic mite *Acarophenax lacunatus* Cross and Krantz (Prostigmata: Acarophenacidae) on *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *Neotrop. Entomol.* **33**: 243-248.

- Gonçalves J R, Faroni L R D A, Guedes R N C, De Oliveira C R F 2006. Interaction between *Acarophenax lacunatus* Cross and Krantz (Prostigmata: Acarophenacidae) and *Anisopteromalus calandrae* Howard (Hymenoptera: Pteromalidae) on *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *Neotrop. Entomol.* **35** (6): 823-827.
- Greenberg B 1971. *Flies and Diseases Vol. 1. Ecology, Classification and Biotic Associations*. Princeton University Press, Princeton.
- Greenberg B 1973. *Flies and Diseases, Vol. 2. Biology and Disease Transmission*, Princeton University Press, Princeton.
- Gross G F 1954. A revision of the flower bugs (Heteroptera: Anthocoridae) of the Australian and adjacent Pacific regions. Part 1. *Records. S. Austral. Mus.* **11**: 149-164.
- Grosscurt A C 1978. Diflubenzuron: some aspects of its ovicidal and larvicidal mode of action and an evaluation of its practical possibilities. *Pestic. Sci.* **9**: 373-386.
- Guedes R N C, Dover B A and Kambhampati S 1996. Resistance to chlorpyrifos-methyl, pirimiphos-methyl, and malathion in Brazilian and U.S. populations of *Rhyzopertha dominica* (Coleoptera: Bostrichidae). *J. Econ. Entomol.* **89**: 27-32.
- Guedes R N C, Kambhampati S and Dover B A 1997. Organophosphate resistance and its biochemical mechanisms in Brazilian and U S populations of the lesser grain borer, *Rhyzopertha dominica*. *Resistant Pest Management Newsletter* **9**: 24-25.
- Haghtalab N, Shayesteh N and Aramideh S 2009. Insecticidal efficacy of castor and hazelnut oils in stored cowpea against *Callosobruchus maculatus* F. (Coleoptera: Bruchidae). *J. Biol. Sci.* **9**: 175-179.

- Hagstrum D W 1989. Infestation of *Cryptolestes ferrugineus* of newly-harvested wheat stored on three Kansas farms. *J. Econ. Entomol.* **82**: 655-659.
- Hagstrum D W 2001. Immigration of insects into bins storing newly harvested wheat on 12 Kansas farms. *J. Stored Prod. Res.* **37**: 221–229.
- Hagstrum D W and Throne J E 1989. Predictability of stored-wheat insect population trends from life history traits. *Environ. Entomol.* **18**: 660–664.
- Hagstrum D W and Flinn P W 1994. Survival of *Rhyzopertha dominica* (Coleoptera: Bostrichidae) in stored wheat under fall and winter temperature conditions. *Environ. Entomol.* **23**: 390-395.
- Hagstrum D W, Flinn P W and Subramanyam Bh 1998. Predicting insect density from probe trap catch in farm stored wheat. *J. Stored Prod. Res.* **34**: 251-262.
- Hagstrum D W, Reed C and Kenkel P 1999. Management of stored wheat pests in the USA. *Int. Pest Manage. Rev.* **4**: 127–142.
- Hagstrum D W, Flinn P W, Reed C R and Phillips T W 2008. Stored-grain insect areawide pest management. In Koul O, Cuperus G W and Elliott N (eds.), *Areawide Pest Management: Theory and Implementation*. CABI, Oxfordshire, UK, pp. 226-243.
- Hagstrum D W, Flinn P W, Reed C R and Phillips T W 2010. Ecology and IPM of insects at grain and elevators and flat storages. *Biopestic. Int.* **6**(1): 1-20.
- Haines C P 1984. Biological methods for integrated control of insects and mites in tropical stored products. The use of predators and parasites. *Trop. Stored Prod. Inf.* **48**: 17-24.
- Haines C P 1991. Insects and arachnids of tropical stored products: Their biology and identification (A training manual). Natural Resources Institute, Chatham, 246 pp.

- Hajjar N P and Casida J E 1979. Structure activity relationships of benzyolphenyl ureas as toxicants and chitin synthesis inhibitors in *Oncopeltus fasciatus*. *Pestic. Biochem. Physiol.* **11**: 33-35.
- Halstead D G H 1963. External sex differences in stored products Coleoptera. *Bull. Entomol. Res.* **54**: 119-134
- Halstead D G H 1993. Keys for the identification beetles associated with stored products-II Laemophloeidae Passandridae and Silvanidae. *J. Stored Prod. Res.* **29 (2)**: 99-197.
- Hansen L S 1998. Prospects for developing strategies for biological control of the Mediterranean flour moth *Ephestia kuehniella* in flour mills. *Integrated Protection of Stored Products (IOBC Bulletin)* **21(3)**: 33-37.
- Hasan M 1995. Comparative sensitivity of *Tribolium* spp. to gamma irradiation throughout ontogeny. Ph D Thesis, Department of Agriculture and Environmental Sciences, University of New Castle Upon Tyne, UK, 262pp.
- Hasanuzzoha S M 2004. *Environmental friendly use of pesticides in field crop protection in Bangladesh and pre/post safety measures for the farmers*. Ph D thesis, University of Rajshahi, Bangladesh, 366pp.
- Hasen L S, Skovgard H and Hell K 2004. Life table study of *Sitotroga cereal* La (Lepidoptera: Gelichiidae) a strain from west Africa. *J. Econ. Entomol.* **97(4)**: 1484-1490.
- Hashem M Y 1989. *Prostephanus truncatus* (Hon) and Des Getreidekapuziners *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *Mitt. Dtsch. Ges. Allg. Angew. Ent.* **7**: 205-209.
- Helbig J 1999. Efficacy of *Xylocoris flavipes* Reuter (Het : Anthocoridae) to suppress *Prostephanus truncatus* Horn (Col: Bostrichidae) in traditional maize stores in Southern Togo . *J. App. Entomol.* **123(8)**: 503-508.



- Heller J J, Mattioda H, Klein E and Sagenmuller A 1992. Field evaluation of RH 5992 of lepidopterous pests in Europe. *Proc. Brighton Crop. Prot. Conf. Pests Dis.* pp. 59-65.
- Henry T J 1988. Family Anthocoridae Fieber, 1837: the minute pirate bugs, In Henry T J and Froeschner R C (eds.), *Catalogue of the heteroptera or true bugs of Canada and the continental United States*. Brill E J, New York, pp.12-28.
- Herrera A M, Dalhsten D D, Tomic-Carruthers N and Carruthers R I 2005. Estimating temperature-dependent rates of *Diorhabda elongate* (Coleoptera: Chrysomalidae) a biological agent of Saltceder (*Tamarix spp.*). *Environ. Entomol.* **34**(4): 775-784.
- Herron G A 1990. Resistance to grain protectants and phosphine in coleopterous pests of grain stored on farms in New South Wales. *Aust. J. Entomol.* **29**: 183-189.
- Hertlein M B, Thompson G D, Subramanyam Bh and Athanassiou C G 2011. Spinosad a new natural product for stored grain protection. *J. Stored Prod. Res.* **47**(3): 131-146.
- Highland H A. 1991. Protecting packages against insects. In *Ecology and Management of Food- Industry Pests*, Gorham, J.R. (Ed.). AOAC, Arlington, VA. pp. 345-350.
- Hill E G 1978. *Controlling Insect Pests in Flour Mills*. MAFF London, H M Stationary Office. 137pp.
- Hill T A and Foster R E 2000. Effect of insecticides on the diamondback moth (Lepidoptera: Plutellidae) and its parasitoid *Diadegma insulare* (Hymenoptera: Ichneumonidae). *J. Econ. Entomol.* **93**: 763-768.
- Hoffman W A 1933. *Rhizopertha dominica* as a library pest. *J. Econ. Entomol.* **26**: 293-294.

- Hokkamen H M T, Lynch J M and Robinson J 1995. Preface: overview of benefits and risk of biological control introductions. In *Biological Control: Benefits and Risks*. (Hokkamen H M T and Lynch J M eds.). pp17-22, Cambridge University Press, 746pp.
- Hole D, Bell C H, Mills K A and Goodship G 1976. The toxicity of phosphine to all developmental stages of thirteen species of stored product beetles. *J. Stored Prod. Res.* **1**: 235-244.
- Hossain M, Verner P H and Rezaur R 1986. Taxonomic descriptions of the mature larvae of six species of *Cryptolestes* (Coleoptera: Cucujidae). *Bangladesh J. Zool.* **14** : 139- 148.
- Howe R W 1956. The biology of the two common storage species of *Oryzaephilus* (Coleoptera: Cucujidae). *Ann. Appl. Biol.* **44**: 341-355.
- Howe R W 1950. The development of *Rhyzopertha dominica* (F.) (Coleoptera: Bostrichidae) under constant temperature. *Entomologist's Monthly Magazine* **86**: 1-5.
- Howe R W 1953. The rapid determination of the intrinsic rate of increases of an insect population. *Ann. Appl. Biol.* **40**: 134-151.
- Howe R W 1965a. A summary of estimates of optimal and minimal conditions for population increase of some stored products insects. *J. Stored Prod. Res.* **1**: 177-184.
- Howe R W 1965b. Losses caused by insects and mites in stored foods and feeding stuffs. *Nutrition Abstracts and Reviews* **35**: 285-293.
- Huang F and Subramanyam Bh 2003. Responses of *Corcyra cephalonica* (Stainton) to primiphos-methyl, spinosad, and combinations of pirimiphos-methyl and synergized pyrethrins. *Pest Manage. Sci.* **60**: 191-198.

- Huang F, Subramanyam Bh and Toews M 2004. Susceptibility of laboratory and field strains of four stored product pests to Spinosad. *J. Econ. Entomol.* **97**: 2154-2159.
- Huang F and Subramanyam Bh 2007. Effectiveness of spinosad against seven major stored-grain insects on corn. *Insect Sci.* **14**: 225–230.
- Huang F, Subramanyam Bh and Hou X 2007. Efficacy of spinosad against eight stored product insect species on hard winter wheat. *Biopest. Int.* **3**: 117-125.
- Huang F, Subramanyam Bh and Roesli R 2009. Comparative susceptibility of *Liposcelis bostrychophila* Badonnel and *Liposcelis decolor* Pearman (Psocoptera: Liposcelididae) to spinosad on wheat. *Biopest. Int.* **5**: 106-113.
- Huffaker C B and Messenger P S 1976. *Theory of practical of biological control*. Academic, New York.
- Hulasare R B, White N D G and Jayas D S 2005. Effect of suboptimal temperatures and sublethal CO<sub>2</sub> levels on multiplication of *Tribolium castaneum* (Coleoptera: Tenebrionidae), alone or competing with *Cryptolestes ferrugineus* (Coleoptera: Cucujidae). *J. Stored Prod. Res.* **41**: 187-197.
- Hussain T and Imura O 1989. Effect of gamma radiation on the developmental stages of pulse beetle *Callosobruchus chinensis* L. (Coleoptera: Bruchidae). *Appl. Ent. Zool.* **24**(3): 273-280.
- Hussain R A, Muhammad A S, Mushtaq and Ahmed S 2005. Toxicity of some insecticides with novel modes of action against Malathion-Resistant and Organophosphate Susceptible strains of *Tribolium castaneum* larvae. *Int. J. Agric. Biol.* **7**: 768-772.
- Hussain R, Ashfaq M and Saleem M A 2009. Biochemical abnormalities produced by spinosad in *Tribolium castaneum* adult beetles. *Int. J. Agri. Biol.* **11**: 241-244.

- Hyde M B, Baker A A, Ross A C and Lopez C O 1973. Airtight grain storage. F A O Agricultural Services Bulletin No. 17.
- Imamura T, Murata M and Miyanoshita A 2008. Review: *Biological aspects and predatory abilities of hemipterans attacking stored-product insects*. JARQ **42**(1): 1-6.
- Ishijima C, Imamura T, Visarathanonth P and Miyanoshita A 2005. Suppression effects of predatory bugs on the stored-product insect *Tribolium confusum* (Coleoptera: Tenebrionidae). *Jpn. J. Appl. Entomol. Zool.* **49**: 143-145.
- Islam W 1991. *Biology of some hymenopteran parasitoids and evaluation of their potential as a control agent against Callosobruchus chinensis L.* Ph D thesis University of Dhaka, Bangladesh pp. 201.
- Islam W 1993. The biology of *Anisopteromalus calandrae* How ectoparasitoid on *Callosobruchus chinensis L.* *Bangladesh J. Zool.* **21**(1): 123-132.
- Islam W 1995. Biology of *Dinarmus basalis* Rondani (Hymenoptera: Pteromalidae) a larval- pupal parasitoid of *Callosobruchus chinensis L.* *Ann. Entomol.* **13**: 51-56.
- Islam W 1997. Host-size selection and preference for oviposition of the parasitoid *Dinarmus Basalis* Rondani (Hymenoptera: Pteromalidae) on *Callosobruchus chinensis L.* *Entomon.* **13**: 95-100.
- Islam W, Ahmed K N and Malek M A 1985. Hymenopterous parasites on insect pest of two stored pulses. *Bangladesh J. Zool.* **13**: 81-85.
- Islam N, Bhuiyah M I M, Begum A and Karim M A 1989. Comparative efficacy of different material against *Sitophilus oryzae L.* maize seeds in storage. *Bangladesh J. Zool.* **17**: 175-178.

- Islam W and Kabir S M H 1992. Mass rearing and production of *Dinarmus Basalis* Rondani (Hymenoptera: Pteromalidae). A larval- pupal ectoparasitoid of the pulse beetle *Callosobruchus chinensis* L. *Pakistan J. Zool.* **24**(2): 172-174.
- Islam W and Nargis A 1993. Influence of host's body fluid on the longevity and fecundity of the parasitoid *Anisopteromalus calandrae* Howard (Hymenoptera: pteromalidae). *Bangladesh J. Sci. Ind. Res.* **28**: 94-99.
- Islam W and Nargis A 1994. Influence of host instar/stage on the development of the parasitoid *Anisopteromalus calandrae* Howard (Hymenoptera: pteromalidae). *Bangladesh J. Sci. Ind. Res.* **29**: 123-131.
- Islam W and Kabir S M H 1995. Biological control potential of *Dinarmus basalis* Rondani (Hymenoptera: Pteromalidae), a larval- pupal ectoparasitoid of the pulse beetle *Callosobruchus chinensis* L. *Crop Protec.* **14**: 439-443.
- Islam W and Khan A R 2000. Bruchid Research in Bangladesh. *Pakistan J. Biol. Sci.* **3**: 10-19.
- Ivie M A 2002b. Keys to families of beetles in America north of Mexico, in R H Arnett R H, Thomas M C, Skelley P E and Frank J H (Eds.), *American Beetles, Polyphaga: Scarabaeoidea through Curculionoidea, vol. 2, CRC Press, Boca Raton* **2**: 816-835.
- Ivie M A 2002a. Family 69. Bostrichidae, in Arnett R H, Thomas M C, Skelley P E, and Frank J F (Eds.), *American Beetles, Polyphaga: Scarabaeoidea through Curculionoidea, CRC Press, Boca Raton* **2**: 233-244.
- Jachetta J J 2001. *Petition for the Inclusion of Spinosad on the national organic standards board list of approved organic substances.* Indianapolis: Dow Agro Sciences

- Jay E, Davis R and Brown S 1968. Studies on the predatious habit of *Xylocoris flavipes* Reuter (Hemiptera: anthocoridae). *J. Georgia. Entomol. Soc.* **3**: 126-130.
- Jembre B, Obeng-Ofori D, Hassanali A and Nyamasyo G N N 1995. Products derived from the leaves of *Ocimum kilimandscharicum* (Labiatae) as postharvest grain protectants against the infestation of three major stored product pests. *Bull. Ent. Res.* **85**: 361-367.
- Jha L K 1987. *Applied agricultural entomology*. Publisher: New central book agency. India. pp 258.
- Jia F, Toews M D, Campbell J F, Ramaswamy S B 2008. Survival and reproduction of lesser grain borer *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) on flora associated with native habitats in Kansas *J. Stored Prod. Res.* **44**: 366-372.
- Johnson D E, Brookhart G L, Kramer K J, Barnett B D and McGaughey W H 1990. Resistance to *Bacillus thuringiensis* by the Indian meal moth *Plodia interpunctella* comparison of midgut proteinases from susceptible and resistant larvae. *J. Inverte. Path.* **55**: 235-244.
- Jolly DA, Schutz H G, Diaz-Knauf K V and Johal J 1989. Organic Foods: consumer attitudes and use. *Food Technol* **43**: 60-66.
- Kabak B, Dobson A D W and Var I 2006. Strategies to prevent mycotoxin contamination of food and animal feed: *A review. Crit. Rev. Food Sci. Nutr.* **46**: 593-619.
- Kapil R P and Chowdhury J P 1973. Recover of nine new Hymenopterous parasites for Khapra beetle, *Trogoderma granarium* Everts (Coleoptera: Dermestidae). *Indian J. Ent.* **35**: 353-355.

- Kavallieratos N G, Athanassiou C G, Pashalidou F G, Andris N S and Tomanovic Z 2005. Influence of grain type on the insecticidal efficacy of two diatomaceous earth formulations against *Rhyzopertha dominica* F. (Coleoptera: Bostrychidae). *Pest Manage. Sci.* **61**: 660-666.
- Kavallieratos N G, Athanassiou C G, Vayias B J, Kotzamanidis S and Synodis S D 2010. Efficacy and adherence ratio of diatomaceous earth and spinosad in three wheat varieties against three stored-product insect pests. *J. Stored Prod. Res.* **46**: 73-80.
- Kavallieratos N G, Athanassiou C G, Arthur F H and Throne J E 2012. Lesser grain borer, *Rhyzopertha dominica* select rough rice kernels with cracked hulls for reproduction. *J. Insect Science* **12**: 38.
- Keever D W 1983. Distribution patterns of lesser grain borer (Coleoptera: Bostrichidae) in towers of wheat, and effects of the presence of the granary weevil (Coleoptera: Curculionidae). *J. Econ. Entomol.* **76**: 492-495.
- Keever D W, Mullen J W, Press J W and Arbogast R T 1986. Augmentation of natural enemies for suppression of two major insect pests in stored farmers stock peanuts. *Environ. Entomol.* **15**: 767-770.
- Keita S M, Vincent C, Schmit J P, Amason J T and Belanger A 2001. Effect of essential oil of *Ocimum basilium* L and *O. gratissimum* L applied as insecticidal fumigant and powder to control *Callosobruchus maculatus* Fab. (Coleoptera : Bruchidae). *J. Stored Prod. Res.* **37**: 339-349.
- Kendall H W and Pimentel D 1994. Constraints on the expansion of the global food supply. *Ambio.* **23**: 198-205.
- Kenis M and Branco M 2010. Chapter 5: Impact of alien terrestrial arthropods in Europe. In: Roques A *et al.* (Eds) Alien terrestrial arthropods of Europe. *BioRisk*, **4**(1): 51-71.

- Kenkel P, Criswell J T, Cuperus G, Noyes R T, Anderson K, Fargo W S, Shelton K, Morrison W P and Adams B 1993. Current management practices and impact of pesticide loss in the hard red wheat post-harvest system. Oklahoma Cooperative Extension Service, E-930, Oklahoma State University, Stillwater, OK, USA
- Kerrich G J 1960. The state of our knowledge of the systematics of the Hymenoptera Parasitica. *Trans. Soc. Brit. Ent.* **14**: 1-18.
- Khan A R 1981. *The combined action of organophosphorous insecticides and microsporidians on Tribolium castaneum*. Unpubl. Ph D Thesis, University of Newcastle upon Tyne, 163pp.
- Khan A R and Mannan A 1991. Stored-Products Entomology in the Tropics. *Agric. Zool. Rev.* **4**: 67-95.
- Khan A R and Selman B J 1981. Some techniques for minimizing the difficulties in egg counting in *Tribolium castaneum* (Herbst). *Entomol. Record J. Variata* **3**: 36-37.
- Khan A R and Selman B J 1996. Biological control of vegetable pests. *Agric. Zool. Rev.* **7**: 267-302.
- Khan A R, Saha B N and Islam W 2004. Effect of temperature on the pulse beetle *Callosobruchus chinensis* L. (Coleoptera: Bruchidae). *Bangladesh J. Zool.* **32**(1): 77-80.
- Khashaveh A, Safaralizade M H and Ghosta Y 2008. Pathogenicity of three Iranian isolates of the fungus, *Metarhizium anisopliae* (Metsch.) Sorokin (Deuteromycotina: Hyphomycetes) against granary weevil, *Sitophilus granarius* L. (Coleoptera: Curculionidae). *J. Biol. Sci.* **8**: 804-808.
- Khashaveh A, Ziaee M, Safaralizadeh M H and Lorestani F A 2009. Control of *Tribolium castaneum* Herbst (Coleoptera: Tenebrionidae) with spinosad dust formulation in different oilseeds. *Turkish J. Agriculture and Forestry.* **33**: 203-209.



- Khater F A 2012. Prospects of botanical biopesticides in insect pest management. *J. Appl. Pharmaceutical Sci.* **2**(9): 244-259.
- Khattak S U K and Jilani G 1984. Gamma radiation sensitivity of eggs of various ages of the red flour beetle *Tribolium castaneum* Herbst (Coleoptera: Tenebrionidae). *Pakistan. J. Zool.* **16**(1):21-24.
- Khorramshahi A and Burkholder W E 1981. Behavior of the lesser grain borer *Rhyzopertha dominica* (Coleoptera: Bostrichidae) male produced aggregation pheromone attracts both sexes. *J. Chem. Eco.* **7**: 33-38.
- Kirkpatrick R L and Cagle 1978. Controlling insects in bulk wheat by infrared radiation. *J. Kansas Entomol. Soc.* **51**:386-393.
- Kirst H A, Michel K H, Mynderse J S, Chao E H, Yak R C, Nakatsukasa W M, Boeck L D, Occlowitz J, Paschel J W, Deeter J B, Thompson G D 1992. Discovery, isolation and structure elucidation of a family of structurally unique fermentation-derived tetracyclic macrolides. In Baker D R, Fenyes J G, Steffens J J (eds.), *Synthesis and Chemistry of Agrochemicals*, American Chemical Society, Washington DC, **3**: 214-225.
- Kitching RG 1977. The resources and population dynamics of insects. *Aust. J. Ecol.* **2**: 31-42.
- Koolman J 1989. *Ecdyson from chemistry to mode of action*. Georgia Thieme Verlag, Stuttgart, Germany.
- Korunic Z, Cenkowski S and Fields P G 1998. Grain bulk density as affected by diatomaceous earth and application method. *Postharvest Biology and Technology* **13**: 81-89.
- Kostyukovsky M, Chen B, Atsmi S and Shaaya E 2000. Biological activity of two juvenoids and two ecdysteroids against three stored product insects. *Insect Biochem. Mol. Biol.* **30**: 891-897.

- Kovendan K, Murugan K, Kumar A N, Vincent S and Hwang J S 2012. Bioefficacy of larvicidal and pupicidal properties of *Carica papaya* (Caricaceae) leaf extract and bacterial insecticide, spinosad, against chikungunya vector, *Aedes aegypti* (Diptera: Culicidae). *Parasitol Res.* **110**: 669-678.
- Kowalska J 2008. Laboratory studies of the activity of Spinosad against *Leptinotarsa decemlineata* Say depending on different temperature. Institute of plant protection, W Wegorka 20 Str. Poznan, Poland.
- Kraszpulski P and Davis R 1988. Interactions of a parasite, *Bracon hebetor* (Hymenoptera: Braconidae) and a predator, *Xylocoris flavipes* (Hemiptera: Anthocoridae), with populations of *Tribolium castaneum* and *Plodia interpunctella*. *The American Midland Naturalist* **119**(1): 71-76.
- Krishnamurthy K 1975. Post-harvest losses in food grains. *Bull. Grain Tech.* **13**: 33-49.
- Kucerova Z and Stejskal V 2008. Differences in egg morphology of the stored grain pests *Rhyzopertha dominica* and *Prostephanus truncatus* (Coleoptera: Bostrichidae). *J. Stored Prod. Res.* **44**: 103–105.
- Kunkel B A, Held D W and Potter D A 2001. Lethal and sublethal effects of bendiocarb, halofenozide and imidacloprid on *Harpalus pennsylvanicus* (Coleoptera: Carabidae) following different modes of exposure in turfgrass. *J. Econ. Entomol.* **94**: 60 - 67.
- Laliberte R 1995. How safe is your child's food? *Parent.* **70**: 30-32.
- Lapp H M, Madrid E J and Smith L B 1986. A Continuous Thermal Treatment to Eradicate Insects from Stored Wheat. American Society of Agricultural Engineers, USA.
- Lecato G L 1974. Increase in populations of *Cryptolestes pusillus* and *C. turcicus* on diets of natural products. *The Florida Entomologists* **57**(3): 309-312.

- Lecato G L 1975. Habitat influencing predation by *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae). *American Midland Naturalist* **93**(2): 510-512.
- Lecato G L 1976. Predation by *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae): influence of stage, species and density of prey and of starvation and density of predator. *Entomophaga* **21**(2): 217-221.
- Lecato G L and Davis R 1973. Preference of the predator *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae) for species and instars of stored product insects. *Florida Entomol.* **56**(1): 57-59.
- LeCato G L and Flaherty B R 1974. Description of eggs of selected species of stored-product insects (Coleoptera and Lepidoptera). *J. Kansas Entomol. Soci.* **47**: 308-317.
- Lecato G L and Collins J M 1976. *Xylocoris flavipes* maximum kill of *Tribolium castaneum* and minimum kill required for survival of the predator. *Environ. Entomol.* **5**:1059-1061.
- Lecato G L, Collins J M and Arbogast R T 1977. Reduction of residual populations of stored product insects of *Xylocoris flavipes* (Hemiptera: Anthocoridae). *J. Kansas Entomol. Soc.* **50**: 84-88.
- Lecato G L and Arbogast R T 1979. Functional response of *Xylocoris flavipes* to Angoumois grain moth and influence of predation on regulation of laboratory populations. *J. Econ. Entomol.* **72**(6): 847-849.
- Leckie B M, Ownley B H, Pereira R M, Klingeman W E, Jones C J and Gwinn K D 2008. Mycelia and Spent Fermentation Broth of *Beauveria bassiana* Incorporated Into Synthetic Diets Affect Mortality, Growth and Development of Larval *Helicoverpa zea* (Lepidoptera: Noctuidae). *Biocontrol Sci. and Tech.* **18**: 697-710.
- Leconte J L 1862. *Classification of the Coleoptera of North America*. Smithsonian Miscellaneous Collection **3**: 207-208.

- Lefkovitch L P 1968. Interaction between four species of beetles in wheat and wheat feed. *J. Stored Prod. Res.* **4**:1-8.
- Legaspi J C and Legaspi J C B 2005. Life table analysis for *Podisus maculiventris* Immatures and female adults under four constant temperatures. *Environ. Entomol.* **34(5)**: 990-998.
- Leong E C W and Ho S H 1993. Research on *L. bostrychophila* Badonnel and *L. entomophila* Enderlein (Psocoptera:Leposelidae). In Naewbanij J O, Manilay A A (Eds), *Proc. 14th ASEAN Seminar on grain postharvest Techn.* Manila, The Philippines, pp.317-327.
- Le Patourel G N J 1986. The effect of grain moisture content on the toxicity of a sorptive silica dust to four species of grain beetles. *J. Stored Prod. Res.* **22**: 63-69.
- Lesne P 1896. Revision des coléoptères de la famille des Bostrychides. Extrait des *Annales Sociéteé Entomologique de France* **65**: 332-333.
- Lessard F E 1987. Control of storage insects by physical means and modified environmental conditions feasibility and applications. In *Stored products pest control* (Lawson T J eds.), British Crop Protection Council Monograph. *The British Crop Protection Council*, Thornton Heath. **37**: 209-218.
- Levinson H Z and Levinson A R 1989. Food storage and storage protection in ancient Egypt. *Boletinde Sanidad Vegetal* **17**: 475-482.
- Levitan L, Merwin I and Kovach J 1995. Assessing the relative environmental impacts of agricultural pesticides: the quest for a holistic method. *Agri. Ecosyst. Environ.* **55**: 153-168.
- Lippert G E and Hagstrum D W 1987. Detection or estimation of insect populations in bulk-stored wheat with probe traps. *J. Econ. Entomol.* **80**: 601-604.

- Liu H, Cupp E W, Guo A and Liu N 2004a. Insecticide resistance in Alabama and Florida mosquito strains of *Aedes albopictus*. *J. Med Entomol.* **41**: 946-952.
- Liu H, Cupp E W, Micher K M, Guo A and Liu N 2004b. Insecticide resistance and cross-resistance in Alabama and Florida strains of *Culex quinquefasciatus*. *J. Med Entomol.* **41**: 408-413.
- Liu Z L and Ho S H 1999. Bioactivity of the essential oil extracted from *Evodia rutaecarpa* Hook f. et Thomas against the grain storage insects *Sitophilus zeamais* Motsch. and *Tribolium castaneum* Herbst. *J. Stored Prod. Res.* **35**(4): 317-328.
- Longley M and Jepson P C 1997. Effects of life stage, substrate, and crop position on the exposure and susceptibility of *Aphidius rhopalosiphii* Destefani-Perez (Hymenoptera: Braconidae) to deltamethrin. *Environ. Toxicol. and Chemist.* **16**:1034-1041.
- Longstaff B C and Evans D E 1983. The demography of the rice weevil, *Sitophilus oryzae* L. (Coleoptera: Curculionidae), submodels of age-specific survivorship and fecundity. *Bull. Entomol. Res.* **73**: 333-344.
- Longstaff B B 1999. An experimental and modeling study of the demographic performance of *Rhyzopertha dominica* (F.) I. development rate. *J. Stored Prod. Res.* **35**: 89-98.
- Longstaff B C and Starick N T 1989. The influence of media on the survival of pupae of *Rhyzopertha dominica* (Coleoptera: Bostrychidae) after sexing. *J. Stored Prod. Res.* **25**: 93-95.
- Lorini I and Galley D J 1996. Changes in resistance status of *Rhyzopertha dominica* F. (Coleoptera: Bostrychidae) a pest of stored grain in Brazil with and without deltamethrin selection. *Resistant Pest Management Newsletter* **8**: 12-14.

- Lorini I and Galley D J 1999. Deltamethrin resistance in *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae) a pest of stored grain in Brazil. *J. Stored Prod. Res.* **35**: 37- 45.
- Lorini I and Galley D J 2000. Estimation of realized heritability of resistance to deltamethrin insecticide in selected strains of *Rhyzopertha dominica* F. (Coleoptera: Bostrychidae). *J. Stored Prod. Res.* **36**: 119-124.
- Lorini I and Collins P J 2006. Resistance to phosphine in *Rhyzopertha dominica* (F.) (Coleoptera: Bostrychidae) collected from wheat storages in Brazil. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolini OF de, Sartori M R, Elias M C, Guedes R N C, Fonseca R G da and Scussel V M (eds.), *Proc. 9th Int. Work. Conf. on Stored prod. Protect*, 15 to 18 October 2006, Campinas, Sao Paulo, Brazil. pp. 319-323.
- Lorini H, Beckel and Schneider S 2006a. Efficacy of spinosad and IGR Plus to control the pests *Rhyzopertha dominica* and *Sitophilus zeamais* on stored wheat grain. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolinide O F L, Sartori M R, Elias M C, Guedes R N C, Fonseca R G da and Scussel V M (eds.) *Proc. 9th Int. Work. Conf. for Stored Prod. Protect.* 15–18 October 2006, ABRAPOS, Campinas, Sao Paulo, Brazil, pp. 269-273.
- Loschiavo S R and Atkinson J M 1967. A trap for the detection and recovery of insects in stored grain. *Can. Entomol.* **99**: 1160-1163.
- Loschiavo S R and Smith L B 1986. Population fluctuations of the rusty grain beetle, *Cryptolestes ferrugineus* (Coleoptera: Cucujidae), monitored with insect traps in wheat stored in a steel granary. *Can. Entomol.* **118**: 641- 647.
- Ludwig S W and Oetting R D 2001. Susceptibility of Natural Enemies to Infection by *Beauveria bassiana* and Impact of Insecticides on *Ipheseius degenerans* (Acari: Phytoseiidae). *J. Agri. Urban Entomol.* **18**: 169-178.

- Magan N and Evans P 2000. Volatiles as an indicator of fungal activity and differentiation between species and the potential use of electronic nose technology for early detection of grain spoilage. *J. Stored Prod. Res.* **36**: 319-340.
- Mahal N 2002. *Biology and control of Rhyzopertha dominica* Fabricius (Coleoptera: Bostrichidae). Ph D Thesis, University of Rajshahi, Bangladesh pp. 329.
- Mahal N, Islam W, Parween S and Mondal KAMSH 2005. Effect of *Anisopteromalus calandrae* (Hymenoptera: Pteromalidae) in controlling residual populations of *Rhyzopertha dominica* (Coleoptera: Bostrichidae) in wheat stores. *Int.J. Trop. Insect Sci.* **25**: 245-250.
- Mahal N, Islam W, Mondal K and Parveen S 2006. Deformities produced by some plant powders in *Rhyzopertha dominica* F. Coleoptera (Bostrichidae). *J. Biol. Sci.* **14**: 69-72.
- Mahdi S H A and Khalequzzaman M 2006. Toxicity studies of some inert dusts with the cowpea beetle, *Callosobruchus maculatus* (F.) (Coleoptera: Bruchidae). *J. boil-sci* **6**: 402- 407.
- Mahdneshin Z, Safaralizadah M H and Ghosta Y 2009. Study on the efficacy of Iranian isolates of *Beauveria bassiana* (balsamo) vuillemin and *Metarhizium anisopliae* (metsch.) sorokin against *Rhyzopertha dominica* F. (Coleoptera: Bostrichidae). *J. biol-sci* **9**: 170-174.
- Mahroof R and Phillips T W 2007. Stable isotopes as markers to investigate host use by *Rhyzopertha dominica*. *Entomologia Experimentalis et Applicata* **125**: 205-213.
- Mahroof R M, Edde P A, Robertson B, Puckette T and Phillips T W 2010. Dispersal of *Rhyzopertha dominica* F. in different habitats. *Environ. Entomol.* **39**: 930-938.

- Maia M F and Moore S J 2012. Plant-based insect repellents: a review of their efficacy, development and testing. *Malaria Journal* **10** (1): 1-15.
- Maier D E, Ileleji K E and Szabela D 2006. Efficacy of spinosad for insect management in farm stored maize. Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P dos, Biagi J D, Celaro J C, Faroni L R D A, Bortolinide O F L, Sartori M R, Elias M C, Guedes R N C, Fonseca R G da and V M Scussel V M (eds.), *Proc. 9th Int. Work. Conf. for Stored Prod. Protect.* 15–18 October 2006, ABRAPOS, Campinas, Sao Paulo, Brazil. pp. 789-796.
- Maina Y T and Lale N E S 2004. Integrated Management of *Callosobruchus maculatus* (F.) infesting cowpea seeds in storage using varietal resistance application of neem (*Azadirachta indica* A. Juss) seed oil and solar heat. *Int. J. Agric. Biol.* **6**: 440- 446.
- Mallis A 1982. *Handbook of Pest Control*. Franzak and Foster, Cleveland.
- Mansour S A and Mossa A H 2005. Comparative effects of some insecticides as technical and formulated on male albino rats. *J. Egypt Soc. Toxicol.* **32**: 41-54.
- Marina C F, Bond J G, Munoz J, Valle J, Chirino N and Williams T 2012. Spinosad: a biorational mosquito larvicide for use in car tires in southern Mexico. *Parasites and Vectors* **5**: 95.
- Markham R H, Borgemeister C and Meikle W G 1994. Can biological control resolve the larger grain borer crisis. *Proc. 6th Int. Work. Conf. on Stored Prod. Protect.* April 17-23, Canberra, Australia. pp.1087-1097.
- Marske K A and Ivie M A 2003. Beetle fauna of the United State and Canada. *The Coleopterist Bulletin* **57**: 495-503.
- Mason L J and Strait C A 1998. Stored product integrated pest management with extreme temperatures. Hallman G J and Denlinger D L (eds.), Perseus Publishing, Cambridge, MA, USA, pp.141-177.



- Mason P G and Hubner J T 2001. *Biological control programmes in Canada, 1981–2000*. CABI Publishing, Wallingford, UK, pp. 583.
- Mason P G, Erlandson M A, Elliott R H and Harris B J 2002. Potential impact of spinosad on parasitoids of *Mamestra configurata* (Lepidoptera: Noctuidae). *Can. Entomol.* **134**: 59-68.
- Mathew G 1987. Insect borers of commercially important stored timber in state of Kerala, India. *J. Stored Prod. Res.* **23**: 185-190.
- Mazid M A, Mondal KAMSH, Islam W and Parween S 2006. Ovicidal and adulticidal effects of triflumuron against *Tribolium confusum* (Duval). *Bangladesh J. Zool.* **34**(1): 105-110.
- McEwen F L 1978. Food Production- the challenge for pesticides. *Bio-Science.* **28**: 773-777.
- Mertz F P and Yao R C 1990. *Saccharopolyspora spinosa* isolated from soil collected in a sugar mill rum still. *Int. J. Syst. Bacteriol.* **40**: 34-39.
- Metcalf C L and Flint W P 1962. Destructive and useful insects, their habits and control, 4th edition, McGraw-Hill, San Francisco, pp.1087.
- Metcalf R L 1980. Changing role of insecticides in crop protection. *Ann. Rev. Ent.* **25**: 219-258.
- Metcalf R L and Luckman W H 1975. Introduction to insect pest management. John Willey and sons. New York, Toronto, London, Sydney. pp. 235-273.
- Mian L S and Mulla M S 1982a. Biological activity of IGRs against four stored product coleopterans. *J. Econ. Ent.* **75**: 80-85.
- Mian L S and Mulla M S 1982b. Residual activity of insect growth regulators agent stored product beetles in grain commodities. *J. Econ. Ent.* **75**: 599-603.

- Michaud J P 2003. Toxicity of fruit fly baits to beneficial insects in citrus. *J. Insect Sci.* **3**: 1-9.
- Miles M 2006. The effects of spinosad on beneficial insects and mites used in integrated pest management systems in greenhouses. *Pesticides and Beneficial Organisms IOBC/wprs Bulletin* **29**: 53–59.
- Miles M and Dutton R 2000. Spinosad- a naturally derived insect control agent with potential for use in glasshouse integrated pest management systems. *Mededelingen Faculteit Landbouwkundige en Toegepaste Biologische Wetenschappen Universiteit Gent* **65(2a)**: 393–400.
- Miles M and Eelen H 2006. The Effects of Spinosad to beneficial insects and mites and its use in IPM communications in applied biological science. *Ghent University* **71(2b)**: 275–284.
- Mohyuddin A I 1971. Comparative biology and ecology of *Apanteles flavipes* Cam. and *A. sesamiae* as parasite of graminaceous borers. *Bull. Ent. Res.* **61**: 33-39.
- Mollaie M, Izadi H and Dashti H 2011. Efficacy of spinosad against three stored-product insect pests. *Iranian J. Entomol.* **1**: 8-12.
- Mondal K A M S H 1984a. *Effect of methylquinone, aggregation pheromone and pirimiphos-methyl on Tribolium castaneum Herbst larvae*. Unpublished PhD thesis, University of Newcastle upon Tyne, UK, pp. 259.
- Mondal K A M S H 1985. Response of *Tribolium castaneum* Herbst. Larvae to aggregation pheromone and quinones produced by adult conspecifics. *Int. Pest Cont.* **27(3)**: 64-66.
- Mondal K A M S H 1986. Effect of methylquinone, aggregation pheromone and piriphos-methyl on larval growth of *Tribolium castaneum* Herbst. *Bangladesh J. Zool.* **14(2)**: 123-128.

- Mondal K A M S H 1988. Effect of synthetic methylquinone, aggregation pheromone and piriphos-methyl on fertility of *Tribolium castaneum* Herbst. *Pakistan J. Zool.* **21**: 45-51.
- Mondal K A M S H and Malek M A 1996. Traditional paddy drying in Bangladesh and associated problems (B R Champ, Highly E and Johnson G I eds). *Proc. Conf. Grain Drying in Asia*. 17-20 October, Bangkok, Thailand.
- Mondal K A M S H and Parween S 2000. Insect growth regulators and their potential in the management of stored product insect pests. *Integra. Pest Manage. Rev.* **5**: 255-295.
- Mondal K A M S H and Parween S 1997. Laboratory culturing of flour beetles *Tribolium* species. *Tribolium Int. Bull.* **37**:153-162.
- Mondal K A M S H and Port G R 1995. Effects of Cyromazine on larval growth and adult population of susceptible and malathion-resistant strains of *Tribolium castaneum* Herbst. (Coloptera: Tenebrionidae). *J. Biol. Sci.* **3**:1-10.
- Mondal M and Khalequzzaman M 2010. Toxicity of naturally occurring compounds of plant essential oil against *Tribolium castaneum* Herbst. *J. Biol. Sci.* **10**: 10-17.
- Mondal O A, Mondal KAMSH, Islam N and Khan AR 2012. Screening of *Derris indica* Bennet. for cytotoxicity against *Artemia salina* and phytotoxicity on mustard seeds. *Univ. J. Zool. Rajshahi Univ.* **31**:59-64.
- Mulder R and Gijswitj M J 1973. The laboratory evaluation of two promising new insecticides which interfere with cuticle deposition. *Pestic. Sci.* **4**: 737-745.
- Mulder R, Wellinga K and van Daalen J J 1975. A new class of insecticides. *Naturwissenschaften* **62**: 531-532.
- Muller G and Schlein Y 2006. Sugar questing mosquitoes in arid areas gather on scarce blossoms that can be used for control. *Int. J. Parasitol.* **36**:1077-1080.

- Munakata K 1977. Insect feeding deterrents in plants. In *Chemical control of insect behaviour: Theory and Application*. John Wiley and Sons. New York, pp. 93-102.
- Murata M, Imamura T and Miyanoshita A 2007. Suppression of the stored-product insect *Tribolium castaneum* by *Xylocoris flavipes* and *Amphibolus venator*. *J. Appl. Entomol.* **131**(8): 559-563.
- Mutambuki K, Ngatia C M, Mbugua J N and Likhayo P 2003. Evaluation of the efficacy of spinosad dust against major storage pests. *Proc. 8<sup>th</sup> Int. Conf. on Stored Prod. Protect.* 22-26 July 2002, York, UK. CAB International Wallingford, Oxon, pp 888-891.
- Mutambuki K and Harberd A J 2004. Reference manual on the major insect pests of stored cereal and pulse grains in Somalia and their control.
- Mutambuki K, Ngatia C M, Mbugua J N and Likhayo P 2012. Evaluation on the efficacy of spinosad dust against major storage insect pests. *J. Stored Prod. and Postharvest Res.* **3**(2): 19-23.
- Nayak M K, Darglish G J and Byrne V S 2005. Effectiveness of spinosad as a grain protectant against resistant beetle and psocid pests of stored grain in Australia. *J. Stored Prod. Res.* **41**: 455- 467.
- Nayak M K and Darglish G J 2007. Combined treatments of spinosad and chlorpyrifos methyl for management of resistant psocid pests (Psocoptera: Liposcelididae) of stored grain. *Pest Manage. Sci.* **63**: 104-109.
- Nayar K K, Ananthkrishnan T N and David B Y 1976. *General and applied entomology*. Tala McGraw-Hill, pp.589.
- Nelson S O 1967. Electromagnetic energy. In *Pest control, Biological, Physical and Selected Chemical Methods* (Kilgore W W and Douth R L eds.), Academic Press, London and New York, pp. 89-145.

- Nelson S O and Kantach BH 1966. Stored-grain insect control studies with radio-frequency energy. *J. Econ. Entomol.* **59**: 588-594.
- Newman C R 2010. A novel approach to limit the development of phosphine resistance in Western Australia. Carvalho M O, Fields P G, Adler C S, Arthur F H, Athanassiou C G, Campbell J F, Lessard F F, Flinn P W, Hodges R J, Isikber A A, Navarro S, Noyes R T, Riudavets J, Sinha K K, Thorpe G R, Timlick B H, Trematerra P and White N D G (eds.), *Proc. 10th Int. Work. Conf. on Stored prod. Protect.* 27 June to 2 July 2010, Estoril, Portugal, pp.1038-1044.
- Nguyen D T, Hodges R J and Belmain S R 2008. Do walking *Rhyzopertha dominica* (F.) locate cereal hosts by chance? *J. Stored Prod. Res.* **44**: 90-99.
- Nilakhe S S and Parker R D 1990. Implementation of parasites and predator for control of stored product pests. In *proc. 3<sup>rd</sup> National Stored Grain Pest Manage. Training Conf. Kansas city, Mo, Oct. 20-25. 1990*, pp. 241-250.
- Nishi A. *et al.* 2004. Predatory abilities of *Amphibolus venator* Klug. (Hemiptera: Reduviidae) a predator of stored-product insect pests. *Appl. Entomol. Zool.* **39**: 32 -326
- Obeng-Ofori D 1995. Plant oils as grain protectants against infestations of *Cryptolestes pusillus* and *Rhyzopertha dominica* in stored grain. *Entomologia Experimentalis et Applicata* **77**(2): 133-139.
- Oberlander H, Silhacek D L, Shaaya E and Ishaaya I 1997. Current status and future perspectives of the use of insect growth regulators for the control of stored product insects. *J. Stored Prod. Res.* **33**: 1-6.
- Odderskaer P, Tybirk K, Topping J A, Axelsen M and Pedersen C J B 2003. Effect of reduced pesticide use on plants, insects and birds. *DJF Rapport, Markbrug* **89**: 119-211.

- Okamoto K 1972. The synchronization of the life cycles between *Callosobruchus chinensis* (Linn) and the parasite *Anisopteromalus calandrae* (Howard). I. *Japanese J. Ecol.* **21**: 233-237.
- Oliveira C R F de, Faroni L R A, Guedes R N C and Pallini A 2003. Parasitism by the mite *Acarophenax lacunatus* on beetle pests of stored products. *Biocontrol* **48**: 503-513.
- Oudejans J H 1982. *Agro pesticides: their management and application*. ESCAP Bangkok, Thailand, pp. 205.
- Pajni H R and Bedi A 1974. Male genitalia of *Oryzaephilus mercator* and *Laemophloeus pusillus* Schon. with some remarks on these grains in family Cucujidae (Coleoptera). *Indian J. Ent.* **36**: 28-30.
- Pajni H R and Virk N 1978. Irradiation induced sterility in the males and females of *Tribolium castaneum* Herbst. (Coleoptera: Tenebrionidae). *Curr. Sci.* **47**(5): 175.
- Pandey A C, Ali N and Alam A 1980. *Post-harvest technology in India*. Central Institute of Agricultural Engineering. Nabibagh. Bhopal, India.
- Panford J A. 1987. Application of Near infrared Reflectance Spectroscopy in North America. In: Near-Infrared Technology in the Agricultural and Food Industries, Williams P and K Norris (eds.), ASCC, St. Paul, Minnesota, pp. 201-211.
- Parajulee M N and Phillips T W 1992. Laboratory rearing and field observations of *Lyctocoris campestris* (Heteroptera: Anthocoridae), a predator of stored product insects. *Ann. Entomol. Soc. Am.* **85**: 736-743.
- Parajulee M N and Phillips T W 1993. Effects of prey species on development and reproduction of the predator *Lyctocoris campestris* (Heteroptera: Anthocoridae). *Environ. Entomol.* **22**: 1035-1042.

- Parajulee M N, Phillips T W and Hogg D B 1994. Functional response of *Lyctocoris campestris* F. adults: effects of predator sex, prey species and experimental habitat. *Biol. Control*. **4**: 80 - 87.
- Parajulee M N and Phillips T W 1995. Seasonal Abundance and spatial patterns of the predator *Lyctocoris campestris* in stored corn. *Entomol. Exp. Appl.* **75**(1): 33–42.
- Parajulee M N, Phillips T W, Thorne J E and Nordheim E V 1995. Life history of immature *Lyctocoris campestris* (Hemiptera: Anthocoridae): Effects of constant temperature and relative humidities. *Environ. Entomol.* **24**: 889-897.
- Park T 1962. Beetles competition and population. *Science* **138**: 1369-1475.
- Park T and Frank M B 1948. The fecundity and development of the flour beetles, *Tribolium castaneum* and *Tribolium confusum* at the three constant temperature. *Ecology* **29**:368-375.
- Park S H, Arthur F H, Bean S R and Schober T J 2008. Impact of differing population levels of *Rhyzopertha dominica* (F.) on milling and physicochemical properties of sorghum kernel and flour. *J. Stored Prod. Res.* **44**: 322-327.
- Parker R D and Falconer L L 2004. Preliminary Report Insecticides for the control of insects in stored corn: First on the Evaluation of t 12 Months. Results of Insect Control Evaluations on Corn, Sorghum, and Cotton in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons. Texas Cooperative Extension. Texas A and M University. pp.33-38.
- Parker R D, Falconer L L and Livingston S D 2004a. Evaluation of Insecticides for Control of Insects in Stored Sorghum through Nineteen Months: Part 1. Results of Insect Control Evaluations on Corn, Sorghum, and Cotton in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons. Texas Cooperative Extension. Texas A and M University. pp. 54-79.

- Parker R D, Falconer L L and Livingston S D 2004b. Evaluation of Insecticides for Control of Insects in Stored Sorghum through Twenty-Four Months: Part 2. Results of Insect Control Evaluations on Corn, Sorghum, and Cotton in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons Texas Cooperative Extension. Texas A and M University. pp. 80-95.
- Parker R D and Falconer L L 2005. Report on the Evaluation of Insecticides for Control of Insects in stored Corn: Months 13–21 of Storage. Results of Insect Control Evaluations on Corn, Sorghum, Cotton and Bermudagrass in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons. Texas Cooperative Extension. Texas A and M University. pp. 25-40.
- Parker R D and Falconer L L 2006. Effectiveness of Insecticides on Stored Corn with Rates Selected Based on Four Cents per Bushel Maximum Cost: Ten Month Preliminary Report. Results of Insect Control Evaluations on Corn, Sorghum, and Cotton in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons. Texas Cooperative Extension. Texas A and M University. pp. 16-29.
- Parker R D and Falconer L L 2007. Effectiveness of insecticides on stored corn with rates selected based on four cents per bushel maximum cost: final four months of a fourteen month study. Results of Insect Control Evaluations on Corn, Sorghum, and Cotton in Texas Coastal Bend Counties and Gulf Coast Crop Hybrid/Variety Comparisons. Texas Cooperative Extension. Texas A and M University. pp. 23-29.
- Parween S 1996. *The effect of Triflumuron on Malathion-Susceptible (FSS 11) and malathion-resistant (CTC 12) strains of Tribolium castanum* Herbst. Ph D thesis, University of Newcastle upon Tyne. UK, pp 229.



- Patel K P And Valand V M 1994. Bio-efficacy of plant materials Against *Rhyzopertha dominica* Fab. infesting stored wheat *Triticum aestivum* Linn. *Gujarat Agric. Univ. Res. J.* **20** (1): 180-182.
- Peck S L and McQuate G T 2000. Field tests in environmentally friendly malathion replacements to suppress mediterranean fruit fly populations. *J. Econ. Entomol.* **93**(2): 280-289.
- Pedigo L P 1996. *Entomology and pest management*. Prentice-Hall of India Pvt. Ltd. New Delhi, India, pp.1-646.
- Phillips T W, Parajulee M N and Weaver D K 1995. Toxicity of terpenes secreted by the predator *Xylocoris flavipes* (Reuter) to *Tribolium castaneum* (Herbst) and *Oryzaephilus surinamensis* (L.). *J. Stored Prod. Res.* **31**(2): 131-138.
- Phillips T W, Berberet R C and Cuperus G W 2000. In Francis F J (ed.), *Encyclopedia of food science and technology*, 2<sup>nd</sup> ed. Wiley New York. *Post-harvest integrated pest management*, pp. 2690-2701.
- Phillips T W and Throne J E 2010. Biorational approaches to managing stored-product insects. *Ann. Rev. Entomol.* **55**: 375-397.
- Pimental D 1978. World food. *Pest losses and the development*. American Association for the advancement of science selected symposium No. 13 Westview, Boulder, Colorado.
- Pimental D 1981. *An overview of Integrated Pest Management*. Department of Ecology and Systematics, Cornell University, Ithaca N Y (Mimca) pp.52.
- Pimental D 1983. Environmental aspects of pest management in *Chemistry and World Food Supplies: The Frontiers* (L W SHemitt ed) Pergamon Press, Oxford pp.185-201.

- Pimentel D 2007. Area-Wide Pest Management: Environmental, Economic, and Food Issues. In Vreysen M J B, Robinson A S and Hendrichs J (eds) *Area-Wide Control of Insect Pests: from research to field implementation*. Dordrecht, The Netherlands: Springer, pp. 35-47.
- Pimentel D, Harman R, Pacenza M, Pecarsky J and Pimentel M 1994. Natural resources and an optimum human population. *Population and Environment* **15**: 347- 369.
- Pinniger D B, Stubbs M R and Chambers J 1984. The evaluation of some food attractants for the detection of *Oryzaephilus surinamensis* L. and other storage pests. *Proc. 3<sup>rd</sup> Int. Work. Conf. on Stored Prod. Entomol.* Oct. 23-28, Kansas, USA, pp: 640-650.
- Post L C and Vincent W R 1973. A new insecticide inhibits chitin synthesis. *Naturwissenschaften* **60**: 431-432.
- Post L C, Dejong B J and Vincent W R 1974. 1-(2,6-disubstituted benzoyl)-3-phenylurea insecticides: inhibitors of chitin synthesis. *Pestic. Biochem. Physiol.* **4**: 473-483.
- Potter C 1935. The biology and distribution of *Rhyzopertha dominica* F. *Transactions of the Royal Entomological Society of London* **83**: 449- 482.
- Potting R P J, Otten H and Vet L E M 1997. Absence of odour learning in the stemborer parasitoid, *Cotesia flavipes*. *Anim. Behav.* **53**: 1211-1223.
- Prabhakaran S 2006. Commercial performance and global development status of Profumes gas fumigant. *Proc. 9th Int. Work. Conf. on Stored Prod. Protect.* Oct.15-18, 2006, Brazilian Post-harvest Association, Campinas, Brazil. pp. 635-641.
- Prates H T, Santos J P, Waquil J M, Fabris J D, Oliveira A B and Foster J E 1998. Insecticidal activity of monoterpenes against *Rhyzopertha dominica* F. and *Tribolium castaneum* Herbst. *J. Stored Prod. Res.* **34**(4): 243-249.

- Press J W 1989. Compatibility of *Xylocoris flavipes* (Hemiptera: Anthocoridae) and *Ventura canescens* (Hymenoptera: Ichneumonidae) for suppression of the almond moth *Cadra cautella* (Lepidoptera: Pyralidae). *J. Entomol. Sci.* **24**: 155-160.
- Press J W, Flaherty B R and Arbogast R T 1973. Development of *Xylocoris flavipes* on *Plodia interpunctella* killed by gamma radiation or freezing. *The Florida Entomol.* **56**: 1.
- Press J W, Flaherty B R and Arbogast R T 1974. Interactions among *Plodia interpunctella*, *Bracon hebetor* and *Xylocoris flavipes*. *Environ. Entomol.* **3**: 183-184.
- Press J W, Flaherty B R and Arbogast R T 1975. Control of the red flour beetle, *Tribolium castaneum*, in a ware house by a predacious bug, *Xylocoris flavipes*. *J. Ga. Entomol. Soc.* **10**: 76-78.
- Press J W, Flaherty B R and Arbogast R T 1976. The effect of low temperature on the egg hatch and subsequent nymphal survival of the predacious bug, *Xylocoris flavipes* (Hemiptera: Anthocoridae). *J. Ga. Entomol. Soc.* **10**:150-153.
- Press J, Flaherty W B R and McDonald L L 1978. Toxicity of five insecticides to the predaceous bug *Xylocoris flavipes* (Hemiptera: Anthocoridae). *J. Ga. Entomol. Soc.* **13**: 177-181.
- Press J W, Flaherty B R and Arbogast R T 1979. Vertical disperation and control efficacy of the predator *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae) in farmer's stock peanuts. *J. Kansas Entomol. Soc.* **52**: 561-564.
- Press J W, Cline L D and Flaherty B R 1982. A comparison of two parasitoids, *Bracon hebetor* (Hymenoptera: Braconidae) and *Venturia canescens* (Hymenoptera: Anthocoridae), and a predator *Xylocoris flavipes* (Hemiptera: Anthocoridae) in suppressing residual populations of the almond moth, *Ephestia cautella* (Lepidoptera: Pyralidae). *J. Kansas Entomol. Soc.* **55**(4): 725-728.

- Press J W, Cline L D and Flaherty B R 1984. Suppression of residual populations of the rice weevil, *Stophilus oryzae* by the parasite wasp, *Anisopteromalus calandrae*. *J. Ga. Entomol. Soc.* **19**: 110-113.
- Prokopy R J, Jacome I, Pintero J, Gullen L, Diaz Leischer F, Hu X and Aluja M 2000. Postalighting responses of Mexican fruit flies (Dipt. Tephritidae) to different insecticides in paint on attractive spheres. *J. Appl. Entomol.* **124**: 239-244.
- Prozell S, Scholler M, Hassan S A and Reichmuth Ch 1996. Release of *Trichogramma evanescens* as a component of an integrated pest management programme in organic food bakeries and stores (Hymenoptera: Trichogrammatidae). *Proc. 20<sup>th</sup> Int. Congress Entomol. Firenze, Italy, August 25-31,1996*, pp. 555.
- Prozell S and Scholler M 1998. Insect fauna of a bakery, processing organic grain and applying *Trichogramma evanescens* Westwood. *Integrated Protection of Stored Products* (IOBC Bulletin), **21**: 39- 44.
- Quarles W 1992. Silica gel for pest control. *IPM Practitioner.* **14**:1-11.
- Rahman M M and Yadav T D 1985. Efficacy of Deltamethrin, Cypermethrin, Permethrin and Fenvalerate dusts on three seeds with different moisture contents stored in different containers up to 180 days against *Callosobruchus maculatus* F. and *C. chinensis* L. *Seeds and Farms* **11**: 49-50.
- Rahman M M 2006. *Bionomics of Platanoxus westwoody (Kieffer) (Hymenoptera: Bethyridae) and Xylocoris flavipes (Reuter) (Hemiptera: Anthcoridae) on Cryptolestes pusillus (Schon) (Coleoptera: Cucujidae)*. Ph D thesis, University of Rajshahi, Rajshahi, Bangladesh. 188pp.
- Rahman M M and Islam W 2007. Effect of acetic extracts of *Calotropis procera* R Br in (Aif) on reproductive potential of the flat grain beetle *Cryptolestes pusillus* Schon (Coleoptera: Cucujidae). *Bangladesh J. Sci. Ind. Res.* **42** (2):157-162.

- Rahman S S, Rahman M M, Begum S A, Khan M M R and Bhuiyan M M H 2007. Investigation of *Sapindus mukorossi* extracts for repellency, insecticidal activity and plant growth regulatory effect. *J. Appl. Sci. Res.* **3**(2): 95-101.
- Rahman M M, Islam W and Ahmed K N 2007. Effect of temperature on the predator *Xylocoris flavipes* Reuter (Hemiptera: Anthocoridae) feeding on *Cryptolestes pusillus* Schon (Coleoptera: Cucujidae). *J. bio-sci.* **15**: 41- 46.
- Rahman M M, Islam W and Ahmed K N 2008. Fertility life table of *Plastanoxus westwoody* (Kieffer) (Hymenoptera: Bethyridae) on *Cryptolestes pusillus* Schon (Coleoptera: Cucujidae). *J. bio-sci.* **16**: 25-28.
- Rahman M M, Islam W and Ahmad K N 2009. Functional response of the predator *Xylocoris flavipes* to three stored product insect pests. *Int. J. Agric. Biol.* **11**: 316-320.
- Rajakpase R 2000. Pesticidal effect of tropical plants-insecticidal activity of some selected botanicals against *Callosobruchus maculatus* F. and *C. chinensis* L. (Coleoptera: Bruchidae) Entomocongress, 5-8 November, Trivandrum, Kerala, India. pp.11-12.
- Rajashekar Y, Bakthavatsalam N and Shivanandappa T 2012. Botanicals as Grain Protectants. Hindawi Publishing Corporation Psyche Volume 2012, Article ID 646740, 13 pp.
- Rajashekar Y, Gunasekaran N and Shivanandappa T 2010. Insecticidal activity of the root extract of *Decalepis hamiltonii* against stored-product insect pests and its application in grain protection. *J. Food Sci. Tech.* **47**(3): 310–314.
- Rajendran C 1990. *Toxicity of selected plant products and insecticides in the flour beetle Tribolium castaneum* Herbst. and the fruit fly, *Drosophila melanogaster* Meig. Ph D Thesis, 181pp.

- Rajendran S and Chayakumari S 2003. Insect infestation and control in stored grain sorghum and millerts. *J. Food Sci. Technol.* **40**(5): 451- 457.
- Rajendran S and Sriranjini V 2008. Plant products as fumigants for stored-product insect control. *J. Stored Prod. Res.* **44**(2): 126-135.
- Ranali R P, Howell T A, Arthur F H and Gardisser D R 2002. Controlled ambient aeration during rice storage for temperature and insect control. *Applied Eng. in Agric.* **18**(4): 485-490.
- Rao H R G and Wilbur D A 1972. Loss of wheat weight from feeding of lesser grain borer. *J. Kansas Entomol. Soc.* **45**: 238-241.
- Reed C and Harner J 1998a. Cooling of stored wheat using multiple or single cycles using automatic aeration controllers. *Applied Eng. in Agric.* **14**(5): 497-500.
- Reed C and Harner J 1998b. Thermostatically controlled aeration for insect control in stored hard red winter wheat. *Applied Eng. Agric.* **14**(5): 501-505.
- Reed C R, Wright V F, Mize T W, Pedersen J R and Evans J B 1991. Pitfall traps and grain samples as indicators of insects in farm-stored wheat. *J. Econ. Entomol.* **84**: 1381-1387.
- Rees D 2004a. *Insects of stored products*. Collingwood, VIC, Australia: CSIRO Publishing, Australia.
- Rees D 2004b. Beetles-bruchid or seed beetles. In *Insects of stored products*. CSIRO Publishing, Collingwood, Australia, pp.39-46.
- Reichmuth C H 1992. A quick test of determined phosphine resistance in stored product insect pests. *Proc. European Cong. Ent. April.1991, Vienna.* pp. 245-247.
- Reimann J G and Flint H M 1967. Irradiation effects on midgut and testes of the adult boll weevil *Anthonomus grandis*, determined by histological and shielding studies. *Ann. Ent. Soc. Am.* **60**: 298-308.

- Reinhardt F, Herle M, Bastiansen F and Streit B 2003. Economic impact of the spread of alien species in Germany. Berlin, Germany: Federal Environmental Agency (Umweltbundesamt). 229 pp.
- Remold H 1963. Scent-glands of land-bugs, their physiology and biological function. *Nature* **198**: 764-768.
- Retnakaran A, Granett J and Ennis T 1985. Insect growth regulators. In *Comprehensive insect physiology, Biochemistry and Pharmacology* (Kerkut G A and Gilbert L I eds.), Pergamon Press. Oxford **12**(15): 529-601.
- Reus J, Leendertse P, Bockstaller C, Fomsgaard I, Gutsche V, Lewis K, Nilsson C, Pussemier L, Trevisan M, Van Derwere H, Alfarroba F, Blumel S, Isart J, Mcgrath D and Seppa L A T 2002. Comparison and evaluation of eight pesticide environmental risk indicators developed in Europe and recommendations for future use. *Agri. Ecosyst. and Environ.* **90**:177-187.
- Reynolds S E 1987. The cuticle, growth and moulting in insects: the essential background to the action of acylurea insecticides. *Pestic. Sci.* **20**:131-146.
- Richard W M, Cummins K W and Berg M B 2007. An Introduction to the Aquatic Insects of North America 4th edn .
- Romi R, Proietti S, Di Luca M and Cristofaro M 2006. Laboratory evaluation of the bioinsecticide spinosad for mosquito control. *J Am Mosq Control Assoc.* **22**: 93-96.
- Rooker J 1999. Alternatives to organophosphates to be widely encouraged on farms. *World Food Regul. Rev.* **8**: 13-13.
- Russo A C and Vasta G E M C 2004. Life tables of *Xylocoris flavipes* (Hemiptera: Anthocoridae) feeding on *Tribolium castaneum* (Coleoptera: Tenebrionidae). *J. Stored Prod. Res.* **40**: 103-112.

- S A S Institute 1996. SAS / STAT user's guide for personal computers, version 6.12 ed, S A S Institue, Cary, NC.
- Sabbour M M 2003. Combined effects of some microbial control agents mixed with botanical extracts on some stored product insects. *Pak. J. Biol. Sci.* **6**: 51-56.
- Sabbour M M and Abd El-Aziz S E 2007. Evaluation of some bioinsecticides and packaging materials for protecting broad bean against *Callosobruchus maculatus* (Coleoptera: Bruchidae) infestation during storage. *Bull. Entomol. Soc. Egypt Econ. Ser.* **33**:129-137.
- Sabbour M M and Abd El-Aziz S E 2010. Efficacy of some bioinsecticides against *Bruchidius incarnates* (Boh.) (Coleoptera: Bruchidae) infestation during storage. *J. Plant Prot. Res.* **50**: 25-31.
- Saha S R 2007. *Performance of the predator Xylocoris flavipes Reuter (Hemiptera: Anthocoridae) reared on artificial diets on Tribolium*. PhD thesis, Rajshahi University, Rajshahi, Bangladesh. 197 pp.
- Salgado V L 1997. The mode of action of Spinosad and other insect control products. *Down to Earth* **52**: 35- 44.
- Salgado V L 1998. Studies on the mode of action of Spinosad, insect symptoms and physiological correlates. *Pestic. Biochem. Physiol.* **60**: 91-102.
- Salgado V L and Sparks T C 2005. The spinosyns: chemistry, biochemistry, mode of action and resistance. Gilbert L I, Iatrou K and Gill S (eds.), *Comprehensive Insect Molecular Science*, Elsevier B V **6**:137-173.
- Salgado V L, Sheets J L, Watson G B and Schmidt A L 1998. Studies on the mode of action of spinosad: the internal effective concentration and the concentration dependence of neural excitation. *Pestic. Biochem. Physiol.* **60**: 103-110.



- Samson P R, Parker R J and Hall E A 1990. Efficacy of the insect growth regulators methoprene, fenoxycarb and diflubenzuron against *Rhyzopertha dominica* (F.) (Coleoptera: Bostrichidae) on maize, paddy- rice. *J. Stored Prod. Res.* **26**: 215-221.
- Sanchez-Marinez R I, Cortez-Rocha M O, Ortega-Dorame F, Morales-Valdes M, Silveira M I 1997. End-use quality of flour from *Rhyzopertha dominica* infested wheat. *Cereal Chemist* **74**: 481- 483.
- Sanguanpong U 1996. Using the neem oil pellets in controlling the rice weevil *Sitophilus oryzae*. *The Agricultural Science Society of Thailand Newsletter (ASST Newsletter)*. **29** (1-3): 6-15.
- Sanon A, Ba N B, Binso-Dabire C L and Pittendrigh B R 2010. Effectiveness of spinosad (Naturalytes) in controlling the cowpea storage pest, *Callosobruchus maculatus* (Coleoptera: Bruchidae). *J. Econ. Entomol.* **103**: 203-210.
- Saunders D G and Bret B L 1997. Fate of spinosad in the environment . *Down to Earth* **52**: 14-20.
- Saxena A B 1996. *Biological control of insect pests*. Anmol Publication, New Delhi, India, pp.54.
- Saxena R C 1995. Pests of Stored Products. In Schmutterer H (Editor), The neem tree *Azadirachta indica* A. Juss. and other meliaceous plants. VCH Publishers Inc., New York, USA, pp. 418- 432.
- Saxena S C and Kumar D 1989. Effect of two new chitin synthesis inhibitor compounds on different developmental stages of *Trogoderma granarium* Evert. *J. Anim. Morphol. Physiol.* **36** (2): 219-222.
- Saxena S C and Mathur G 1981a. Suppression of adult emergence of treating eggs of *Tribolium castaneum* Herbst. by new synthesized distributed benzoylphenyl urea compounds. *Curr. Sci.* **50**(7): 33.

- Saxena S C and Mathur G 1981b. Suppression of adult emergence by administering new synthesized chitin synthesis inhibitor compound in *Tribolium castaneum* Herbst. *J. Environ. Biol.* **2**: 7-10.
- Schatzki T F and Fine T A 1988. Analysis of radiograms of wheat kernels for quality control. *Cereal Chemistry* **65**: 233-239.
- Schatzki T F, Wilson E K, Kitto G B, Behrens P and Heller I 1993. Determination of hidden *Sitophilus granarius* (Coleoptera: Curculionidae) in wheat by myosin ELISA. *J. Econ. Entomol.* **86**: 1584-1589.
- Schlupalius D, Chen W, Collins P, Nguyen T, Reilly P and Ebert P 2008. Gene interactions constrain the course of evolution of phosphine resistance in the lesser grain borer, *Rhyzopertha Dominica*. *Heredity*. **100**: 506-516.
- Scholler H, Hasa S A and Reichmuth C 1996. Efficacy assessment of *Trichogramma evanescens* and *T. embryophagum* (Hymenoptera: Trichogrammatidae) for control of stored product moth pests in bulk wheat. *Entomophaga* **41**(1):125-132.
- Scholler M and Flinn P W 2000. Parasitoids and predators. In *Alternatives to pesticides in stored products IPM*. (Subramanyam Bh and Hagstrum DW eds.), Kluwer Academic Publishers, 101 Philip Drive, Massachusetts pp. 229-271.
- Scholler M, Prozell S, Al-Kirshi A G and Reichmuth Ch 1997. Towards biological control as a major component of integrated pest management in stored product protection. *J. Stored Prod. Res.* **33**: 81-97.
- Schoonover J R and L L Larson 1995. Laboratory activity of spinosad on non-target beneficial arthropods. *Arthropod Manage. Tests* **20**: 357.
- Schwardt H H 1933. Life history of the lesser grain borer. *J. Kansas Entomol. Soc.* **2**: 61- 66.

- Scott H G 1991. Nutrition changes caused by pests in food. In Ecology and Management of Food-Industry Pests, Gorham J R (eds.). AOAC, Virginia, USA, pp 463- 467.
- Scott J G 1998. Toxicity of Spinosad to susceptible and resistant strains of house fly, *Musca domestica*. *Pestic Sci.* **54**: 131-133.
- Scott J G, Alefantis T G, Kaufman P E and Rutz D A 2000. Insecticide resistance in house flies from caged-layer poultry facilities. *Pest. Manag. Sci.* **56**: 147-153.
- Seitz L M and Ram M S 2004. Metabolites of lesser grain borer in grains. *J. Agric. and Food Chem.* **52**: 898 - 908.
- Shaaya E, Kostjukovski M, Eilberg J, Sukprakarn C, Shaaya E (ed) and Bell C 1997. Plant oils as fumigants and contact insecticides for the control of stored insects: ecologically safe alternatives for the control of stored-product insects. Papers from the 13<sup>th</sup> Int. Plant Protect. Congress, July 1995, The Hague, The Netherlands. *J. Stored Prod. Res.* **33**(1): 7-15.
- Sharangapani M V and Pingale S V 1957. A study of movements of some insect pests through grain stored in bags. *Indian J. Entomol.* **18**: 243-250.
- Sharififard M, Mossadegh M S, Vazirianzadhe B and Mahmoudabadi A Z 2011. Laboratory pathogenicity of entomopathogenic fungi, *Beauveria bassiana* (Bals.) Vuill. and *Metarhizium anisoplae* (Metch.) Sorok. to larvae and adult of house fly, *Musca domestica* L. (Diptera: Muscidae). *Asian J Bio Sci.* **4**(2): 128-137.
- Shejbal J 1980. *Controlled atmosphere storage of grains*. Elsevier, Amsterdam
- Shrama P K and Michaelraj S 2006. Efficacy of spinosad as seed protectant against the pests of stored maize. *Pestic. Res. J.* **18**: 173-176.

- Shukla R M, Chand G and Saini M L 1992. Laboratory evaluation of effectiveness of edible oils against three species of stored grain insects. *Plant Prot. Bull. (Faridabad)* **44**: 14-15.
- Shuman D, Coffelt J A, and Weaver D K 1996. A computer-based electronic fall-through probe insect counter for monitoring infestation in stored products. *Trans. Am. Assoc. Agric. Eng.* **39**: 1773-1780.
- Shuman D, Weaver D K and Larson R G 2005. Performance of an analytical, dual infrared-beam, stored product insect monitoring system. *J. Econ. Entomol.* **98**: 1723-1732.
- Simelane D O, Steinkraus D C and Kring T J 2008. Predation Rate and Development of *Coccinella septempunctata* L. Influenced by *Neozygites fresenii*-Infected Cotton Aphid Prey. *Biological Control* **44**: 128-135.
- Simmonds F J, Franz J M and Sailer R I 1976. History of the biological control. In *Theory and Practice Biological Control* (Huffaker C B and Messenger P S eds). Academic Press, New York, pp.17-39.
- Sinclair E R 1982. Population estimates of insect pests of stored products on farms on the Darling Downs, Queensland. *Aust. J. Experi. Agric. Ani. Husb.* **22**: 127-132.
- Sing S E 1979. Suppression of bruchids infesting stored grain legumes with the predatory bug *Xylocoris flavipes* (Reuter) (Hemiptera: Anthocoridae). M S Thesis, Me Gill University, Montreal pp 97
- Sing S E and Arbogast R T 2008a. Optimal *Xylocoris flavipes* (Reuter) (Hemiptera: Anthocoridae) density and time of introduction for suppression of bruchid progeny in stored legumes. *Environ. Entomol.* **37**(1):131-142.
- Sing S E and Arbogast R T 2008b. Predatory response of *Xylocoris flavipes* (Reuter) (Hemiptera: Anthocoridae) to bruchid pests of stored food legumes. *Entomol. Exp. Appl.* **126**:107-114.

- Sinha R N and Watters F L 1985. *Insect pests of flour mills, grain elevators, and feed mills and their control*. Ottawa, on: Agriculture Canada.
- Smet H, Rans M and Deloof A 1990. Comparative effectiveness of insect growth regulators with juvenile hormone, anti-juvenile hormone and chitin synthesis inhibiting activity against several stored food insect pests. *Proc 5<sup>th</sup> Int. Work. Conf. Stored Prod. Prot.* Bordeaux, France, 9-14 September, 1990 (Fleurt- Lessard F and Ducom D eds.) **2**: 649-657.
- Smith H S 1919. On some phases of insect control by the biological method. *J. Econ. Entomol.* **12**: 288-292.
- Smith R, Van den F and Bosh R 1967. Integrated control. In *Pest Control: Biological, Physical and Selected Chemical Methods* (W W Kilgore and Douthett R L eds). Academic Press, New York , pp.295-340.
- Smith L 1993. Effect of humidity on life history characteristic of *Anisopteromalus calandrae* parasitizing maize weevil larvae in shelled corn. *Environ. Entomol.* **22**: 618-624.
- Sobhy I, Sarhan A, Shoukry A, El-Kady G, Mandour N and Reitz S 2010. Development, consumption rates and reproductive biology of *Orius albidipennis* reared on various prey. *Bio Control* **55**: 753-765.
- Sokoloff A 1974. *The biology of Tribolium, with special emphasis on genetic aspects*. Oxford University Press, **2**: 628.
- Sparks T C, Thompson G D, Larson L L, Kirst H A, Jantz O K, Worden T V, Hertlein M B and Busacca J D 1995. Biological characteristics of the spinosyns: new naturally derived insect control agents. Proceedings of the Beltwide Cotton Conference, San Antonio, Texas, National Cotton Council of America, Memphis, TN. pp. 903-907.

- Sparks T C, Thompson G D, Kirst H A, Hertlein M B, Mynderse J S, Turner J R, and Worden T V 1999. Fermentation-derived insect control agents: The spinosyns. In *Biopesticides: Use and Delivery*. Hall F R and Menn J J eds. Humana Press, Totowa, NJ. pp. 171-188.
- Sparks T C, Crouse G D and Durst G 2001. Natural products as insecticides, the biology, biochemistry and quantitative structure-activity relationships of spinosyns and spinosoids. *Pest Manage. Sci.* **57**: 96-905.
- Spotti C A 2004. The use of fumigation and grafted plants as alternative to methylbromide for the production of tomatoes, vegetables and strawberries in Italy. *International conference on alternatives to methylbromide*. Lisbon 27-30.
- Srinivasa K B, Murthy M S N and Ramesh T B 1993. Effect of botanicals on certain parasitoids. Paper presented at World Neem Conference, India, 1993. *Neem and Environ*, India **2**: 1117. Oxford and IBH Publishing Co. Pvt. Ltd.
- Stark J D, Jepson P C and Mayer D F 1995. Limitations to use of topical toxicity data for predictions of pesticide side effects in the field. *J. Econ. Entomol.* **88**:1081-1088.
- Stark J D, Vargas R I and Miller N W 2004. Toxicity of spinosad in protein bait to three economically important tephritid fruit fly species (Diptera: Tephritidae) and their parasitoids (Hymenoptera: Braconidae). *J. Econ. Entomol.* **97**: 911-915.
- Stat Soft Inc 1997. StatSoft Inc, 1997. STATISTICA for windos (computer program manual) Tulsa ok.
- Steidle J L M, Rees D and Wright E J 2001. Assessment of Australian *Trichogramma* species (Hymenoptera: Trichogrammatidae) as control agents of stored product moths. *J. Stored Prod. Res.* **37**: 263-275.
- Storey C L, Sauer, D B, Ecker O and Fulk D W 1982. Insect infestation in wheat and corn exported from the United States. *J. Econ. Entomol.* **75**: 827-832.

- Subramanyam Bh 2006a. Performance of spinosad as a stored grain protectant. In Lorini I, Bacaltchuk B, Beckel H, Deckers D, Sundfeld E, Santos J P, Biagi J D, Celaro JC, Faroni L R D A, Bortolini L O F, Sartori M R, Elias M C, Guedes R N C, Fonseca R G and Scussel V M (eds.), *Proc. 9<sup>th</sup> Int. Conf. on Stored Prod. Protect.* 15-18 October 2006, ABRAPOS, Campinas, Sao Paulo, Brazil. pp. 250-257.
- Subramanyam Bh 2006b. Spinosad: a new grain protectant. *World Grain*. pp. 58-63.
- Subramanyam Bh, Swanson C L, Madamanchi N and Norwood S 1994. Effectiveness of Insecto™, a new diatomaceous earth formulation, in suppressing several stored-grain insect species. Highley E, Wright E J, Banks H J and Champ B R (eds.), *Proc. 6<sup>th</sup> Int. Work. Conf. on Stored prod. Protect.* 17–23 April 1994, Canberra, Australia, CAB International, Oxford, UK. pp. 650-659.
- Subramanyam Bh and Hagstrum D W 1995. Resistance measurement and management. In *Integrat. Manage Insect in Stored Prod.* Subramanyam Bh and Hagstrum D W (eds.). Marcel Decker, New York, pp.331-398.
- Subramanyam Bh and Hagstrum DW 1996. Resistance measurement and management. Subramanyam Bh and Hagstrum D W (eds.), *Integrat. Manage. Insects in Stored Prod.* Marcel Decker, New York, pp. 331-397.
- Subramanyam Bh and Nelson J 1999a. Trapping indoors and out-lessons from the red flour beetle survey. *The Sanitarian* **3**: 7-9.
- Subramanyam Bh, Nelson J J, Meronuck R A and Flora E A 1999b. Evaluation of spinosad on stored-product insects. Jin Z X, Liang Q, Liang Y S, Tan X C and Guan L H (eds.), *Stored Product Protection. Proc. 7<sup>th</sup> Int. Work. Conf. on Stored Prod. Protect.* Beijing, China, October 14–19, 1998, Chengdu, China, Sichuan Publishing House of Science and Technology, Chengdu, PR China. **1**: 940-949.

- Subramanyam Bh, Toews M D and Fang L 2002. Spinosad: an effective replacement for organophosphate grain protectants. Credland P F, Armitage D M, Bell C H, Cogan P M and Highley E (eds.), *Proc. 8th Int. Work. Conf. on Stored Prod. Protect.* July 22–26, 2002, York, UK, CAB International, Wallington, Oxon. pp. 916-920.
- Subramanyam Bh, Toews M D and Fang L 2003. Spinosad: an effective replacement for organophosphate grain protectants. Credland P F, Armitage D M, Bell C H, Cogan P M and Highley E (Eds.), *Proc. 8th Int. Work. Conf. on Stored Prod. Protect.* 22–26 July 2002, York, UK, CAB International, Wallingford, UK. pp. 916-924.
- Subramanyam Bh, Toews M D, Pitts T J, Thompson G D and Hertlein M B 2004. Spectrum of activity of spinosad against stored-product insects. In *Proceedings of the International Quality Grains Conference, a global symposium on quality-assured, traceable and biosecure grains and oilseeds for the 21st century*, 19–22 July 2004, Indianapolis, IN.
- Subramanyam Bh, Toews M D, Ileleji K E, Maier D E, Thompson G D and Pitts T J 2007. Evaluation of spinosad as a grain protectant on three Kansas farms. *Crop Prot.* **26**:1021-1030.
- Subramanyam Bh, Hartzler M and Boina D R 2012. Performance of pre commercial release formulations of Spinosad against five stored-product insect species on four stored commodities. *J. Pest Sci.* **85**: 331-339.
- Suchita M G, Reddy G P U and Murthy M M K 1989. Relative efficacy of pyrethroids against rice weevil (*Sitophilus oryzae* L.) infesting stored wheat. *Indian J. Plant Protect.* **17**: 243-246.
- Suh C P C, Orr D B and Van Duyn J W 2000. Effect of insecticides on *Trichogramma exiguum* (Hymenoptera) preimaginal development and adult survival. *J. Econ. Entomol.* **93**: 577-583.



- Sumita F 2006. Combination of neem and physical disturbance for the control of flour insect pests of stored products. *Int. J. Tro. Insect Sci.* 16-27.
- Suresh S, White N D G, Jayas D S and Hulasare R B 2001. Mortality caused by interactions between the red flour beetle, *Tribolium castaneum* and the rusty grain beetle, *Cryptolestes ferrugineus*. *Proc. Entomol. Soc. of Manitoba* **57**: 11-18.
- Szabela DA 2005. *The fate and efficacy of spinosad for insect management in farm stored corn*. M S Thesis. Purdue University, West Lafayette, Indiana, 146 pp.
- Tawfik M F S, Awadallah K T, Abou-zeid N A and Abdella M M H 1982. Effect of feeding on various preys on the bio-cycle of *Xylocoris flavipes* Reuter. *Res. Bull.* No. 623, Faculty of Agriculture, Zagazig University, pp 1-10.
- Taylor R W D 1989. Phosphine: a major fumigant at risk. *Int. Pest Con.* **31**:10-14.
- Taylor R W D 1994. Methyl-bromide – Is there any future for this note worthy fumigant ? *J. Stored Prod. Res.* **30**: 253-260.
- Thomas A, Green P D, Dawn H and Gouge P D 2009. School IPM 2015: A strategic plan for integrated pest management in school in the united states.USDA Northeastern, North Central, Southern and Western Regional IPM Centers.
- Thomas P J and Bhatnagar-Thomas P L 1968. Use of a juvenile hormone analogue as insecticides of pests of stored grain. *Nature* (London) **219**: 949.
- Thompson V 1966. Biology of the lesser grain borer, *Rhyzopertha dominica* (F). *Bull. Grain Tech.* **4**:163-168.
- Thompson G D, Busacca J D, Jantz O K, Krist H A, Larson L L and Sparks T C 1995. Spinosyns: an overview of new natural insect management systems. *Proc. Belkwide cotton Conf.* pp.1039-1043.

- Thompson G D, Michel K H, Yao R C, Mynderse J S, Mosburg C T, Woden T V, Chio E H, Sparks T C and Hutchins S H 1997. The discovery of *Saccharopolyspora spinosa* and a New Class of Insect Control Products. *Down to Earth* **52**:1-5.
- Thompson G D R , Dutton and T C Sparks 2000. Spinosad a case study an example from a natural products discovery programme. *Pest Manage. Sci.* **56**: 696-702.
- Thompson D G, Harris B J, Lanteigne L J, Buacarint T M and Chartrand D T 2002. Fate of spinosad in litter and soils of a mixed conifer stand in the Acacian forest region of New Brunswick. *J. Agric. Food Chem.* **50**: 790-795.
- Tillman P G and J E Mulrooney 2000. Effect of selected insecticides on the natural enemies *Coleomegilla maculate* and *Hippodamia convergens* (Coleoptera: Coccinellidae), *Geocoris punctipes* (Hemiptera: Lygaeidae) and *Bracon mellitor*, *Cardiochiles nigriceps* and *Cotesia marginiventris* (Hymenoptera: Braconidae) in cotton. *J. Econ. Entomol.* **93**: 1638-1643.
- Tiwari S N 1994. Efficacy of some plant products as grain protectants against *Rhizopertha dominica* F. (Col: Bostrichidae). *Int. J. Pest Manage.* **40**(1): 94-97.
- Toews M D and Subramanyam Bh 2003. Contribution of contact toxicity and wheat condition to mortality of stored-product insects exposed to spinosad. *Pest Manage. Sci.* **59**: 538-544.
- Toews M D, Subramanyam Bh and Rowan J 2003. Knockdown and mortality of adults of eight species of stored-product beetles exposed to four surfaces treated with Spinosad. *J. Econ. Entomol.* **96**:1967-1973
- Toews M D and Subramanyam Bh 2004. Survival of stored-product insect natural enemies in spinosad-treated wheat. *J. Econ. Entomol.* **97**: 1174-1180.

- Toews M D, Phillips T W and Payton M E 2005. Estimating populations of grain beetles using probe traps in wheat-filled concrete silos. *Environ. Entomol.* **34**: 712-718.
- Toews M D, Campbell J F, Arthur F H and Ramaswamy S B 2006. Out door flight activity and immigration of *Rhyzopertha dominica* into seed wheat warehouses. *Entomologia Experimentalis et Applicata* **121**: 73- 85.
- .Torres J B, De Clercq P and Barros R 1999. Effect of spinosad on the predator *Podisus nigrispinus* and its lepidopterous prey. Mededelingen Faculteit Land bouwkundige en Toegepaste Biologische Wetenschappen Universiteit Gent **64** (3a): 211-218.
- Tukey J W 1953. The problem of multiple comparisons. Department of Statistics, Princeton University (Unpublished).
- Turner B D 1975. The Psocoptera of Jamaica. *Transactions of the Royal Entomological Society of London* **126**: 533-609.
- Tyler P S, Taylor R W and Rees D P 1983. Insect resistance to phosphine fumigation in food warehouses in Bangladesh. *Int. Pest Cont.* **25**: 10-13.
- Valizadegan O, Pourmirza A A and Safaralizadeh M H 2009. Combination of microwaves radiation and cold storage for control of *Oryzaephilus surinamensis* L. (Col.Silvanidae). *J. Biol. Sci.* **9**: 231-236
- Van Huis A, Wijkamp M G, Lammers P M, Klein Goldewijk C G M, van Seeters J H and Kaashoek N K 1991. *Uscana lariophaga* (Hymenoptera: Trichogrammatidae), an egg parasitoid of bruchid beetle (Coleoptera: Bruchidae) storage pests in West Africa: host-species selection. *Bull. Ent. Res.* **81**: 65-75.
- Vardeman E A, Arthur F H, Nechols J R and Campbell J F 2006. Effect of temperature, exposure interval, and depth of diatomaceous earth treatment on distribution, mortality, and progeny production of lesser grain borer (Coleoptera: Bostrichidae) in stored wheat. *J. Econ. Entomol.* **99**(3):1017-1024.

- Vargas R I, Peck S L, Mcquate G T, Jackson C G, Stark J D and Armstrong J W 2001. Potential for are awide integrated management of Mediteranean Fruit Fly (Diptera: Tephritidae) with a braconid parasitoid and a novel bait spray. *J. Econ. Entomol.* **94**: 817- 825.
- Vayias B J and Athanassiou C G 2004. Factors affecting efficacy of the diatomaceous earth formulation SilicoSec against adults and larvae of the confused beetle *Tribolium confusum* Du Val (Col.Tenebrionidae). *Crop Prot.* **23**: 565-573.
- Vayias B J, Athanassiou C G, Milonas D N and Mavrotas C 2009. Activity of spinosad against three stored-product beetle species on four grain commodities. *Crop Prot.* **28**: 561-566.
- Vayias B J, Athanassiou C G, Kavallieratos N G and Tatsi G 2010. Insecticidal action of the combined use of spinosad and deltamethrin against three stored product pests in two stored hard wheat varieties. In Carvalho O M, Fields P G, Adler C S, Arthur F H, Athanassiou C G, Campbell J F, Fleurat-Lessard F, Flinn P W, Hodges R J, Isikber A A, Navarro S, Noyes R T, Riudavets J, Sinha K K, Thorpe G R, Timlick B H, Trematerra P, White N D G (eds.), *Proc. 10th Int. Work. Conf. on Stored Prod. Protect.* 27 June–2 July 2010, Estoril, Portugal, Julius-Kühn-Archiv, 978-3-930037-65-0, Vol. 425 Berlin, Germany (2010). pp. 921–924.
- Vayias B J, Athanassiou C G, Milonas D N and Mavrotas C 2010a. Persistence and efficacy of spinosad on wheat, maize, and barley grains against four major stored product pests. *Crop Protect.* **29**: 496-505.
- Vayias B J, Athanassiou C G, Milonas D N and Mavrotas C 2010b. Persistence and efficacy of spinosad on wheat, maize and barley grains against four major stored product pests. *Crop Prot.* **29**(5): 496-505.

- Vela-Coiffier E L, Fargo W S, Bonjour E L, Cuperus G W and Ward W D 1987. Immigration of insects into on farm stored wheat and relationship among trapping methods. *J. Stored Prod. Res.* **33**(2): 157-166.
- Vela-Coiffier E L, Fargo W S, Bonjour E L, Cuperus G W and Warde W D 1997. Immigration of insects into on-farm stored wheat and relationships among trapping methods. *J. Stored Prod. Res.* **33**:157–166.
- Verkerk R H J, Leather S R and Wright D J 1998. The potential for manipulating crop-pest-natural enemy interactions for improved insect pest management. *Bull. Entomol. Res.* **88**: 493-501.
- Vijayanna S V 2006. *Effect of fumigation on seed quality during storage of ground nut*. M Sc Thesis, Univ Agric Sci, Dharwad, Karnataka, India.
- Vinson S B and Iwantsch G F 1980. Host survivability for insect parasitoids. *Ann. Rev. Entomol.* **20**: 397-419.
- Visarathanonth P, Nakakita H and Sittisuang P 1994. Role of natural enemies in the regulation of stored-product insect populations in rice storages in Thailand. *JIRCAS J.* **1**:1-7.
- Visarathanonth P, Khumlekasing M and Sukprakarn C 1990. Insecticidal control of cowpea weevil, *Callosobruchus maculatus* F. a pest of mungbean. Bruchids and Legumes: Economics, Ecology and Coevolution (Fujii K, Gatehouse A M R, Johnson C D, Mitchell R and Yoshida T eds.), Kluwer Academic Publishers, Dordrecht, the Netherlands. pp.101-104.
- Waage J K 1991. Biological control: the old and the new. In *Proc. Workshop on Biological control of pest in Canada*, October 11-12, 1990 (A S Mc Clay ed), Calgary, Alberta Environmental Centre, Vegreville, Alberta, Canada, AECV 91-PI pp.105-112.

- Wakefield M E and Cogan P M 1999. The use of a managed bulk of grain for the evaluation of PC, Pitfall beaker, Insect probe and WBII probe traps for monitoring *Sitophilus granarius* during the winter and summer in the UK. *J. Stored Prod. Res.* **35**: 329-338.
- Wang J, Lei Z R, Xu H F and Gao Y L 2011. Virulence of *Beauveria bassiana* Isolates Against the First Instar Nymphs of *Frankliniella occidentalis* and Effects on Natural Enemy *Amblyseius barkeri*. *Plant Protect.* **27**: 479-484.
- Wang X G, Jarjees E A, McGraw B K, Bokonon-Ganta A H, Messing R H and Johnson M W 2005. Effects of spinosad-based fruit fly bait GF-120 on tephritid fruit fly and aphid parasitoids. *Biol. Cont.* **35**: 155-162.
- Watters F L and Shuyler H R 1977. Control of post-harvest losses. *FAO Plant Protect. Bull.* **25**: 184-188.
- Wen B and Deng W 1988. Studies on the simulated control of several stored product insect pests by the predator *Xylocoris* sp. *Acta Phytophylact. Sin.* **15**: 273-276.
- White N D G and Loschiavo S R 1989. Factors affecting survival of the merchant grain beetle (Coleoptera: Cucujidae) and confused flour beetle (Coleoptera: Tenebrionidae) exposed to silica aerogel. *J. Econ. Ent.* **82**: 960-969.
- White N D, Harein P K and Sinha R N 1985. Current status on insecticide recommendations for managing stored grains in Canada and the United States. *Minnesota Agricultural Experiments Station Bull. A D S B*, pp. 25-65.
- WHO 1999. Draft Guideline Specifications for Bacterial Larvicides for Public Health Use. Pesticide Evaluation Scheme. World Health Organization, Geneva.
- Wilbur D A and Halazon G 1955. Pests of farm stored wheat and their control. *Kansas Agricultural Experimental Station Bulletin.* **371**: 3-4.

- Wilbur D A and Mills R B 1978. Stored grain insect. In *Fundamentals of Applied Entomology*, 3rd edn. Macmillan Publishing Co. Inc. pp.73-81.
- Wilkin D K and Nelson G 1987. Microclimate and environmental physiology of insects. *Adv. Insect physiol.* **16**: 1-57.
- Wilkin D R and Fishwick 1981. Residues of the organophosphorus pesticides in wholemeal flour and bread produced from treated wheat. *Proc. British Crop. Prot. Conf. and Diseases* **1**: 183.
- Williams R N and Floyd E H 1971. Effects of low temperature on Hymenopterous parasites *Choetospila elegans* and *Anisopteromalus calandrae* of maize. *J. Entomol.* **64**: 1438-1439.
- Williams T, Valle J and Vinuela E 2003. Is the naturally-derived Insecticide spinosad compatible with insect natural enemies? *Bio. Sci. and Tech.* **13**(5): 459-475.
- Wills J H 1974. Morphogenetic action of insect hormone. *Ann. Rev. Ent.* **19**: 97-115.
- Wilson E O 2009. Threat to Global Diversity. Retrieved 05-17.
- Wing H D and Aller H E 1990. Ecdysteroid agonists as novel insect growth regulators. In *Pesticides and alternatives* (Casida J E ed.), Elsevier Science B V, Amsterdam, Oxford, New York, pp. 251-257.
- Winterbottom D C 1922. Weevil in wheat and storage of grain in bags. A Record of Australian Experience during the War Period (1915 to 1919). Government Printer, North Terrace, Adelaide, Australia.
- Wittenberg R 2005. *An inventory of alien species and their threat to biodiversity and economy in Switzerland*. CABI Bioscience Switzerland Centre.
- Wright J W 1976. Insecticides in human health. In: *The future for insecticides: Needs and Prospects*. (Metcalf R L and Mckelvey Jr J J eds). John Wiley and Sons, New York, pp. 17-34.

- Wright V F, Fleming E E and Post D 1990. Survival of *Rhyzopertha dominica* (Coleoptera: Bostrichidae) on fruits and seeds collected from woodrat nests in Kansas. *J. Kansas Entomol. Soci.* **63**: 344-347.
- Wright D J and Verkerk R H J 1995. Integration of chemical and biological control systems for arthropods: evaluation in a multitrophic context. *Pestic. Sci.* **44**: 207-218.
- Xu HanHong, Chiu S F, Jiang F Y and Huang G W 1993. Experiment on the use of essential oils against stored product insects in a storehouse. *J. South China Agric. Univ.* **14**(3): 42- 47.
- Xu Z, Weng L and He J 2008. A new species of *Cephalonomia* Westwood (Hymenoptera: Bethylidae) parasitizing *Rhyzopertha dominica* (F.) (Coleoptera: Bostrychidae). *Proc. Entomol. Soc. Washington* **110**: 477- 480.
- Yadav T D 1987. Toxicity of Deltamethrin, Cypermethrin, Permethrin against thirteen stored product insects. *Indian J. Ent.* **49**: 21-26.
- Yadav T D 1993. Olfactory, Oviposition and Developmental Response of Four Species of Pulse Beetle to Four Neem Oil Treated Legumes. *World Neem Conf. Bangalore. India*, pp. 343-356.
- Yamanouchi M and Takano T 1980. The effectiveness of milling and sifting of wheat in destruction and elimination of eggs of some stored product insects. *Res. Bull. Plant Prot. Japan* **16**: 99-100.
- Yousefnezhad-Irani R and Asghar P A 2007. Effect of spinosad on adults of *Tribolium castaneum* Herbst (Coleoptera: Tenebrionidae) and *Sitophilus oryzae* L. (Coleoptera: Curculionidae). *Pakistan J. Bio. Sci.* **10**: 2505-2509.
- Zettler L J and Cuperus G R 1990. Pesticide resistance in *Tribolium castaneum* (Coleoptera: Tenebrionidae) and *Rhyzopertha dominica* (Coleoptera: Bostrichidae) in wheat. *J. Econ. Entomol.* **83**: 1677-1681.



- Zettler L J and Arthur F H 2000. Chemical control of stored product insects with fumigants and residual treatments. *Crop Protect.* **19**: 577-582.
- Zimmermann G 2007. Review on Safety of the Entomopathogenic Fungi *Beauveria bassiana* and *Beauveria brongniartii*. *Biocontrol Sci.Technol.* **17**: 553-596.
- Zyromska-Rudzka H 1996. Abundance and emigration of *Tribolium* in a laboratory model. *Ekol. Pol. A.* **14**: 491-578.



# Appendices

Appendix table 1 Effect of 1ppm of Spinosad against the immature and adult stages of different stored product insects

| Insect pests                     | Life stage        | Commodities                        | References  |
|----------------------------------|-------------------|------------------------------------|---|
| <i>Plodia interpunctella</i>     | Immature          | Wheat, corn, sunflower             | Subramanyam <i>et al.</i> (1999), Fang <i>et al.</i> (2002a) and Huang <i>et al.</i> (2007)   |
| <i>Corcyra cephalonica</i>       | Immature          | Corn                               | Huang and Subramanyam (2003), Shrama and Michaelraj (2006)  |
| <i>Cadra cautella</i>            | Immature          | Corn                               | Subramanyam (2004)  |
| <i>Sitotroga cerealella</i>      | Immature          | Wheat, corn                        | Huang <i>et al.</i> (2007)  |
| <i>Rhyzopertha dominica</i>      | Immature<br>Adult | Wheat, corn, rice, sorghum, barley | Subramanyam <i>et al.</i> (1999), Fang <i>et al.</i> (2002a), Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Bonjour <i>et al.</i> (2006), Huang <i>et al.</i> (2007), Athanassiou <i>et al.</i> (2008c), Vayias <i>et al.</i> (2009b, 2010b)       |
| <i>Prostephanus truncatus</i>    | Adult             | Wheat                              | Athanassiou <i>et al.</i> (2008c)   |
| <i>Cryptolestes ferrugineus</i>  | Immature<br>Adult | Wheat, corn, sorghum, barley       | Daghli <i>et al.</i> (2003), Huang <i>et al.</i> (2007) and Vayias <i>et al.</i> (2010b)  |
| <i>Cryptolestes pusillus</i>     | Immature<br>Adult | Wheat                              | Subramanyam <i>et al.</i> (2002)  |
| <i>Sitophilus zeamais</i>        | Immature<br>Adult | Wheat, corn                        | Huang <i>et al.</i> (2007)  |
| <i>Sitophilus oryzae</i>         | Immature<br>Adult | Wheat, corn, sorghum, barley, rice | Subramanyam <i>et al.</i> (1999), Daghli and Wallbank (2002), Fang <i>et al.</i> (2002a), Nayak <i>et al.</i> (2005), Bonjour <i>et al.</i> (2006), Huang <i>et al.</i> (2007), Athanassiou <i>et al.</i> (2008c, 2009a), Vayias <i>et al.</i> (2009b, 2010b) |
| <i>Tribolium confusum</i>        | Immature<br>Adult | Wheat, barley, rice                | Huang <i>et al.</i> (2007) and Athanassiou <i>et al.</i> (2008c)  |
| <i>Tribolium castaneum</i>       | Immature<br>Adult | Wheat, corn, sorghum, sunflower    | Subramanyam <i>et al.</i> (1999), Fang <i>et al.</i> (2002a), Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Bonjour <i>et al.</i> (2006), Huang <i>et al.</i> (2007)   |
| <i>Oryzaephilus surinamensis</i> | Immature<br>Adult | Wheat, corn, sorghum               | Subramanyam <i>et al.</i> (1999), Fang <i>et al.</i> (2002a), Bonjour <i>et al.</i> (2006)  |
| <i>Lepinotus reticulatus</i>     | Immature<br>Adult | Wheat, corn, rice                  | Athanassiou <i>et al.</i> (2009a)   |
| <i>Liposcelis entomophila</i>    | Immature<br>Adult | Wheat, corn, rice                  | Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Nayak and Daghli (2007), Athanassiou <i>et al.</i> (2009a)   |
| <i>Liposcelis decolor</i>        | Immature<br>Adult | Wheat                              | Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Nayak and Daghli (2007), Huang <i>et al.</i> (2009)  |
| <i>Liposcelis bostrychophila</i> | Immature<br>Adult | Wheat, corn, rice                  | Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Nayak and Daghli (2007), Huang <i>et al.</i> (2009), Athanassiou <i>et al.</i> (2009a)   |
| <i>Liposcelis paeta</i>          | Immature<br>Adult | Wheat, corn, rice                  | Daghli <i>et al.</i> (2003), Nayak <i>et al.</i> (2005), Nayak and Daghli (2007), Athanassiou <i>et al.</i> (2009a)   |

Appendix table 2 Developmental periods and adult longevity of *X. flavipes* fed on different life stages of *C. pusillus* under laboratory condition at  $30\pm 0.5^{\circ}\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity

| Life stages of <i>C. pusillus</i> | Diet (g) | Mean Developmental periods (day) of nymphal instar |                 |                 |                 |                 | Total duration (day) of nymphal stages | Adult longevity (day) of <i>X. flavipes</i> |           | Total duration (day) |        |
|-----------------------------------|----------|--|-----------------|-----------------|-----------------|-----------------|--|---|-----------|----------------------|--------|
|                                   |          | 1 <sup>st</sup>                                    | 2 <sup>nd</sup> | 3 <sup>rd</sup> | 4 <sup>th</sup> | 5 <sup>th</sup> |  | Male  | Female    | Male                 | Female |
| Eggs                              | 2        | 3±0.58a  | 2±0.58a         | 3±0.58ab        | 3±0.58a         | 4±1.15a         | 15±2.00bcd                             | 8±1.15ab                                    | 20±1.15cd | 23                   | 35     |
| 1 <sup>st</sup> larvae            | 3        | 4±0.58a  | 3±0.58a         | 5±0.58a         | 4±0.58a         | 4±0.58a         | 20±0.00ab                              | 10±1.15ab                                   | 25±2.89bc | 30                   | 45     |
| 2 <sup>nd</sup> larvae            | 3        | 4±0.58a  | 3±0.58a         | 5±0.58a         | 5±0.58a         | 5±0.58a         | 22±0.58a                               | 12±1.15a                                    | 31±1.15ab | 39                   | 53     |
| 3 <sup>rd</sup> larvae            | 3        | 4±0.58a  | 3±0.58a         | 4±0.58ab        | 3±0.58a         | 4±0.58a         | 18±1.00abc                             | 11±1.15a                                    | 28±1.15a  | 29                   | 56     |
| 4 <sup>th</sup> larvae            | 3        | 3±0.58a  | 2±0.58a         | 3±0.58ab        | 3±0.58a         | 3±0.58a         | 14±1.15de                              | 9±0.58ab                                    | 26±0.58bc | 23                   | 40     |
| Pupae                             | 2        | 3±0.0a   | 2±0.0a          | 2±0.58b         | 3±0.58a         | 2±0.0a          | 12±1.15d                               | 6±0.58b                                     | 14±1.15d  | 18                   | 26     |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 3 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of 1<sup>st</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1671  | 1  | 1671 | 5.305  | 0.254   |
| Host      | 18420 | 5  | 3684 | 11.695 | 0.054   |
| Rep       | 4710  | 2  | 2355 | 7.476  | 0.157   |
| Host*Diet | 4521  | 3  | 1507 | 4.784  | 0.820   |
| Host*Rep  | 908   | 1  | 908  | 2.883  | 0.528   |
| Rep*Diet  | 1321  | 1  | 1321 | 4.194  | 0.362   |
| Error     | 1575  | 5  | 315  |        |         |
| Total     | 33126 | 18 |      |        |         |

Appendix table 4 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of 2<sup>nd</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1674  | 1  | 1674 | 7.440  | 0.245   |
| Host      | 18125 | 5  | 3625 | 16.111 | 0.054   |
| Rep       | 4980  | 2  | 2490 | 11.067 | 0.125   |
| Host*Diet | 4950  | 3  | 1650 | 7.333  | 0.820   |
| Diet*Rep  | 607   | 1  | 607  | 2.698  | 0.528   |
| Rep*Host  | 998   | 1  | 998  | 4.436  | 0.321   |
| Error     | 1125  | 5  | 225  |        |         |
| Total     | 32459 | 18 |      |        |         |

Appendix table 5 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of 3<sup>rd</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1765  | 1  | 1765 | 6.418  | 0.242   |
| Host      | 22590 | 5  | 4518 | 16.429 | 0.039   |
| Rep       | 4682  | 2  | 2341 | 8.513  | 0.142   |
| Host*Diet | 4503  | 3  | 1501 | 5.458  | 0.811   |
| Diet*Rep  | 936   | 1  | 936  | 3.404  | 0.415   |
| Rep*Host  | 1328  | 1  | 1328 | 4.829  | 0.326   |
| Error     | 1375  | 5  | 275  |        |         |
| Total     | 37179 | 18 |      |        |         |

Appendix table 6 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of 4<sup>th</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1682  | 1  | 1682 | 4.806  | 0.251   |
| Host      | 18080 | 5  | 3616 | 10.331 | 0.061   |
| Rep       | 4430  | 2  | 2215 | 6.329  | 0.125   |
| Host*Diet | 4509  | 3  | 1503 | 4.294  | 0.845   |
| Diet*Rep  | 925   | 1  | 925  | 2.643  | 0.625   |
| Rep*Host  | 1319  | 1  | 1319 | 3.469  | 0.148   |
| Error     | 1750  | 5  | 350  |        |         |
| Total     | 32695 | 18 |      |        |         |

Appendix table 7 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of 5<sup>th</sup> instar nymphs

| Source    | SS    | DF | MS   | F     | P value |
|-----------|-------|----|------|-------|---------|
| Diet      | 1648  | 1  | 1648 | 4.395 | 0.245   |
| Host      | 18095 | 5  | 3619 | 9.650 | 0.071   |
| Rep       | 4452  | 2  | 2226 | 5.936 | 0.136   |
| Host*Diet | 4410  | 3  | 1470 | 3.920 | 0.645   |
| Diet*Rep  | 939   | 1  | 939  | 2.504 | 0.528   |
| Rep*Host  | 1313  | 1  | 1313 | 3.501 | 0.138   |
| Error     | 1875  | 5  | 375  |       |         |
| Total     | 32732 | 18 |      |       |         |

Appendix table 8 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of adult male

| Source    | SS    | DF | MS   | F     | P value |
|-----------|-------|----|------|-------|---------|
| Diet      | 1653  | 1  | 1653 | 3.983 | 0.325   |
| Host      | 18095 | 5  | 3619 | 8.720 | 0.072   |
| Rep       | 4472  | 2  | 2236 | 5.388 | 0.145   |
| Host*Diet | 4284  | 3  | 1428 | 3.440 | 0.645   |
| Diet*Rep  | 932   | 1  | 932  | 2.246 | 0.529   |
| Rep*Host  | 1331  | 1  | 1331 | 3.207 | 0.134   |
| Error     | 2075  | 5  | 415  |       |         |
| Total     | 32842 | 18 |      |       |         |

Appendix table 9 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on longevity of adult female

| Source    | SS    | DF | MS   | F     | P value |
|-----------|-------|----|------|-------|---------|
| Diet      | 1621  | 1  | 1621 | 3.413 | 0.245   |
| Host      | 17630 | 5  | 3526 | 7.423 | 0.015   |
| Rep       | 4450  | 2  | 2225 | 4.684 | 0.132   |
| Host*Diet | 4593  | 3  | 1531 | 3.223 | 0.412   |
| Diet*Rep  | 945   | 1  | 945  | 1.989 | 0.558   |
| Rep*Host  | 1363  | 1  | 1363 | 2.869 | 0.164   |
| Error     | 2375  | 5  | 475  |       |         |
| Total     | 32977 | 18 |      |       |         |

Appendix table10 Developmental periods and adult longevity of *X. flavipes* fed on different life stages of *R. dominica* under laboratory condition at  $30\pm 0.5^{\circ}\text{C}$  temperature and  $70\pm 0.5\%$  relative humidity

| Life stages of <i>R. dominica</i> | Diet (g) | Mean Developmental periods (day) of nymphal instar |                 |                 |                 |                 | Total duration (day) of nymphsal stages | Adult longevity (day) of <i>X. flavipes</i> |           | Total duration (day) |        |
|-----------------------------------|----------|--|-----------------|-----------------|-----------------|-----------------|---|---|-----------|----------------------|--------|
|                                   |          | 1 <sup>st</sup>                                    | 2 <sup>nd</sup> | 3 <sup>rd</sup> | 4 <sup>th</sup> | 5 <sup>th</sup> |   | Male  | Female    | Male                 | Female |
| Eggs                              | 2        | 3±0.58a  | 3±0.58a         | 4±0.58a         | 4±0.58ab        | 4±0.58a         | 18±1.00ab                               | 10±2.31b                                    | 22±3.46bc | 28                   | 40     |
| 1 <sup>st</sup> larvae            | 3        | 4±0.58a  | 3±0.58a         | 4±0.58a         | 5±0.58a         | 4±0.58a         | 20±0.58a                                | 12±1.15ab                                   | 26±0.88ab | 32                   | 46     |
| 2 <sup>nd</sup> larvae            | 3        | 3±0.58a  | 2±0.58a         | 3±0.58a         | 4±0.58ab        | 4±0.58a         | 16±2.00abc                              | 18±0.58a                                    | 34±2.31a  | 34                   | 50     |
| 3 <sup>rd</sup> larvae            | 3        | 3±0.58a  | 2±0.58a         | 3±0.58a         | 3±0.58ab        | 3±0.58a         | 14±1.15bc                               | 10±1.33b                                    | 24±2.31bc | 24                   | 38     |
| 4 <sup>th</sup> larvae            | 3        | 3±0.58a  | 2±0.58a         | 2±0.58a         | 2±0.58b         | 3±0.58a         | 12±1.15c                                | 8±1.15b                                     | 20±1.15bc | 20                   | 32     |
| Pupae                             | 2        | 3±0.58a  | 2±0.58a         | 3±0.58a         | 2±0.58b         | 3±0.58a         | 13±0.58bc                               | 5±0.58b                                     | 15±1.15c  | 18                   | 28     |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 11 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of 1<sup>st</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1771  | 1  | 1771 | 6.440  | 0.254   |
| Host      | 18920 | 5  | 3784 | 13.760 | 0.054   |
| Rep       | 4910  | 2  | 2455 | 8.927  | 0.157   |
| Host*Diet | 4821  | 3  | 1607 | 5.844  | 0.820   |
| Diet*Rep  | 1008  | 1  | 1008 | 3.665  | 0.528   |
| Rep*Host  | 1421  | 1  | 1421 | 5.167  | 0.362   |
| Error     | 1375  | 5  | 275  |        |         |
| Total     | 34226 | 18 |      |        |         |

Appendix table 12 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of 2<sup>nd</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1774  | 1  | 1774 | 9.337  | 0.245   |
| Host      | 18625 | 5  | 3725 | 19.605 | 0.054   |
| Rep       | 4910  | 2  | 2455 | 12.921 | 0.125   |
| Host*Diet | 5121  | 3  | 1707 | 8.982  | 0.820   |
| Diet*Rep  | 998   | 1  | 998  | 5.253  | 0.528   |
| Rep*Host  | 1098  | 1  | 1098 | 5.779  | 0.321   |
| Error     | 950   | 5  | 190  |        |         |
| Total     | 33476 | 18 |      |        |         |

Appendix table 13 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of 3<sup>rd</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1765  | 1  | 1765 | 8.209  | 0.242   |
| Host      | 18590 | 5  | 3718 | 17.293 | 0.039   |
| Rep       | 4882  | 2  | 2441 | 11.353 | 0.142   |
| Host*Diet | 4953  | 3  | 1651 | 7.679  | 0.811   |
| Diet*Rep  | 1036  | 1  | 1036 | 4.819  | 0.415   |
| Rep*Host  | 1428  | 1  | 1428 | 6.642  | 0.326   |
| Error     | 1075  | 5  | 215  |        |         |
| Total     | 33729 | 18 |      |        |         |

Appendix table 14 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of 4<sup>th</sup> instar nymphs

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1782  | 1  | 1782 | 5.940  | 0.251   |
| Host      | 18580 | 5  | 3716 | 12.387 | 0.061   |
| Rep       | 4630  | 2  | 2315 | 7.717  | 0.125   |
| Host*Diet | 4779  | 3  | 1593 | 0.310  | 0.845   |
| Diet*Rep  | 1025  | 1  | 1025 | 3.417  | 0.625   |
| Rep*Host  | 1419  | 1  | 1419 | 4.730  | 0.148   |
| Error     | 1500  | 5  | 300  |        |         |
| Total     | 33715 | 18 |      |        |         |

Appendix table 15 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of 5<sup>th</sup> instar nymphs

| Source    | SS    | DF | MS   | F     | P value |
|-----------|-------|----|------|-------|---------|
| Diet      | 1748  | 1  | 1748 | 4.540 | 0.245   |
| Host      | 19095 | 5  | 3819 | 9.919 | 0.071   |
| Rep       | 4652  | 2  | 2326 | 6.042 | 0.136   |
| Host*Diet | 4536  | 3  | 1512 | 3.927 | 0.645   |
| Diet*Rep  | 1039  | 1  | 1039 | 2.699 | 0.528   |
| Rep*Host  | 1413  | 1  | 1413 | 3.670 | 0.138   |
| Error     | 1925  | 5  | 385  |       |         |
| Total     | 34408 | 18 |      |       |         |

Appendix table 16 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of adult male

| Source    | SS    | DF | MS   | F      | P value |
|-----------|-------|----|------|--------|---------|
| Diet      | 1753  | 1  | 1753 | 5.009  | 0.325   |
| Host      | 19095 | 5  | 3819 | 10.911 | 0.072   |
| Rep       | 4872  | 2  | 2436 | 6.960  | 0.145   |
| Host*Diet | 4884  | 3  | 1628 | 4.651  | 0.645   |
| Diet*Rep  | 998   | 1  | 998  | 2.851  | 0.529   |
| Rep*Host  | 1531  | 1  | 1531 | 4.374  | 0.134   |
| Error     | 1750  | 5  | 350  |        |         |
| Total     | 34883 | 18 |      |        |         |

Appendix table 17 Factorial ANOVA showing the effects of different life stages of *R. dominica* on longevity of adult female

| Source    | SS    | DF | MS   | F     | P value |
|-----------|-------|----|------|-------|---------|
| Source    | SS    | DF | MS   | F     | P value |
| Diet      | 1721  | 1  | 1721 | 4.049 | 0.245   |
| Host      | 18630 | 5  | 3726 | 8.767 | 0.015   |
| Rep       | 4850  | 2  | 2425 | 5.706 | 0.132   |
| Host*Diet | 5193  | 3  | 1731 | 4.073 | 0.412   |
| Diet*Rep  | 1045  | 1  | 1045 | 2.459 | 0.558   |
| Rep*Host  | 1563  | 1  | 1563 | 3.678 | 0.164   |
| Error     | 2125  | 5  | 425  |       |         |

Appendix table 18 Average (%) consumption rate by different life stages of *X. flavipes* per day on different life stages of *C. pusillus* under laboratory condition

| Life stages of <i>C. pusillus</i> | Diet (g) | Average (%) consumption rate of <i>X. flavipes</i> |                 |                 |                 |                 |              |             |
|-----------------------------------|----------|--|-----------------|-----------------|-----------------|-----------------|--------------|-------------|
|                                   |          | Nymphs   |                 |                 |                 |                 | Adults       |             |
|                                   |          | 1 <sup>st</sup>                                    | 2 <sup>nd</sup> | 3 <sup>rd</sup> | 4 <sup>th</sup> | 5 <sup>th</sup> | Male         | Female      |
| Eggs                              | 2        | 7.33±0.33a   | 8.33±0.33a      | 10.33±0.33a     | 12.67±1.20a     | 14.33±0.33a     | 16.33±0.88a  | 20.67±0.33a |
| 1 <sup>st</sup> larvae            | 3        | 6.33±0.33a   | 7.67±0.33a      | 8.67±0.33a      | 9.33±0.33b      | 11.67±0.33b     | 14.33±0.33ab | 16.33±0.33b |
| 2 <sup>nd</sup> larvae            | 3        | 3.33±0.33b   | 4.33±0.33b      | 5.67±0.33b      | 6.33±0.33c      | 8.67±0.33c      | 12.33±0.33b  | 14.33±0.33c |
| 3 <sup>rd</sup> larvae            | 3        | 2.33±0.33bc  | 2.67±0.33c      | 4.33±0.33b      | 4.67±0.33cd     | 6.67±0.33d      | 9.67±0.33c   | 11.33±0.33d |
| 4 <sup>th</sup> larvae            | 3        | 1.33±0.33c   | 1.67±0.33c      | 2.33±0.33c      | 3.67±0.33cd     | 5.33±0.33d      | 8.67±0.33c   | 9.33±0.33e  |
| Pupae                             | 2        | 1.33±0.33c   | 1.67±0.33c      | 2.00±0.58c      | 2.33±0.33d      | 2.67±0.33e      | 4.33±0.33d   | 5.67±0.33f  |

Note: Means with same letter do not significantly differed from each other Tukey's Test, P<0.001



Appendix table 19 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of 1<sup>st</sup> instar nymphs

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 70982    | 1  | 70982   | 4.693   | 0.258   |
| Host      | 15281800 | 5  | 3056360 | 202.073 | 0.001   |
| Rep       | 26152    | 2  | 13076   | 0.865   | 0.765   |
| Host*Diet | 2033490  | 3  | 677830  | 44.815  | 0.425   |
| Diet*Rep  | 43775    | 1  | 43775   | 2.894   | 0.502   |
| Rep*Host  | 28569    | 1  | 28569   | 1.889   | 0.762   |
| Error     | 75625    | 5  | 15125   |         |         |
| Total     | 17560393 | 18 |         |         |         |

Appendix table 20 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of 2<sup>nd</sup> instar nymphs

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 70859    | 1  | 70859   | 4.973   | 0.248   |
| Host      | 15283175 | 5  | 3056635 | 214.500 | 0.003   |
| Rep       | 26030    | 2  | 13015   | 0.913   | 0.745   |
| Host*Diet | 2032290  | 3  | 677430  | 47.534  | 0.158   |
| Diet*Rep  | 43625    | 1  | 43625   | 3.0614  | 0.425   |
| Rep*Host  | 28236    | 1  | 28236   | 1.981   | 0.623   |
| Error     | 71250    | 5  | 14250   |         |         |
| Total     | 17555465 | 18 |         |         |         |

Appendix table 21 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of 3<sup>rd</sup> instar nymphs

| Source    | SS      | DF | MS      | F       | P value |
|-----------|---------|----|---------|---------|---------|
| Diet      | 70458   | 1  | 70458   | 3.866   | 0.246   |
| Host      | 1581290 | 5  | 3056258 | 167.696 | 0.004   |
| Rep       | 26724   | 2  | 13362   | 0.733   | 0.369   |
| Host*Diet | 2014440 | 3  | 671480  | 36.844  | 0.145   |
| Diet*Rep  | 43425   | 1  | 43425   | 2.383   | 0.369   |
| Rep*Host  | 28632   | 1  | 28632   | 1.571   | 0.758   |
| Error     | 91125   | 5  | 18225   |         |         |
| Total     | 3856094 | 18 |         |         |         |

Appendix table 22 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of 4<sup>th</sup> instar nymphs

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 70441    | 1  | 70441   | 4.116   | 0.252   |
| Host      | 15281620 | 5  | 3056324 | 178.576 | 0.005   |
| Rep       | 26916    | 2  | 13458   | 0.786   | 0.335   |
| Host*Diet | 2017080  | 3  | 672360  | 39.285  | 0.248   |
| Diet*Rep  | 43145    | 1  | 43145   | 2.521   | 0.365   |
| Rep*Host  | 28635    | 1  | 28635   | 1.673   | 0.762   |
| Error     | 85575    | 5  | 17115   |         |         |
| Total     | 17553412 | 18 |         |         |         |

Appendix table 23 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of 5<sup>th</sup> instar nymphs

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 70448    | 1  | 70448   | 4.369   | 0.215   |
| Host      | 15281810 | 5  | 3056362 | 189.542 | 0.002   |
| Rep       | 26938    | 2  | 13469   | 0.835   | 0.333   |
| Host*Diet | 2017410  | 3  | 672470  | 41.704  | 0.263   |
| Diet*Rep  | 43126    | 1  | 43126   | 2.674   | 0.275   |
| Rep*Host  | 28621    | 1  | 28621   | 1.775   | 0.632   |
| Error     | 80625    | 5  | 16125   |         |         |
| Total     | 17548978 | 18 |         |         |         |

Appendix table 24 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of adult male

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 70451    | 1  | 70451   | 7.473   | 0.248   |
| Host      | 15283195 | 5  | 3056639 | 194.072 | 0.021   |
| Rep       | 26884    | 2  | 13442   | 0.853   | 0.312   |
| Host*Diet | 2014680  | 3  | 671560  | 42.639  | 0.148   |
| Diet*Rep  | 43121    | 1  | 43121   | 2.738   | 0.639   |
| Rep*Host  | 28632    | 1  | 28632   | 1.818   | 0.425   |
| Error     | 78750    | 5  | 15750   |         |         |
| Total     | 17545713 | 18 |         |         |         |

Appendix table 25 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on consumption rate of adult female

| Source    | SS       | DF | MS      | F       | P value |
|-----------|----------|----|---------|---------|---------|
| Diet      | 60362    | 1  | 60362   | 3.939   | 0.251   |
| Host      | 15282105 | 5  | 3056421 | 199.440 | 0.002   |
| Rep       | 30882    | 2  | 15441   | 1.008   | 0.452   |
| Host*Diet | 1864740  | 3  | 621580  | 40.560  | 0.458   |
| Diet*Rep  | 40136    | 1  | 40136   | 2.629   | 0.741   |
| Rep*Host  | 28131    | 1  | 28131   | 1.836   | 0.458   |
| Error     | 76625    | 5  | 15325   |         |         |
| Total     | 17381981 | 18 |         |         |         |

Appendix table 26 Average (%) consumption rate by different life stages of *X. flavipes* per day on different life stages of *R. dominica* under laboratory condition

| Life stages of <i>R. dominica</i> | Diet (g) | Average (%) consumption rate of <i>X. flavipes</i> |                 |                 |                 |                 |             |              |
|-----------------------------------|----------|--|-----------------|-----------------|-----------------|-----------------|-------------|--------------|
|                                   |          | Nymphs   |                 |                 |                 |                 | Adults      |              |
|                                   |          | 1 <sup>st</sup>                                    | 2 <sup>nd</sup> | 3 <sup>rd</sup> | 4 <sup>th</sup> | 5 <sup>th</sup> | Male        | Female       |
| Eggs                              | 2        | 8.00±0.58a   | 10.67±0.67a     | 14.33±0.88a     | 16.67±1.20a     | 19.33±0.88a     | 21.33±0.88a | 24.67±1.20a  |
| 1 <sup>st</sup> larvae            | 3        | 3.33±0.88b   | 4.67±1.20b      | 5.00±0.58b      | 6.33±0.88b      | 8.67±1.20b      | 10.00±1.15b | 14.00±1.15b  |
| 2 <sup>nd</sup> larvae            | 3        | 2.33±0.88b   | 3.67±1.20b      | 4.33±0.88b      | 5.67±1.20b      | 7.33±0.88b      | 9.33±0.88b  | 12.33±0.88bc |
| 3 <sup>rd</sup> larvae            | 3        | 2.00±0.58b   | 3.33±0.88b      | 4.00±0.58b      | 5.00±0.58b      | 6.67±1.20bc     | 8.67±1.20b  | 11.33±0.88bc |
| 4 <sup>th</sup> larvae            | 3        | 1.33±0.33b   | 2.33±0.88b      | 2.67±1.20b      | 3.33±1.45b      | 4.33±0.88bc     | 6.33±0.88c  | 8.33±0.88cd  |
| Pupae                             | 2        | 1.00±0.00b   | 1.33±0.33b      | 1.67±0.33b      | 2.00±0.58b      | 2.33±0.88c      | 3.00±0.58c  | 4.00±0.58d   |

Note: Means with same letter do not significantly differed from each other Tukey's Test, P<0.001

Appendix table 27 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of 1<sup>st</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40093   | 1  | 40093  | 5.627  | 0.480   |
| Host      | 2071065 | 5  | 414213 | 58.135 | 0.015   |
| Rep       | 86706   | 2  | 43353  | 6.085  | 0.001   |
| Host*Diet | 154470  | 3  | 51490  | 7.227  | 0.999   |
| Diet*Rep  | 13449   | 1  | 13449  | 1.888  | 0.067   |
| Rep*Host  | 41535   | 1  | 41535  | 5.829  | 0.003   |
| Error     | 35625   | 5  | 7125   |        |         |
| Total     | 2442943 | 18 |        |        |         |

Appendix table 28 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of 2<sup>nd</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40091   | 1  | 40091  | 6.440  | 0.481   |
| Host      | 2071075 | 5  | 414215 | 66.540 | 0.012   |
| Rep       | 126738  | 2  | 63369  | 10.170 | 0.001   |
| Host*Diet | 154350  | 3  | 51450  | 8.265  | 0.985   |
| Diet*Rep  | 13445   | 1  | 13445  | 2.150  | 0.062   |
| Rep*Host  | 41525   | 1  | 41525  | 6.670  | 0.001   |
| Error     | 31125   | 5  | 6225   |        |         |
| Total     | 2478349 | 18 |        |        |         |

Appendix table 29 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of 3<sup>rd</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40085   | 1  | 40085  | 4.859  | 0.382   |
| Host      | 2070625 | 5  | 414125 | 50.197 | 0.011   |
| Rep       | 127250  | 2  | 63625  | 7.712  | 0.005   |
| Host*Diet | 153750  | 3  | 51250  | 6.212  | 0.915   |
| Diet*Rep  | 13351   | 1  | 13351  | 1.618  | 0.025   |
| Rep*Host  | 41245   | 1  | 41245  | 4.999  | 0.006   |
| Error     | 41250   | 5  | 8250   |        |         |
| Total     | 2487556 | 18 |        |        |         |

Appendix table 30 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of 4<sup>th</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40152   | 1  | 40152  | 3.287  | 0.582   |
| Host      | 2070710 | 5  | 414142 | 33.904 | 0.024   |
| Rep       | 127272  | 2  | 63636  | 5.210  | 0.002   |
| Host*Diet | 153150  | 3  | 51050  | 4.179  | 0.812   |
| Diet*Rep  | 13314   | 1  | 13314  | 1.080  | 0.022   |
| Rep*Host  | 41225   | 1  | 41225  | 3.375  | 0.012   |
| Error     | 61075   | 5  | 12215  |        |         |
| Total     | 2506898 | 18 |        |        |         |

Appendix table 31 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of 5<sup>th</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40521   | 1  | 40521  | 2.952  | 0.125   |
| Host      | 2070560 | 5  | 414112 | 30.172 | 0.032   |
| Rep       | 127348  | 2  | 63674  | 4.639  | 0.005   |
| Host*Diet | 153300  | 3  | 51100  | 3.723  | 0.425   |
| Diet*Rep  | 13145   | 1  | 13145  | 0.958  | 0.021   |
| Rep*Host  | 41215   | 1  | 41215  | 3.002  | 0.041   |
| Error     | 68625   | 5  | 13725  |        |         |
| Total     | 2514714 | 18 |        |        |         |

Appendix table 32 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of adult male

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40314   | 1  | 40314  | 8.860  | 0.110   |
| Host      | 2072125 | 5  | 414425 | 91.082 | 0.032   |
| Rep       | 26204   | 2  | 13102  | 2.880  | 0.005   |
| Host*Diet | 153360  | 3  | 51120  | 11.235 | 0.125   |
| Diet*Rep  | 13143   | 1  | 13143  | 2.888  | 0.021   |
| Rep*Host  | 41269   | 1  | 41269  | 9.070  | 0.041   |
| Error     | 22750   | 5  | 4550   |        |         |
| Total     | 2369165 | 18 |        |        |         |

Appendix table 33 Factorial ANOVA showing the effects of different life stages of *R. dominica* on consumption rate of adult female

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 40316   | 1  | 40316  | 7.642  | 0.120   |
| Host      | 2072375 | 5  | 414475 | 78.573 | 0.014   |
| Rep       | 26202   | 2  | 13101  | 2.484  | 0.006   |
| Host*Diet | 153450  | 3  | 51150  | 9.697  | 0.131   |
| Diet*Rep  | 13140   | 1  | 13140  | 2.491  | 0.041   |
| Rep*Host  | 41251   | 1  | 41251  | 7.820  | 0.012   |
| Error     | 26375   | 5  | 5275   |        |         |
| Total     | 2373109 | 18 |        |        |         |

Appendix table 34 Average percent ( $\pm$ SE) no. of survivability of different life stages of *X. flavipes* on different life stages of *C. pusillus* under laboratory condition

| Life stages of <i>C. pusillus</i> | Diet (gm) | Average (%) no. of survivability of <i>X. flavipes</i> |                    |                   |                  |                  |                  |                  |
|-----------------------------------|-----------|--|--------------------|-------------------|------------------|------------------|------------------|------------------|
|                                   |           | Nymphs   |                    |                   |                  |                  | Adults           |                  |
|                                   |           | 1 <sup>st</sup>  | 2 <sup>nd</sup>    | 3 <sup>rd</sup>   | 4 <sup>th</sup>  | 5 <sup>th</sup>  | Male             | Female           |
| Eggs                              | 2         | 9.00 $\pm$ 0.58a                                       | 8.33 $\pm$ 0.33abc | 7.33 $\pm$ 0.33ab | 6.33 $\pm$ 0.33a | 5.33 $\pm$ 0.33a | 3.67 $\pm$ 0.67a | 6.33 $\pm$ 0.67a |
| 1 <sup>st</sup> larvae            | 3         | 10.00 $\pm$ 0.00a                                      | 9.67 $\pm$ 0.33ab  | 8.00 $\pm$ 1.53ab | 8.00 $\pm$ 1.53a | 7.00 $\pm$ 1.15a | 4.67 $\pm$ 0.88a | 5.33 $\pm$ 0.88a |
| 2 <sup>nd</sup> larvae            | 3         | 10.00 $\pm$ 0.00a                                      | 10.00 $\pm$ 0.00a  | 10.00 $\pm$ 0.00a | 8.67 $\pm$ 0.33a | 6.67 $\pm$ 0.88a | 3.33 $\pm$ 0.88a | 6.67 $\pm$ 0.88a |
| 3 <sup>rd</sup> larvae            | 3         | 9.67 $\pm$ 0.58a                                       | 6.67 $\pm$ 1.20c   | 5.00 $\pm$ 1.15b  | 5.00 $\pm$ 1.15a | 4.67 $\pm$ 1.45a | 3.67 $\pm$ 1.45a | 5.67 $\pm$ 0.88a |
| 4 <sup>th</sup> larvae            | 3         | 8.33 $\pm$ 0.58a                                       | 6.00 $\pm$ 0.58c   | 5.67 $\pm$ 0.33b  | 5.00 $\pm$ 0.58a | 4.67 $\pm$ 0.33a | 2.33 $\pm$ 0.33a | 7.67 $\pm$ 0.33a |
| Pupae                             | 2         | 8.00 $\pm$ 0.58a                                       | 7.00 $\pm$ 0.58bc  | 6.33 $\pm$ 0.33ab | 5.33 $\pm$ 0.67a | 4.33 $\pm$ 0.33a | 2.67 $\pm$ 0.33a | 7.33 $\pm$ 0.33a |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 35 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of 1<sup>st</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 299.39  | 1  | 299.39 | 14.022 | 0.000   |
| Host      | 3212.20 | 5  | 642.44 | 30.090 | 0.000   |
| Rep       | 463.50  | 2  | 231.75 | 10.85  | 0.922   |
| Host*Diet | 268.38  | 3  | 89.46  | 4.190  | 0.005   |
| Diet*Rep  | 70.64   | 1  | 70.64  | 3.308  | 0.801   |
| Rep*Host  | 98.62   | 1  | 98.61  | 4.618  | 0.330   |
| Error     | 106.75  | 5  | 21.35  |        |         |
| Total     | 4519.48 | 18 |        |        |         |

Appendix table 36 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of 2<sup>nd</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 297.45  | 1  | 297.45 | 14.524 | 0.005   |
| Host      | 3711.55 | 5  | 742.31 | 36.245 | 0.001   |
| Rep       | 622.90  | 2  | 311.45 | 15.208 | 0.922   |
| Host*Diet | 298.74  | 3  | 99.58  | 4.862  | 0.005   |
| Diet*Rep  | 60.21   | 1  | 60.21  | 2.940  | 0.801   |
| Rep*Host  | 86.32   | 1  | 86.32  | 4.215  | 0.330   |
| Error     | 102.40  | 5  | 20.48  |        |         |
| Total     | 5179.57 | 18 |        |        |         |

Appendix table 37 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of 3<sup>rd</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 399.15  | 1  | 399.15 | 21.992 | 0.005   |
| Host      | 3491.25 | 5  | 698.25 | 38.471 | 0.005   |
| Rep       | 462.30  | 2  | 231.15 | 12.736 | 0.985   |
| Host*Diet | 264.69  | 3  | 88.23  | 4.861  | 0.005   |
| Diet*Rep  | 65.02   | 1  | 65.02  | 3.582  | 0.785   |
| Rep*Host  | 96.32   | 1  | 96.32  | 5.307  | 0.521   |
| Error     | 90.75   | 5  | 18.15  |        |         |
| Total     | 4869.48 | 18 |        |        |         |

Appendix table 38 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of 4<sup>th</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 345.31  | 1  | 345.31 | 16.779 | 0.005   |
| Host      | 3710.75 | 5  | 742.15 | 36.061 | 0.005   |
| Rep       | 223.16  | 2  | 111.58 | 5.422  | 0.995   |
| Host*Diet | 240.54  | 3  | 80.18  | 3.896  | 0.852   |
| Diet*Rep  | 75.42   | 1  | 75.42  | 3.665  | 0.925   |
| Rep*Host  | 95.10   | 1  | 95.10  | 4.620  | 0.936   |
| Error     | 102.90  | 5  | 20.58  |        |         |
| Total     | 4793.18 | 18 |        |        |         |

Appendix table 39 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of 5<sup>th</sup> instar nymphs

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 295.58  | 1  | 295.58 | 11.614 | 0.006   |
| Host      | 3445.60 | 5  | 689.12 | 27.077 | 0.005   |
| Rep       | 181.16  | 2  | 90.58  | 3.559  | 0.725   |
| Host*Diet | 267.54  | 3  | 89.18  | 3.504  | 0.852   |
| Diet*Rep  | 55.42   | 1  | 55.42  | 2.178  | 0.925   |
| Rep*Host  | 90.10   | 1  | 90.10  | 3.540  | 0.859   |
| Error     | 127.25  | 5  | 25.45  |        |         |
| Total     | 4462.65 | 18 |        |        |         |

Appendix table 40 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of adult male

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 298.12  | 1  | 298.12 | 13.399 | 0.009   |
| Host      | 3126.80 | 5  | 625.36 | 28.106 | 0.005   |
| Rep       | 186.50  | 2  | 93.25  | 4.191  | 0.814   |
| Host*Diet | 256.86  | 3  | 85.62  | 3.848  | 0.485   |
| Diet*Rep  | 40.43   | 1  | 40.43  | 1.817  | 0.425   |
| Rep*Host  | 92.56   | 1  | 92.56  | 4.160  | 0.693   |
| Error     | 111.25  | 5  | 22.25  |        |         |
| Total     | 4112.52 | 18 |        |        |         |

Appendix table 41 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on no. of survivability of adult female

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 345.42  | 1  | 345.42 | 29.243 | 0.008   |
| Host      | 2628.10 | 5  | 525.62 | 29.282 | 0.006   |
| Rep       | 199.24  | 2  | 99.62  | 5.545  | 0.858   |
| Host*Diet | 585.45  | 3  | 195.15 | 10.872 | 0.425   |
| Diet*Rep  | 90.42   | 1  | 90.42  | 5.037  | 0.431   |
| Rep*Host  | 102.28  | 1  | 102.28 | 5.698  | 0.574   |
| Error     | 89.75   | 5  | 17.95  |        |         |
| Total     | 4040.66 | 18 |        |        |         |

Appendix table 42 Average percent ( $\pm$ SE) no. of survivability of different life stages of *X. flavipes* on different life stages of *R. dominica* under laboratory condition

| Life stages of <i>R. dominica</i> | Diet (gm) | Average (%) survivability of <i>X. flavipes</i> |                   |                   |                   |                   |                  |                  |
|-----------------------------------|-----------|---|-------------------|-------------------|-------------------|-------------------|------------------|------------------|
|                                   |           | Nymphs  |                   |                   |                   |                   | Adults           |                  |
|                                   |           | 1 <sup>st</sup>                                 | 2 <sup>nd</sup>   | 3 <sup>rd</sup>   | 4 <sup>th</sup>   | 5 <sup>th</sup>   | Male             | Female           |
| Eggs                              | 2         | 9.00 $\pm$ 0.58a                                | 8.00 $\pm$ 0.58ab | 7.33 $\pm$ 0.67ab | 6.00 $\pm$ 0.00a  | 5.67 $\pm$ 0.33a  | 4.33 $\pm$ 1.20a | 5.67 $\pm$ 1.20a |
| 1 <sup>st</sup> larvae            | 3         | 9.33 $\pm$ 0.33a                                | 8.67 $\pm$ 0.33a  | 8.33 $\pm$ 0.33a  | 7.00 $\pm$ 0.58a  | 6.00 $\pm$ 0.58a  | 3.00 $\pm$ 0.58a | 7.00 $\pm$ 0.58a |
| 2 <sup>nd</sup> larvae            | 3         | 8.00 $\pm$ 0.58ab                               | 7.00 $\pm$ 0.00b  | 6.67 $\pm$ 0.33ab | 6.33 $\pm$ 0.33a  | 5.67 $\pm$ 0.33a  | 2.67 $\pm$ 0.33a | 6.33 $\pm$ 0.88a |
| 3 <sup>rd</sup> larvae            | 3         | 8.33 $\pm$ 0.33ab                               | 7.67 $\pm$ 0.33ab | 6.33 $\pm$ 0.33b  | 6.00 $\pm$ 0.58a  | 5.00 $\pm$ 0.00a  | 3.33 $\pm$ 0.33a | 6.67 $\pm$ 0.33a |
| 4 <sup>th</sup> larvae            | 3         | 7.33 $\pm$ 0.33ab                               | 7.00 $\pm$ 0.00b  | 5.67 $\pm$ 0.33bc | 5.00 $\pm$ 0.58ab | 4.33 $\pm$ 0.33ab | 3.00 $\pm$ 0.58a | 6.00 $\pm$ 0.00a |
| Pupae                             | 2         | 6.33 $\pm$ 0.33b                                | 5.33 $\pm$ 0.33c  | 4.33 $\pm$ 0.33c  | 3.67 $\pm$ 0.33b  | 2.67 $\pm$ 0.33b  | 2.00 $\pm$ 0.00a | 5.00 $\pm$ 1.00a |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 43 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of 1<sup>st</sup> instar nymphs

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 623.10   | 1  | 623.10  | 4.965  | 0.016   |
| Host      | 23472.00 | 5  | 4694.40 | 37.406 | 0.000   |
| Rep       | 1257.80  | 2  | 628.90  | 5.011  | 0.025   |
| Host*Diet | 279.30   | 3  | 93.10   | 0.741  | 0.720   |
| Diet*Rep  | 222.50   | 1  | 222.50  | 1.773  | 0.199   |
| Rep*Host  | 154.60   | 1  | 154.60  | 1.232  | 0.387   |
| Error     | 627.50   | 5  | 125.50  |        |         |
| Total     | 26636.80 | 18 |         |        |         |

Appendix table 44 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of 2<sup>nd</sup> instar nymphs

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 623.25   | 1  | 623.25  | 4.888  | 0.015   |
| Host      | 23472.10 | 5  | 4694.42 | 36.819 | 0.001   |
| Rep       | 1257.92  | 2  | 628.96  | 4.933  | 0.022   |
| Host*Diet | 279.30   | 3  | 93.10   | 0.730  | 0.625   |
| Diet*Rep  | 222.50   | 1  | 222.50  | 1.745  | 0.215   |
| Rep*Host  | 154.60   | 1  | 154.60  | 1.213  | 0.147   |
| Error     | 637.50   | 5  | 127.50  |        |         |
| Total     | 26647.27 | 18 |         |        |         |

Appendix table 45 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of 3<sup>rd</sup> instar nymphs

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 623.35   | 1  | 623.35  | 4.788  | 0.016   |
| Host      | 23474.25 | 5  | 4694.85 | 36.064 | 0.001   |
| Rep       | 1256.50  | 2  | 628.25  | 4.826  | 0.022   |
| Host*Diet | 2410.56  | 3  | 803.52  | 6.172  | 0.625   |
| Diet*Rep  | 302.48   | 1  | 302.48  | 2.323  | 0.214   |
| Rep*Host  | 154.62   | 1  | 154.62  | 1.188  | 0.147   |
| Error     | 650.90   | 5  | 130.18  |        |         |
| Total     | 28872.66 | 18 |         |        |         |

Appendix table 46 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of 4<sup>th</sup> instar nymphs

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 723.40   | 1  | 723.40  | 5.466  | 0.018   |
| Host      | 27974.25 | 5  | 5594.85 | 42.273 | 0.001   |
| Rep       | 1200.50  | 2  | 600.25  | 4.535  | 0.022   |
| Host*Diet | 2680.56  | 3  | 893.52  | 6.751  | 0.622   |
| Diet*Rep  | 322.48   | 1  | 322.48  | 2.437  | 0.214   |
| Rep*Host  | 254.63   | 1  | 254.63  | 1.923  | 0.149   |
| Error     | 661.75   | 5  |         |        |         |
| Total     | 33817.57 | 18 |         |        |         |



Appendix table 47 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of 5<sup>th</sup> instar nymphs

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 822.38   | 1  | 822.38  | 5.843  | 0.016   |
| Host      | 33471.95 | 5  | 6694.39 | 47.562 | 0.002   |
| Rep       | 1224.48  | 2  | 612.24  | 4.350  | 0.021   |
| Host*Diet | 2380.26  | 3  | 793.42  | 5.637  | 0.582   |
| Diet*Rep  | 292.82   | 1  | 292.82  | 2.080  | 0.245   |
| Rep*Host  | 354.25   | 1  | 354.25  | 2.517  | 0.485   |
| Error     | 703.75   | 5  | 140.75  |        |         |
| Total     | 39249.89 | 18 |         |        |         |

Appendix table 48 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of adult male

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 712.85   | 1  | 712.85  | 5.186  | 0.020   |
| Host      | 33473.10 | 5  | 6694.62 | 38.595 | 0.002   |
| Rep       | 1256.84  | 2  | 628.42  | 4.572  | 0.022   |
| Host*Diet | 2679.54  | 3  | 893.18  | 6.497  | 0.592   |
| Diet*Rep  | 272.36   | 1  | 272.36  | 1.981  | 0.250   |
| Rep*Host  | 254.47   | 1  | 254.47  | 1.851  | 0.471   |
| Error     | 687.30   | 5  | 137.46  |        |         |
| Total     | 39336.46 | 18 |         |        |         |

Appendix table 49 Factorial ANOVA showing the effects of different life stages of *R. dominica* on no. of survivability of adult female

| Source    | SS       | DF | MS      | F      | P value |
|-----------|----------|----|---------|--------|---------|
| Diet      | 622.47   | 1  | 622.47  | 4.585  | 0.021   |
| Host      | 28471.60 | 5  | 5694.32 | 41.947 | 0.002   |
| Rep       | 1396.84  | 2  | 698.42  | 5.145  | 0.022   |
| Host*Diet | 2380.56  | 3  | 793.52  | 5.845  | 0.592   |
| Diet*Rep  | 252.14   | 1  | 252.14  | 1.857  | 0.250   |
| Rep*Host  | 454.28   | 1  | 454.28  | 3.346  | 0.471   |
| Error     | 678.75   | 5  | 135.75  |        |         |
| Total     | 34256.64 | 18 |         |        |         |

Appendix table 50 Average ( $\pm$ SE) adult size (mm in length) of *X. flavipes* on different life stages of *C. pusillus* under laboratory condition.

| Adult size (mm in length) of <i>X. flavipes</i> | Different life stages of <i>C. pusillus</i> |                   |                   |                  |                    |                   |
|---|---|-------------------|-------------------|------------------|--------------------|-------------------|
|   | Eggs  | 1 <sup>st</sup>   | 2 <sup>nd</sup>   | 3 <sup>rd</sup>  | 4 <sup>th</sup>    | Pupae             |
| Male  | 1.50 $\pm$ 0.06c                            | 1.60 $\pm$ 0.03bc | 1.70 $\pm$ 0.03ab | 1.80 $\pm$ 0.01a | 1.65 $\pm$ 0.03abc | 1.55 $\pm$ 0.04bc |
| Female  | 1.70 $\pm$ 0.06c                            | 1.90 $\pm$ 0.03b  | 2.00 $\pm$ 0.03ab | 2.10 $\pm$ 0.01a | 1.95 $\pm$ 0.03ab  | 1.85 $\pm$ 0.04bc |

Note: Means with same letter do not significantly differed from each other Tukey's Test, P<0.001

Appendix table 51 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on size of adult male

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 219.74  | 1  | 219.74 | 4.867  | 0.282   |
| Host      | 3250.95 | 5  | 650.19 | 14.401 | 0.002   |
| Rep       | 896.30  | 2  | 448.15 | 9.926  | 0.017   |
| Host*Diet | 265.44  | 3  | 88.48  | 1.960  | 0.989   |
| Diet*Rep  | 75.87   | 1  | 75.87  | 1.680  | 0.978   |
| Rep*Host  | 470.98  | 1  | 470.98 | 10.351 | 0.002   |
| Error     | 225.75  | 5  | 45.15  |        |         |
| Total     | 5405.03 | 18 |        |        |         |

Appendix table 52 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on size of adult female

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 199.48  | 1  | 199.48 | 5.659  | 0.251   |
| Host      | 3241.10 | 5  | 648.22 | 18.389 | 0.003   |
| Rep       | 850.30  | 2  | 425.15 | 12.061 | 0.021   |
| Host*Diet | 298.44  | 3  | 99.48  | 2.822  | 0.852   |
| Diet*Rep  | 96.69   | 1  | 96.69  | 2.743  | 0.852   |
| Rep*Host  | 470.82  | 1  | 470.82 | 13.357 | 0.003   |
| Error     | 176.25  | 5  | 35.25  |        |         |
| Total     | 5333.08 | 18 |        |        |         |

Appendix table 53 Average ( $\pm$ SE) adult size (mm in length) of *X. flavipes* male and female on different life stages of *R. dominica* under laboratory condition

| Adult size (mm in length) of <i>X. flavipes</i> | Different life stages of <i>R. dominica</i> |                  |                   |                    |                   |                  |
|---|---|------------------|-------------------|--------------------|-------------------|------------------|
|   | Eggs  | 1 <sup>st</sup>  | 2 <sup>nd</sup>   | 3 <sup>rd</sup>    | 4 <sup>th</sup>   | Pupae            |
| Male  | 1.75 $\pm$ 0.03ab                           | 1.80 $\pm$ 0.02a | 1.85 $\pm$ 0.01a  | 1.81 $\pm$ 0.03a   | 1.76 $\pm$ 0.03ab | 1.65 $\pm$ 0.04b |
| Female  | 2.00 $\pm$ 0.03bcd                          | 2.20 $\pm$ 0.06a | 2.15 $\pm$ 0.02ab | 2.10 $\pm$ 0.01abc | 1.98 $\pm$ 0.05cd | 1.90 $\pm$ 0.03d |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 54 Factorial ANOVA showing the effects of different life stages of *R. dominica* on size of adult male

| Source    | SS      | DF | MS     | F     | P value |
|-----------|---------|----|--------|-------|---------|
| Diet      | 120.47  | 1  | 120.47 | 1.717 | 0.248   |
| Host      | 3371.10 | 5  | 674.22 | 9.611 | 0.005   |
| Rep       | 578.30  | 2  | 289.15 | 4.122 | 0.025   |
| Host*Diet | 57.75   | 3  | 19.25  | 0.274 | 0.874   |
| Diet*Rep  | 16.74   | 1  | 16.74  | 0.239 | 0.874   |
| Rep*Host  | 474.82  | 1  | 474.82 | 6.769 | 0.006   |
| Error     | 350.75  | 5  | 70.15  |       |         |
| Total     | 4969.93 | 18 |        |       |         |

Appendix table 55 Factorial ANOVA showing the effects of different life stages of *R. dominica* on size of adult female

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 121.47  | 1  | 121.47 | 1.681  | 0.251   |
| Host      | 3371.25 | 5  | 674.25 | 9.332  | 0.007   |
| Rep       | 578.62  | 2  | 289.31 | 4.004  | 0.026   |
| Host*Diet | 58.08   | 3  | 19.36  | 0.268  | 0.876   |
| Diet*Rep  | 16.25   | 1  | 16.25  | 0.2245 | 0.858   |
| Rep*Host  | 474.74  | 1  | 474.74 | 6.570  | 0.009   |
| Error     | 361.25  | 5  | 72.25  |        |         |
| Total     | 4981.66 | 18 |        |        |         |

Appendix table 56 Average ( $\pm$ SE) number (%) of *X. flavipes* adult male and female on different life stages of *C. pusillus* under laboratory condition.

| Adults of <i>X. flavipes</i> | Different life stages of <i>C. pusillus</i> |                   |                    |                    |                    |                   |
|------------------------------|---|-------------------|--------------------|--------------------|--------------------|-------------------|
|                              | Eggs  | 1 <sup>st</sup>   | 2 <sup>nd</sup>    | 3 <sup>rd</sup>    | 4 <sup>th</sup>    | Pupae             |
| No. of Male                  | 30.00 $\pm$ 2.89b                           | 45.00 $\pm$ 1.15a | 38.33 $\pm$ 2.73ab | 38.00 $\pm$ 2.31ab | 35.00 $\pm$ 3.46ab | 28.33 $\pm$ 2.03b |
| No. of Female                | 70.00 $\pm$ 2.89ab                          | 55.00 $\pm$ 1.15b | 61.67 $\pm$ 2.73b  | 62.00 $\pm$ 2.31ab | 65.00 $\pm$ 3.46ab | 71.67 $\pm$ 4.04a |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 57 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on number of adult male

| Source    | SS     | DF | MS    | F     | P value |
|-----------|--------|----|-------|-------|---------|
| Diet      | 17416  | 1  | 17416 | 2.130 | 0.148   |
| Host      | 348375 | 5  | 69675 | 8.523 | 0.001   |
| Rep       | 24266  | 2  | 12133 | 1.484 | 0.271   |
| Host*Diet | 17325  | 3  | 5775  | 0.706 | 0.726   |
| Diet*Rep  | 11904  | 1  | 11904 | 1.456 | 0.276   |
| Rep*Host  | 38846  | 1  | 38846 | 4.752 | 0.006   |
| Error     | 40875  | 5  | 8175  |       |         |
| Total     | 499007 | 18 |       |       |         |

Appendix table 58 Factorial ANOVA showing the effects of different life stages of *C. pusillus* on number of adult female

| Source    | SS     | DF | MS    | F     | P value |
|-----------|--------|----|-------|-------|---------|
| Diet      | 17258  | 1  | 17258 | 2.297 | 0.145   |
| Host      | 346295 | 5  | 69259 | 9.217 | 0.002   |
| Rep       | 24464  | 2  | 12232 | 2.141 | 0.262   |
| Host*Diet | 17295  | 3  | 5765  | 0.767 | 0.459   |
| Diet*Rep  | 11941  | 1  | 11941 | 1.589 | 0.251   |
| Rep*Host  | 38936  | 1  | 38936 | 5.182 | 0.007   |
| Error     | 37570  | 5  | 7514  |       |         |
| Total     | 483759 | 18 |       |       |         |

Appendix table 59 Average ( $\pm$ SE) number(%) of *X. flavipes* adult male and female on different life stages of *R. dominica* under laboratory condition.

| Adults of <i>X. flavipes</i> | Different life stages of <i>R. dominica</i> |                   |                    |                     |                    |                   |
|------------------------------|---|-------------------|--------------------|---------------------|--------------------|-------------------|
|                              | Eggs  | 1 <sup>st</sup>   | 2 <sup>nd</sup>    | 3 <sup>rd</sup>     | 4 <sup>th</sup>    | Pupae             |
| No. of Male                  | 37.00 $\pm$ 1.73abc                         | 42.00 $\pm$ 2.31a | 39.00 $\pm$ 2.89ab | 34.00 $\pm$ 1.15abc | 31.00 $\pm$ 0.58bc | 27.00 $\pm$ 3.46a |
| No. of Female                | 63.00 $\pm$ 1.73ab                          | 58.00 $\pm$ 2.31b | 61.00 $\pm$ 2.89b  | 66.00 $\pm$ 1.15ab  | 69.00 $\pm$ 2.85ab | 73.00 $\pm$ 3.46a |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 60 Factorial ANOVA showing the effects of different life stages of *R. dominica* on number of adult male

| Source    | SS      | DF | MS     | F     | P value |
|-----------|---------|----|--------|-------|---------|
| Diet      | 110.74  | 1  | 110.74 | 1.463 | 0.281   |
| Host      | 2950.95 | 5  | 590.19 | 7.850 | 0.002   |
| Rep       | 800.30  | 2  | 400.15 | 5.325 | 0.017   |
| Host*Diet | 2176.44 | 3  | 725.48 | 9.654 | 0.945   |
| Diet*Rep  | 95.21   | 1  | 95.21  | 1.267 | 0.962   |
| Rep*Host  | 470.98  | 1  | 470.98 | 6.267 | 0.004   |
| Error     | 375.75  | 5  | 75.15  |       |         |
| Total     | 6980.37 | 18 |        |       |         |

Appendix table 61 Factorial ANOVA showing the effects of different life stages of *R. dominica* on number of adult female

| Source    | SS      | DF | MS     | F      | P value |
|-----------|---------|----|--------|--------|---------|
| Diet      | 118.62  | 1  | 118.62 | 1.438  | 0.325   |
| Host      | 3251.25 | 5  | 650.25 | 7.885  | 0.005   |
| Rep       | 896.64  | 2  | 448.32 | 5.437  | 0.019   |
| Host*Diet | 2250.45 | 3  | 750.15 | 9.096  | 0.814   |
| Diet*Rep  | 93.21   | 1  | 93.21  | 1.130  | 0.478   |
| Rep*Host  | 825.23  | 1  | 825.23 | 10.006 | 0.005   |
| Error     | 412.35  | 5  | 82.47  |        |         |
| Total     | 7847.75 | 18 |        |        |         |

Appendix table 62 Effects of different concentrations of Spinosad on hatchability of eggs of *C. pusillus*

| Concentrations | Dose rates ( $\mu\text{l}/\text{cm}^2$ ) | Total no of eggs | Total eggs hatched | Average % of egg hatched ( $\pm\text{SE}$ ) | PRC value |
|----------------|--|------------------|--------------------|---|-----------|
| Control        | Untreated                                | 150              | 126                | 42.00 $\pm$ 1.12a                           | -         |
| Spinosad       | 0.491                                    | 150              | 75                 | 25.00 $\pm$ 1.15b                           | 40.48     |
|                | 0.983                                    | 150              | 51                 | 17.00 $\pm$ 1.05c                           | 59.52     |
|                | 1.966                                    | 150              | 33                 | 11.00 $\pm$ 1.10d                           | 73.81     |
|                | 3.932                                    | 150              | 24                 | 8.00 $\pm$ 1.11de                           | 80.95     |
|                | 7.863                                    | 150              | 15                 | 5.00 $\pm$ 1.02e                            | 88.10     |

Note: Means with same letter do not significantly differed from each other Tukey's Test ,  $P < 0.001$

Appendix table 63 Factorial ANOVA showing the effects of different concentrations of Spinosad on hatchability eggs of *C. pusillus*

| Source                          | SS       | DF | MS      | F      | P value |
|---------------------------------|----------|----|---------|--------|---------|
| Concentration                   | 550.770  | 5  | 110.154 | 31.240 | 0.001   |
| Exposure period                 | 420.780  | 2  | 210.390 | 59.668 | 0.002   |
| REP                             | 14.364   | 2  | 7.182   | 2.037  | 0.135   |
| Concentration * REP             | 34.150   | 10 | 3.415   | 0.969  | 0.017   |
| Exposure period * Concentration | 63.890   | 10 | 6.389   | 1.812  | 0.011   |
| Exposure period * REP           | 8.044    | 4  | 2.011   | 0.570  | 0.199   |
| Error                           | 74.046   | 21 | 3.526   |        |         |
| Total                           | 1166.044 | 54 |         |        |         |

Appendix table 64 Dose mortality data of 14-19d old *C. pusillus* larvae treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 10   | 16.667 | 17  | 4.05        | 4.068        | 4.037       | 26.34  | 4.063        |
| 0.983   | 0.9925536         | 60            | 14   | 23.333 | 23  | 4.26        | 4.249        | 4.252       | 30.18  | 4.243        |
| 1.966   | 1.29358           | 60            | 17   | 28.333 | 28  | 4.42        | 4.430        | 4.420       | 33.48  | 4.422        |
| 3.932   | 1.594607          | 60            | 22   | 36.667 | 37  | 4.67        | 4.611        | 4.659       | 36.06  | 4.602        |
| 7.863   | 1.895579          | 60            | 24   | 40     | 40  | 4.75        | 4.792        | 4.740       | 36.96  | 4.782        |
| Y = 3.649872 + 0.5973316 X                            |                   |               |      |        | $\chi^2 = 0.2013416$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 18.20812 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 4.379743 to 75.69753 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 65 Dose mortality data of 14-19d old *C. pusillus* larvae treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 20   | 33.333 | 33  | 4.56        | 4.630        | 4.551       | 36.06  | 4.627        |
| 0.983   | 0.9925536         | 60            | 25   | 41.667 | 42  | 4.80        | 4.733        | 4.792       | 36.96  | 4.731        |
| 1.966   | 1.29358           | 60            | 27   | 45     | 45  | 4.87        | 4.836        | 4.890       | 37.62  | 4.835        |
| 3.932   | 1.594607          | 60            | 29   | 48.333 | 48  | 4.95        | 4.939        | 4.940       | 38.04  | 4.939        |
| 7.863   | 1.895579          | 60            | 30   | 50     | 50  | 5.00        | 5.042        | 5.000       | 38.22  | 5.043        |
| Y = 4.388323 + 0.3452384 X                            |                   |               |      |        | $\chi^2 = 0.5288744$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 5.912253 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 1.421441 to 24.59105 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 66 Dose mortality data of 14-19d old *C. pusillus* larvae treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 32   | 53.333 | 53  | 5.08        | 5.14591      | 5.065       | 38.04  | 3.14457      |
| 0.983  | 0.9925536         | 60            | 37   | 61.667 | 62  | 5.31        | 5.24705      | 5.332       | 37.62  | 5.24212      |
| 1.966  | 1.29358           | 60            | 39   | 65.000 | 65  | 5.39        | 5.34803      | 5.37        | 36.96  | 5.33952      |
| 3.932  | 1.594607          | 60            | 40   | 66.667 | 67  | 5.44        | 5.44902      | 5.429       | 36.06  | 5.43692      |
| 7.863  | 1.895579          | 60            | 42   | 70.000 | 70  | 5.52        | 5.55000      | 5.5         | 34.86  | 5.53430      |
| Y = 4.92096 + 0.3235642 X                              |                   |               |      |        | $\chi^2 = 0.6214318$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 0.1755007 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 0.01161457 to 2.651883 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 67 Dose mortality data of *C. pusillus* pupae treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 5    | 8.333  | 8   | 3.59        | 3.642        | 3.596       | 18.12  | 3.660        |
| 0.983   | 0.9925536         | 60            | 7    | 11.667 | 12  | 3.82        | 3.780        | 3.836       | 20.16  | 3.791        |
| 1.966   | 1.29358           | 60            | 9    | 15     | 15  | 3.96        | 3.916        | 3.970       | 24.30  | 3.923        |
| 3.932   | 1.594607          | 60            | 10   | 16.667 | 17  | 4.05        | 4.053        | 4.037       | 26.34  | 4.054        |
| 7.863   | 1.895579          | 60            | 12   | 20     | 20  | 4.16        | 4.190        | 4.170       | 28.26  | 4.186        |
| Y = 3.356467 + 0.4377169 X                            |                   |               |      |        | $\chi^2 = 0.1827011$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 568.5706 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 2.246793 to 143881.9 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 68 Dose mortality data of *C. pusillus* pupae treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 10   | 16.667 | 17  | 4.05        | 4.062        | 4.037       | 26.34  | 4.055        |
| 0.983   | 0.9925536         | 60            | 12   | 20     | 20  | 4.16        | 4.140        | 4.170       | 28.26  | 4.135        |
| 1.966   | 1.29358           | 60            | 13   | 21.667 | 22  | 4.23        | 4.218        | 4.218       | 30.18  | 4.214        |
| 3.932   | 1.594607          | 60            | 14   | 23.333 | 23  | 4.26        | 4.296        | 4.252       | 30.18  | 4.294        |
| 7.863   | 1.895579          | 60            | 16   | 26.667 | 27  | 4.39        | 4.374        | 4.394       | 31.92  | 4.374        |
| Y = 3.872518 + 0.2643514 X                            |                   |               |      |        | $\chi^2 = 0.1104122$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 1841.139 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 0.09236452 to 36700190 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 69 Dose mortality data of *C. pusillus* pupae treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 15   | 25     | 25  | 4.33        | 4.312        | 4.330       | 31.92  | 4.309        |
| 0.983   | 0.9925536         | 60            | 17   | 28.333 | 28  | 4.42        | 4.425        | 4.420       | 33.48  | 4.421        |
| 1.966   | 1.29358           | 60            | 19   | 31.667 | 32  | 4.53        | 4.538        | 4.516       | 34.86  | 4.532        |
| 3.932   | 1.594607          | 60            | 21   | 35     | 35  | 4.61        | 4.651        | 4.605       | 36.06  | 4.644        |
| 7.863   | 1.895579          | 60            | 25   | 41.667 | 42  | 4.80        | 4.764        | 4.792       | 36.93  | 4.755        |
| Y = 4.053233 + 0.3704698 X                            |                   |               |      |        | $\chi^2 = 0.1278024$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 35.94058 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 2.061289 to 626.6588 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 70 Dose mortality data of 2d *C. pusillus* adult treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 15   | 25     | 25  | 4.33        | 4.3019       | 4.330       | 31.92  | 4.300        |
| 0.983   | 0.9925536         | 60            | 18   | 30     | 30  | 4.48        | 4.475        | 4.480       | 33.48  | 4.474        |
| 1.966   | 1.29358           | 60            | 20   | 33.333 | 33  | 4.56        | 4.648        | 4.551       | 36.06  | 4.648        |
| 3.932   | 1.594607          | 60            | 27   | 45     | 45  | 4.87        | 4.821        | 4.890       | 37.62  | 4.822        |
| 7.863   | 1.895579          | 60            | 30   | 50     | 50  | 5.00        | 4.994        | 4.990       | 38.04  | 4.996        |
| Y = 3.900657 + 0.5777386 X                            |                   |               |      |        | $\chi^2 = 0.5446673$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 7.995372 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 2.947408 to 21.68888 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 71 Dose mortality data of 2d *C. pusillus* adult treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 22   | 36.667 | 37  | 4.67        | 4.640        | 4.659       | 36.06  | 4.639        |
| 0.983   | 0.9925536         | 60            | 25   | 41.667 | 42  | 4.80        | 4.812        | 4.812       | 37.62  | 4.809        |
| 1.966   | 1.29358           | 60            | 28   | 46.667 | 47  | 4.92        | 4.984        | 4.915       | 38.04  | 4.979        |
| 3.932   | 1.594607          | 60            | 35   | 58.333 | 58  | 5.20        | 5.156        | 5.190       | 38.04  | 5.148        |
| 7.863   | 1.895579          | 60            | 38   | 63.333 | 63  | 5.33        | 5.328        | 5.318       | 36.96  | 5.318        |
| Y = 24.249114 + 0.563959 X                            |                   |               |      |        | $\chi^2 = 0.2347469$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> = 2.145135 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 1.191995 to 3.860422 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 72 Dose mortality data of 2d *C. pusillus* adult treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 28   | 46.667 | 47  | 4.92        | 4.820        | 4.942       | 37.62  | 4.840        |
| 0.983   | 0.9925536         | 60            | 30   | 50     | 50  | 5.00        | 5.036        | 5.000       | 38.22  | 5.047        |
| 1.966   | 1.29358           | 60            | 32   | 53.33. | 53  | 5.08        | 5.252        | 5.098       | 37.62  | 5.254        |
| 3.932   | 1.594607          | 60            | 42   | 70     | 70  | 5.52        | 5.468        | 5.510       | 36.06  | 5.461        |
| 7.863   | 1.895579          | 60            | 46   | 76.667 | 77  | 5.74        | 5.684        | 5.730       | 33.48  | 5.668        |
| Y = 4.364444 + 0.6877889 X                            |                   |               |      |        | $\chi^2 = 1.608753$ (3 df)  |             |              |             |        |              |
| LC <sub>50</sub> = 0.839572 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 0.446121 to 1.580054 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 73 Regression equations,  $\chi^2$  values, LC<sub>50</sub> values and 95% confidence limits for Spinosad against 14-19 d larvae, pupae and 2 d adults of *C. pusillus* after 24, 48 and 72 h of exposure.

| Concentration of Spinosad ( $\mu\text{l}/\text{cm}^2$ ) | Life stage of <i>C. pusillus</i> | Exposure period (h) | Regression equation        | $\chi^2$ for heterogeneity | LC <sub>50</sub> ( $\mu\text{l}/\text{cm}^2$ ) | 95% confidence limits |          |
|---|----------------------------------|---------------------|----------------------------|----------------------------|--|-----------------------|----------|
|   |                                  |                     |                            |                            |  | Lower                 | Upper    |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Larvae                           | 24                  | Y = 3.649872 + 0.5973316 X | 0.2013416                  | 18.20812                                       | 4.379743              | 75.69753 |
|   |                                  | 48                  | Y = 4.388323 + 0.3452384 X | 0.5288744                  | 5.912253                                       | 1.421441              | 24.59105 |
|   |                                  | 72                  | Y = 4.92096 + 0.3235642 X  | 0.6214318                  | 0.1755007                                      | 0.01161457            | 2.651883 |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Pupae                            | 24                  | Y = 3.356467 + 0.4377169 X | 0.1827011                  | 568.5706                                       | 2.246793              | 143881.9 |
|   |                                  | 48                  | Y = 3.872518 + 0.2643514 X | 0.1104122                  | 1841.139                                       | 0.09236452            | 36700190 |
|   |                                  | 72                  | Y = 4.053233 + 0.3704698 X | 0.1278024                  | 35.94058                                       | 2.061289              | 626.6588 |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Adults                           | 24                  | Y = 3.900657 + 0.5777386 X | 0.5446673                  | 7.995372                                       | 2.947408              | 21.68888 |
|   |                                  | 48                  | Y = 24.249114 + 0.563959 X | 0.2347469                  | 2.145135                                       | 1.191995              | 3.860422 |
|   |                                  | 72                  | Y = 4.364444 + 0.6877889 X | 1.608753                   | 0.839572                                       | 0.446121              | 1.580054 |

Appendix table 74 Factorial ANOVA showing the effects of different concentrations of Spinosad on the 14-19d old larval mortality of *C. pusillus* after different exposure periods.

| Source                          | SS       | DF | MS      | F      | P value |
|---------------------------------|----------|----|---------|--------|---------|
| Concentration                   | 695.780  | 5  | 139.156 | 38.389 | 0.000   |
| Exposure period                 | 420.778  | 2  | 210.389 | 58.038 | 0.001   |
| REP                             | 14.778   | 2  | 7.389   | 2.038  | 0.245   |
| Concentration * REP             | 35.440   | 10 | 3.544   | 0.978  | 0.027   |
| Exposure period * Concentration | 124.110  | 10 | 12.411  | 3.424  | 0.001   |
| Exposure period * REP           | 15.948   | 4  | 3.987   | 1.100  | 0.207   |
| Error                           | 76.125   | 21 | 3.625   |        |         |
| Total                           | 1382.959 | 54 |         |        |         |

Appendix table 75 Factorial ANOVA showing the effects of different concentrations of Spinosad on pupal mortality of *C. pusillus* after different exposure periods.

| Source                          | SS       | DF | MS      | F      | P value |
|---------------------------------|----------|----|---------|--------|---------|
| Concentration                   | 804.425  | 5  | 160.885 | 61.524 | 0.000   |
| Exposure period                 | 161.038  | 2  | 80.519  | 30.791 | 0.002   |
| REP                             | 15.026   | 2  | 7.513   | 2.873  | 0.140   |
| Concentration * REP             | 28.570   | 10 | 2.857   | 1.093  | 0.389   |
| Exposure period * Concentration | 66.890   | 10 | 6.689   | 2.558  | 0.006   |
| Exposure period * REP           | 6.964    | 4  | 1.741   | 0.666  | 0.154   |
| Error                           | 54.915   | 21 | 2.615   |        |         |
| Total                           | 1137.828 | 54 |         |        |         |



Appendix table 76 Factorial ANOVA showing the effects of different concentrations of Spinosad on the adult mortality of *C. pusillus* after different exposure periods.

| Source                | SS       | DF | MS      | F       | P value |
|-----------------------|----------|----|---------|---------|---------|
| Concentration         | 898.150  | 5  | 179.630 | 42.617  | 0.000   |
| Exposure period       | 1711.038 | 2  | 855.519 | 202.970 | 0.000   |
| REP                   | 7.948    | 2  | 3.974   | 0.943   | 0.610   |
| Concentration * REP   | 402.800  | 10 | 40.280  | 9.556   | 0.000   |
| Exposure period *     |          |    |         |         |         |
| Concentration         | 351.960  | 10 | 35.196  | 8.350   | 0.000   |
| Exposure period * REP | 19.948   | 4  | 4.987   | 1.183   | 0.571   |
| Error                 | 88.515   | 21 | 4.215   |         |         |
| Total                 | 3480.359 | 54 |         |         |         |

Appendix table 77 Effects of different concentrations of Spinosad on hatchability of eggs of *R. dominica*

| Concentrations | Dose rates ( $\mu\text{l}/\text{cm}^2$ ) | Total no of eggs | Total eggs hatched | Average % of egg hatched ( $\pm\text{SE}$ ) | PRC value |
|----------------|--|------------------|--------------------|---|-----------|
| Control        | Untreated                                | 150              | 114                | 38.00 $\pm$ 0.95a                           | -         |
| Spinosad       | 0.491                                    | 150              | 45                 | 15.00 $\pm$ 1.14b                           | 60.53     |
|                | 0.983                                    | 150              | 27                 | 9.00 $\pm$ 1.01c                            | 76.32     |
|                | 1.966                                    | 150              | 12                 | 4.00 $\pm$ 0.84cd                           | 89.47     |
|                | 3.932                                    | 150              | 6                  | 2.00 $\pm$ 1.14d                            | 94.74     |
|                | 7.863                                    | 150              | 1                  | 0.33 $\pm$ 1.03d                            | 99.13     |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 78 Factorial ANOVA showing the effects of different concentrations of Spinosad on hatchability eggs of *R. dominica*

| Source                | SS       | DF | MS      | F      | P value |
|-----------------------|----------|----|---------|--------|---------|
| Concentration         | 354.925  | 5  | 70.985  | 13.851 | 0.001   |
| Exposure period       | 400.956  | 2  | 200.478 | 39.118 | 0.008   |
| REP                   | 31.050   | 2  | 15.525  | 3.029  | 0.053   |
| Concentration * REP   | 402.910  | 10 | 40.251  | 7.854  | 0.011   |
| Exposure period *     |          |    |         |        |         |
| Concentration         | 407.660  | 10 | 40.766  | 7.954  | 0.123   |
| Exposure period * REP | 81.412   | 4  | 20.353  | 3.971  | 0.015   |
| Error                 | 107.625  | 21 | 5.125   |        |         |
| Total                 | 1786.538 | 54 |         |        |         |

Appendix table 79 Dose mortality data of 26-31d *R. dominica* larvae treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 14   | 23.333 | 23  | 4.26        | 4.216        | 4.252       | 30.18  | 4.207        |
| 0.983   | 0.9925536         | 60            | 15   | 25     | 25  | 4.33        | 4.402        | 4.330       | 33.48  | 4.395        |
| 1.966   | 1.29358           | 60            | 20   | 33.333 | 33  | 4.56        | 4.588        | 4.544       | 34.86  | 4.582        |
| 3.932   | 1.594607          | 60            | 27   | 45     | 45  | 4.87        | 4.774        | 4.870       | 36.96  | 4.769        |
| 7.863   | 1.895579          | 60            | 28   | 46.667 | 47  | 4.92        | 4.960        | 4.915       | 38.04  | 4.957        |
| Y = 3.776951 + 0.6223563 X                            |                   |               |      |        | $\chi^2 = 0.6917343$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> is 9.22978 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 3.402471 TO 25.03735 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 80 Dose mortality data of 26-31d *R. dominica* larvae treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )             | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 25   | 41.667 | 42  | 4.80        | 4.792        | 4.792       | 36.96  | 4.796        |
| 0.983   | 0.9925536         | 60            | 27   | 45     | 45  | 4.87        | 4.876        | 4.890       | 37.62  | 4.877        |
| 1.966   | 1.29358           | 60            | 29   | 48.333 | 48  | 4.95        | 4.960        | 4.940       | 38.04  | 4.957        |
| 3.932   | 1.594607          | 60            | 31   | 51.667 | 52  | 5.05        | 5.044        | 5.050       | 38.22  | 5.038        |
| 7.863   | 1.895579          | 60            | 33   | 55     | 55  | 5.13        | 5.128        | 5.115       | 38.04  | 5.118        |
| Y = 4.611174 + 0.2676746 X                      |                   |               |      |        | $\chi^2 = 0.0251174$ (3 df)                                   |             |              |             |        |              |
| LC <sub>50</sub> is 2.835366 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 0.7683601 to 10.46294 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 81 Dose mortality data of 26-31d *R. dominica* larvae treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )              | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 30   | 50     | 50  | 5.00        | 4.984        | 4.990       | 38.04  | 4.984        |
| 0.983  | 0.9925536         | 60            | 32   | 53.333 | 53  | 5.08        | 5.097        | 5.075       | 38.22  | 5.096        |
| 1.966  | 1.29358           | 60            | 35   | 58.333 | 58  | 5.20        | 5.210        | 5.228       | 37.62  | 5.208        |
| 3.932  | 1.594607          | 60            | 38   | 63.333 | 63  | 5.33        | 5.323        | 5.318       | 36.96  | 5.320        |
| 7.863  | 1.895579          | 60            | 40   | 66.667 | 67  | 5.44        | 5.436        | 5.429       | 36.06  | 5.432        |
| Y = 4.726218 + 0.372455 X                        |                   |               |      |        | $\chi^2 = 0.03347778$ (3 df)                                  |             |              |             |        |              |
| LC <sub>50</sub> is 0.5433412 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 0.1273662 to 2.317881 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 82 Dose mortality data of *R. dominica* pupae treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )             | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 3    | 5      | 5  | 3.36        | 3.424        | 3.360       | 14.28  | 3.448        |
| 0.983   | 0.9925536         | 60            | 5    | 8.333  | 8  | 3.59        | 3.572        | 3.596       | 16.14  | 3.587        |
| 1.966   | 1.29358           | 60            | 7    | 11.667 | 12   | 3.82        | 3.720        | 3.836       | 20.16  | 3.726        |
| 3.932   | 1.594607          | 60            | 8    | 13.333 | 13   | 3.87        | 3.868        | 3.873       | 22.20  | 3.865        |
| 7.863   | 1.895579          | 60            | 9    | 15     | 15   | 3.96        | 4.016        | 3.955       | 26.34  | 4.004        |
| Y = 3.129547 + 0.4611072 X                      |                   |               |      |        | $\chi^2 = 0.4201939$ (3 df)                                  |             |              |             |        |              |
| LC <sub>50</sub> is 1138.777 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 1.990441 to 651521.7 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 83 Dose mortality data of *R. dominica* pupae treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )             | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 8    | 13.333 | 13   | 3.87        | 3.910        | 3.878       | 24.30  | 3.916        |
| 0.983   | 0.9925536         | 60            | 10   | 16.667 | 17   | 4.05        | 4.035        | 4.037       | 26.34  | 4.039        |
| 1.966   | 1.29358           | 60            | 13   | 21.667 | 22   | 4.23        | 4.160        | 4.246       | 28.26  | 4.161        |
| 3.932   | 1.594607          | 60            | 14   | 23.333 | 23   | 4.26        | 4.285        | 4.252       | 30.18  | 4.283        |
| 7.863   | 1.895579          | 60            | 16   | 26.667 | 27   | 4.39        | 4.410        | 4.390       | 33.48  | 4.405        |
| Y = 3.636407 + 0.4053654 X                      |                   |               |      |        | $\chi^2 = 0.2772174$ (3 df)                                  |             |              |             |        |              |
| LC <sub>50</sub> is 231.1335 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 2.478723 to 21552.51 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 84 Dose mortality data of *R. dominica* pupae treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 14   | 23.333 | 23  | 4.26        | 4.300        | 4.252       | 30.18  | 4.292        |
| 0.983   | 0.9925536         | 60            | 18   | 30     | 30  | 4.48        | 4.427        | 4.480       | 33.48  | 4.421        |
| 1.966   | 1.29358           | 60            | 20   | 33.333 | 33  | 4.56        | 4.554        | 4.544       | 34.86  | 4.550        |
| 3.932   | 1.594607          | 60            | 22   | 36.667 | 37  | 4.67        | 4.681        | 4.659       | 36.06  | 4.679        |
| 7.863   | 1.895579          | 60            | 25   | 41.667 | 42  | 4.80        | 4.808        | 4.812       | 37.62  | 4.808        |
| Y = 3.995484 + 0.4286425 X                            |                   |               |      |        | $\chi^2 = 0.1803207$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> is 22.0538 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 2.711695 to 179.3602 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 85 Dose mortality data of 2d *R. dominica* adult treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 20   | 33.333 | 33   | 4.56        | 4.576        | 4.554       | 34.86  | 4.565        |
| 0.983  | 0.9925536         | 60            | 23   | 38.333 | 38   | 4.69        | 4.687        | 4.686       | 36.06  | 4.679        |
| 1.966  | 1.29358           | 60            | 26   | 43.333 | 43   | 4.82        | 4.798        | 4.818       | 36.96  | 4.793        |
| 3.932  | 1.594607          | 60            | 28   | 46.667 | 47   | 4.92        | 4.909        | 4.915       | 38.04  | 4.906        |
| 7.863  | 1.895579          | 60            | 30   | 50     | 50   | 5           | 5.020        | 5           | 38.22  | 5.020        |
| Y = 4.303998 + 0.3778334 X                             |                   |               |      |        | $\chi^2 = 0.05872917$ (3 df)                                       |             |              |             |        |              |
| LC <sub>50</sub> is 6.951654 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 1.68851 to 28.62021 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 86 Dose mortality data of 2d *R. dominica* adult treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )             | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 27   | 45     | 45  | 4.87        | 4.828        | 4.890       | 37.62  | 4.842        |
| 0.983   | 0.9925536         | 60            | 30   | 50     | 50  | 5.00        | 5.002        | 5.000       | 38.22  | 5.006        |
| 1.966   | 1.29358           | 60            | 31   | 51.667 | 52  | 5.05        | 5.176        | 5.050       | 38.04  | 5.170        |
| 3.932   | 1.594607          | 60            | 40   | 66.667 | 67  | 5.44        | 5.350        | 5.422       | 36.96  | 5.334        |
| 7.863   | 1.895579          | 60            | 42   | 70     | 70  | 5.52        | 5.524        | 5.500       | 34.86  | 5.500        |
| Y = 4.465182 + 0.544706 X                               |                   |               |      |        | $\chi^2 = 1.017773$ (3 df)  |             |              |             |        |              |
| LC <sub>50</sub> is 0.9590641 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 0.4546266 to 2.02328 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 87 Dose mortality data of 2d *R. dominica* adult treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 32   | 53.333 | 53   | 5.08        | 5.010        | 5.075       | 38.22  | 5.020        |
| 0.983  | 0.9925536         | 60            | 36   | 60.000 | 60   | 5.25        | 5.287        | 5.280       | 37.62  | 5.285        |
| 1.966  | 1.29358           | 60            | 40   | 66.667 | 67   | 5.44        | 5.564        | 5.416       | 34.86  | 5.551        |
| 3.932  | 1.594607          | 60            | 49   | 81.667 | 82   | 5.92        | 5.841        | 5.868       | 30.18  | 5.816        |
| 7.863  | 1.895579          | 60            | 52   | 86.667 | 87   | 6.13        | 6.118        | 6.132       | 24.30  | 6.081        |
| Y = 4.410579 + 0.8814548 X                             |                   |               |      |        | $\chi^2 = 0.8944054$ (3 df)  |             |              |             |        |              |
| LC <sub>50</sub> is 0.466328 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 0.2381866 to 0.912989 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 88 Regression equations,  $\chi^2$  values, LC<sub>50</sub> values and 95% confidence limits for Spinosad against 26-31 d larvae, pupae and 2 d adults of *R. dominica* after 24, 48 and 72 h of exposure.

| Concentration of Spinosad ( $\mu\text{l}/\text{cm}^2$ ) | Life stage of <i>R. dominica</i> | Exposure period (h) | Regression equation        | $\chi^2$ for heterogeneity | LC <sub>50</sub> ( $\mu\text{l}/\text{cm}^2$ ) | 95% confidence limits |          |
|---|----------------------------------|---------------------|----------------------------|----------------------------|--|-----------------------|----------|
|   |                                  |                     |                            |                            |  | Lower                 | Upper    |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Larvae                           | 24                  | Y = 3.776951 + 0.6223563 X | 0.6917343                  | 9.22978  | 3.402471              | 25.03735 |
|   |                                  | 48                  | Y = 4.611174 + 0.2676746 X | 0.0251174                  | 2.835366                                       | 0.7683601             | 10.46294 |
|   |                                  | 72                  | Y = 4.726218 + 0.372455 X  | 0.03347778                 | 0.5433412                                      | 0.1273662             | 2.317881 |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Pupae                            | 24                  | Y = 3.129547 + 0.4611072 X | 0.4201939                  | 1138.777                                       | 1.990441              | 651521.7 |
|   |                                  | 48                  | Y = 3.636407 + 0.4053654 X | 0.2772174                  | 231.1335                                       | 2.478723              | 21552.51 |
|   |                                  | 72                  | Y = 3.995484 + 0.4286425 X | 0.1803207                  | 22.0538  | 2.711695              | 179.3602 |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863    | Adults                           | 24                  | Y = 4.303998 + 0.3778334 X | 0.05872917                 | 6.951654                                       | 1.68851               | 28.62021 |
|   |                                  | 48                  | Y = 4.465182 + 0.544706 X  | 1.017773                   | 0.9590641                                      | 0.4546266             | 2.02328  |
|   |                                  | 72                  | Y = 4.410579 + 0.8814548 X | 0.8944054                  | 0.466328                                       | 0.2381866             | 0.912989 |

Appendix table 89 Factorial ANOVA showing the effects of different concentrations of Spinosad on the 14-19d old larval mortality of *R. dominica* after different exposure periods.

| Source                          | SS        | DF | MS       | F      | P value |
|---------------------------------|-----------|----|----------|--------|---------|
| Concentration                   | 5749.705  | 5  | 1149.941 | 56.006 | 0.000   |
| Exposure period                 | 2341.148  | 2  | 1170.574 | 57.026 | 0.000   |
| REP                             | 80.704    | 2  | 40.352   | 1.966  | 0.128   |
| Concentration * REP             | 200.410   | 10 | 20.041   | 0.976  | 0.001   |
| Exposure period * Concentration | 1605.670  | 10 | 160.567  | 7.795  | 0.000   |
| Exposure period * REP           | 79.992    | 4  | 19.998   | 0.974  | 0.417   |
| Error                           | 431.967   | 21 | 20.527.  |        |         |
| Total                           | 10101.596 | 54 |          |        |         |

Appendix table 90 Factorial ANOVA showing the effects of different concentrations of Spinosad on the pupal mortality of *R. dominica* after different exposure periods.

| Source                          | SS      | DF | MS     | F      | P value |
|---------------------------------|---------|----|--------|--------|---------|
| Concentration                   | 179.945 | 5  | 35.989 | 11.516 | 0.000   |
| Exposure period                 | 151.112 | 2  | 75.556 | 23.986 | 0.002   |
| REP                             | 13.334  | 2  | 6.667  | 2.133  | 0.063   |
| Concentration * REP             | 164.890 | 10 | 16.489 | 5.276  | 0.000   |
| Exposure period * Concentration | 144.530 | 10 | 14.453 | 4.622  | 0.000   |
| Exposure period * REP           | 11.588  | 4  | 2.897  | 0.927  | 0.010   |
| Error                           | 65.625  | 21 | 3.125  |        |         |
| Total                           | 731.024 | 54 |        |        |         |

Appendix table 91 Factorial ANOVA showing the effects of different concentrations of Spinosad on the adult mortality of *R. dominica* after different exposure periods.

| Source                          | SS       | DF | MS      | F      | P value |
|---------------------------------|----------|----|---------|--------|---------|
| Concentration                   | 1105.945 | 5  | 221.189 | 83.468 | 0.000   |
| Exposure period                 | 191.444  | 2  | 95.722  | 36.122 | 0.003   |
| REP                             | 4.334    | 2  | 2.167   | 1.635  | 0.615   |
| Concentration * REP             | 25.890   | 10 | 2.589   | 0.977  | 0.031   |
| Exposure period * Concentration | 53.440   | 10 | 5.344   | 2.017  | 0.001   |
| Exposure period * REP           | 10.224   | 4  | 2.556   | 0.965  | 0.066   |
| Error                           | 55.650   | 21 | 2.650   |        |         |
| Total                           | 1446.927 | 54 |         |        |         |

Appendix table 92 Effects of different concentrations of Spinosad on hatchability of eggs of *X. flavipes*

| Concentrations | Dose rates ( $\mu\text{l}/\text{cm}^2$ ) | Total no of eggs | Total eggs hatched | Average % of egg hatched ( $\pm\text{SE}$ ) | PRC value |
|----------------|--|------------------|--------------------|---|-----------|
| Control        | Untreated                                | 150              | 105                | 35.00 $\pm$ 1.73a                           | -         |
| Spinosad       | 0.491                                    | 150              | 102                | 34.00 $\pm$ 1.15ab                          | 2.86      |
|                | 0.983                                    | 150              | 99                 | 33.00 $\pm$ 1.21ab                          | 5.71      |
|                | 1.966                                    | 150              | 96                 | 32.00 $\pm$ 1.36ab                          | 8.57      |
|                | 3.932                                    | 150              | 90                 | 30.00 $\pm$ 2.89ab                          | 14.29     |
|                | 7.863                                    | 150              | 75                 | 25.00 $\pm$ 2.12b                           | 28.57     |

Note: Means with same letter do not significantly differed from each other Tukey's Test,  $P < 0.001$

Appendix table 93 Factorial ANOVA showing the effects of different concentrations of Spinosad on hatchability eggs of *X. flavipes*

| Source                          | SS      | DF | MS     | F      | P value |
|---------------------------------|---------|----|--------|--------|---------|
| Concentration                   | 144.090 | 5  | 28.769 | 12.599 | 0.001   |
| Exposure period                 | 64.032  | 2  | 32.020 | 37.489 | 0.002   |
| REP                             | 4.702   | 2  | 2.231  | 0.876  | 0.389   |
| Concentration * REP             | 22.452  | 10 | 2.278  | 5.540  | 0.003   |
| Exposure period * Concentration | 15.539  | 10 | 1.499  | 3.608  | 0.005   |
| Exposure period * REP           | 3.305   | 4  | 0.849  | 2.011  | 0.123   |
| Error                           | 0.000   | 0  | .      |        |         |
| Total                           | 754.000 | 54 |        |        |         |

Appendix table 94 Dose mortality data of 4d *X. flavipes* nymphs treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 3    | 5      | 5   | 3.36        | 3.350        | 3.360       | 12.48  | 3.344        |
| 0.983  | 0.9925536         | 60            | 4    | 6.667  | 7   | 3.52        | 3.500        | 3.519       | 16.14  | 3.500        |
| 1.966  | 1.29358           | 60            | 5    | 8.333  | 8   | 3.59        | 3.650        | 3.596       | 18.12  | 3.653        |
| 3.932  | 1.594607          | 60            | 7    | 11.667 | 12  | 3.82        | 3.800        | 3.822       | 22.20  | 3.807        |
| 7.863  | 1.895579          | 60            | 9    | 15     | 15  | 3.96        | 3.950        | 3.970       | 24.30  | 3.962        |
| Y = 2.990045 + 0.5126829 X                             |                   |               |      |        | $\chi^2 = 0.07527256$ (3 df)  |             |              |             |        |              |
| LC <sub>50</sub> is 832.6535 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 2.922949 to 237196.1 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 95 Dose mortality data of 4d *X. flavipes* nymphs treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )           | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 7    | 11.667 | 12  | 3.82        | 3.866        | 3.822       | 22.20  | 3.871        |
| 0.983   | 0.9925536         | 60            | 10   | 16.667 | 17  | 4.05        | 4.008        | 4.037       | 26.34  | 4.010        |
| 1.966   | 1.29358           | 60            | 12   | 20     | 20  | 4.16        | 4.150        | 4.170       | 28.26  | 4.149        |
| 3.932   | 1.594607          | 60            | 15   | 25     | 25  | 4.33        | 4.292        | 4.320       | 30.18  | 4.287        |
| 7.863   | 1.895579          | 60            | 16   | 26.667 | 27  | 4.39        | 4.434        | 4.390       | 33.48  | 4.426        |
| Y = 3.55203 + 0.4612296 X                             |                   |               |      |        | $\chi^2 = 0.16153$ (3 df)   |             |              |             |        |              |
| LC <sub>50</sub> is 137.838 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 3.740582 to 5079.244 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 96 Dose mortality data of 4d *X. flavipes* nymphs treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 10   | 16.667 | 17   | 4.05        | 4.048        | 4.037       | 26.34  | 4.050        |
| 0.983  | 0.9925536         | 60            | 12   | 20     | 20   | 4.16        | 4.182        | 4.170       | 28.26  | 4.181        |
| 1.966  | 1.29358           | 60            | 15   | 25     | 25   | 4.33        | 4.316        | 4.330       | 31.92  | 4.313        |
| 3.932  | 1.594607          | 60            | 18   | 30     | 30   | 4.48        | 4.450        | 4.480       | 33.48  | 4.444        |
| 7.863  | 1.895579          | 60            | 20   | 33.333 | 33   | 4.56        | 4.584        | 4.544       | 34.86  | 4.575        |
| Y = 3.748117 + 0.04364652 X                            |                   |               |      |        | $\chi^2 = 0.09504318$ (3 df)                                       |             |              |             |        |              |
| LC <sub>50</sub> is 73.82966 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 3.22157 to 1691.976 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 97 Dose mortality data of 2d *X. flavipes* adult treated with different concentrations of Spinosad after 24 hours of treatment.

| Concentration ( $\mu\text{l}/\text{cm}^2$ )            | Log concentration | No of insects | Kill | % kill | Corr. %   | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|--|-------------------|---------------|------|--------|---|-------------|--------------|-------------|--------|--------------|
| 0.491  | 0.6910847         | 60            | 3    | 5      | 5   | 3.36        | 3.386        | 3.360       | 12.48  | 3.396        |
| 0.983  | 0.9925536         | 60            | 5    | 8.333  | 8   | 3.59        | 3.552        | 3.596       | 16.14  | 3.557        |
| 1.966  | 1.29358           | 60            | 6    | 10     | 10  | 3.72        | 3.718        | 3.720       | 20.16  | 3.718        |
| 3.932  | 1.594607          | 60            | 8    | 13.333 | 13  | 3.87        | 3.884        | 3.873       | 22.20  | 3.879        |
| 7.863  | 1.895579          | 60            | 10   | 16.667 | 17  | 4.05        | 4.050        | 4.037       | 26.34  | 4.040        |
| Y = 3.027043 + 0.5342836 X                             |                   |               |      |        | $\chi^2 = 0.04168511$ (3 df)  |             |              |             |        |              |
| LC <sub>50</sub> is 492.8509 $\mu\text{l}/\text{cm}^2$ |                   |               |      |        | 95% Conf. limits are 3.859698 to 62932.93 $\mu\text{l}/\text{cm}^2$ |             |              |             |        |              |

Appendix table 98 Dose mortality data of 2d *X. flavipes* adult treated with different concentrations of Spinosad after 48 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )             | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 4    | 6.667  | 7  | 3.52        | 3.532        | 3.519       | 16.14  | 3.537        |
| 0.983   | 0.9925536         | 60            | 6    | 10     | 10   | 3.72        | 3.684        | 3.730       | 18.12  | 3.687        |
| 1.966   | 1.29358           | 60            | 7    | 11.667 | 12   | 3.82        | 3.836        | 3.822       | 22.20  | 3.842        |
| 3.932   | 1.594607          | 60            | 9    | 15     | 15   | 3.96        | 3.988        | 3.970       | 24.30  | 3.997        |
| 7.863   | 1.895579          | 60            | 12   | 20     | 20   | 4.16        | 4.140        | 4.170       | 28.26  | 4.152        |
| Y = 3.175748 + 0.514919 X                       |                   |               |      |        | $\chi^2 = 0.07186127$ (3 df)                                 |             |              |             |        |              |
| LC <sub>50</sub> is 348.9742 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 4.223628 to 28833.73 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 99 Dose mortality data of 2d *X. flavipes* adult treated with different concentrations of Spinosad after 72 hours of treatment.

| Concentration (µl/cm <sup>2</sup> )             | Log concentration | No of insects | Kill | % kill | Corr. %  | Emp. probit | Expt. probit | Work probit | Weight | Final probit |
|---|-------------------|---------------|------|--------|--|-------------|--------------|-------------|--------|--------------|
| 0.491   | 0.6910847         | 60            | 6    | 10     | 10   | 3.72        | 3.760        | 3.720       | 20.16  | 3.766        |
| 0.983   | 0.9925536         | 60            | 9    | 15     | 15   | 3.96        | 3.894        | 3.975       | 22.20  | 3.897        |
| 1.966   | 1.29358           | 60            | 10   | 16.667 | 17   | 4.05        | 4.028        | 4.037       | 26.34  | 4.029        |
| 3.932   | 1.594607          | 60            | 11   | 18.333 | 18   | 4.08        | 0.162        | 4.094       | 28.26  | 4.160        |
| 7.863   | 1.895579          | 60            | 15   | 25     | 25   | 4.33        | 4.296        | 4.320       | 30.18  | 4.291        |
| Y = 3.464713 + 0.4360996 X                      |                   |               |      |        | $\chi^2 = 0.3258066$ (3 df)                                  |             |              |             |        |              |
| LC <sub>50</sub> is 331.5098 µl/cm <sup>2</sup> |                   |               |      |        | 95% Conf. limits are 2.651994 to 41440.03 µl/cm <sup>2</sup> |             |              |             |        |              |

Appendix table 100 Regression equations,  $\chi^2$  values, LC<sub>50</sub> values and 95% confidence limits for Spinosad against 4 d nymphs and 2 d adults of *X. flavipes* after 24, 48 and 72 h of exposure.

| Concentration of Spinosad (µl/cm <sup>2</sup> )      | Life stage of <i>X. flavipes</i> | Exposure period (h) | Regression equation         | $\chi^2$ for heterogeneity | LC <sub>50</sub> (µl/cm <sup>2</sup> ) | 95% confidence limits |          |
|--|----------------------------------|---------------------|-----------------------------|----------------------------|--|-----------------------|----------|
|  |                                  |                     |                             |                            |  | Lower                 | Upper    |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863 | Nymphs                           | 24                  | Y = 2.990045 + 0.5126829 X  | 0.07527256                 | 832.6535                               | 2.922949              | 237196.1 |
|  |                                  | 48                  | Y = 3.55203 + 0.4612296 X   | 0.16153                    | 137.838                                | 3.740582              | 5079.244 |
|  |                                  | 72                  | Y = 3.748117 + 0.04364652 X | 0.09504318                 | 73.82966                               | 3.22157               | 1691.976 |
| Control<br>0.491<br>0.983<br>1.966<br>3.932<br>7.863 | Adults                           | 24                  | Y = 3.027043 + 0.5342836 X  | 0.04168511                 | 492.8509                               | 3.859698              | 62932.93 |
|  |                                  | 48                  | Y = 3.175748 + 0.514919 X   | 0.07186127                 | 348.9742                               | 4.223628              | 28833.73 |
|  |                                  | 72                  | Y = 3.464713 + 0.4360996 X  | 0.3258066                  | 331.5098                               | 2.651994              | 41440.03 |

Appendix table 101 Factorial ANOVA showing the effects of different concentrations of Spinosad on the nymphal mortality of *X. flavipes* after different exposure periods.

| Source                | SS      | DF | MS     | F      | P value |
|-----------------------|---------|----|--------|--------|---------|
| Concentration         | 144.095 | 5  | 28.819 | 13.562 | 0.000   |
| Exposure period       | 64.038  | 2  | 32.019 | 15.068 | 0.003   |
| REP                   | 4.704   | 2  | 2.352  | 1.107  | 0.449   |
| Concentration * REP   | 102.850 | 10 | 10.285 | 4.840  | 0.001   |
| Exposure period *     | 65.520  | 10 | 6.552  | 3.083  | 0.006   |
| Concentration         | 19.408  | 4  | 4.852  | 2.283  | 0.128   |
| Exposure period * REP | 44.625  | 21 | 2.125  |        |         |
| Error                 | 44.625  | 21 | 2.125  |        |         |
| Total                 | 445.240 | 54 |        |        |         |

Appendix table 102 Factorial ANOVA showing the effects of different concentrations of Spinosad on the adult mortality of *X. flavipes* after different exposure periods

| Source                | SS      | DF | MS     | F     | P value |
|-----------------------|---------|----|--------|-------|---------|
| Concentration         | 109.990 | 5  | 21.998 | 5.219 | 0.000   |
| Exposure period       | 61.592  | 2  | 30.796 | 7.306 | 0.000   |
| REP                   | 5.098   | 2  | 2.549  | 0.605 | 0.685   |
| Concentration * REP   | 65.870  | 10 | 6.587  | 1.563 | 0.108   |
| Exposure period *     | 102.150 | 10 | 10.215 | 2.423 | 0.243   |
| Concentration         | 35.664  | 4  | 8.916  | 2.115 | 0.953   |
| Exposure period * REP | 88.515  | 21 | 4.215  |       |         |
| Error                 | 88.515  | 21 | 4.215  |       |         |
| Total                 | 468.879 | 54 |        |       |         |

Appendix table 103 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *C. pusillus* after 3 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 180975  | 3  | 60325  | 65.929  | 0.281   |
| Concentration             | 180531  | 1  | 180531 | 197.303 | 0.003   |
| Rep                       | 780033  | 3  | 260011 | 284.165 | 0.019   |
| Treatment * Concentration | 30555   | 3  | 10185  | 11.131  | 0.974   |
| Treatment * Rep           | 13500   | 1  | 13500  | 14.754  | 0.962   |
| Concentration* Rep        | 170624  | 2  | 85312  | 93.237  | 0.002   |
| Error                     | 10065   | 11 | 915    |         |         |
| Total                     | 1366283 | 24 |        |         |         |

Appendix table 104 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *C. pusillus* after 6 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 174039  | 3  | 58013  | 53.966  | 0.145   |
| Concentration             | 245528  | 1  | 245528 | 228.398 | 0.001   |
| Rep                       | 982503  | 3  | 327501 | 304.652 | 0.262   |
| Treatment * Concentration | 32556   | 3  | 10852  | 10.095  | 0.731   |
| Treatment * Rep           | 14225   | 1  | 14225  | 13.233  | 0.274   |
| Concentration* Rep        | 168026  | 2  | 84013  | 78.152  | 0.004   |
| Error                     | 11825   | 11 | 1075   |         |         |
| Total                     | 1628702 | 24 |        |         |         |



Appendix table 105 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *C. pusillus* after 9 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 927675  | 3  | 309225 | 235.152 | 0.172   |
| Concentration             | 652220  | 1  | 652220 | 495.985 | 0.001   |
| Rep                       | 45756   | 3  | 15252  | 11.598  | 0.125   |
| Treatment * Concentration | 271500  | 3  | 90500  | 68.821  | 0.761   |
| Treatment * Rep           | 12740   | 1  | 12740  | 9.688   | 0.317   |
| Concentration* Rep        | 57220   | 2  | 28610  | 21.757  | 0.003   |
| Error                     | 14465   | 11 | 1315   |         |         |
| Total                     | 1981976 | 24 |        |         |         |

Appendix table 106 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *C. pusillus* after 12 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 123599  | 3  | 41193  | 24.965  | 0.016   |
| Concentration             | 215000  | 1  | 215000 | 130.303 | 0.000   |
| Rep                       | 1450710 | 3  | 483570 | 293.073 | 0.025   |
| Treatment * Concentration | 1664688 | 3  | 554896 | 336.301 | 0.720   |
| Treatment * Rep           | 143228  | 1  | 143228 | 86.805  | 0.199   |
| Concentration* Rep        | 525000  | 2  | 262500 | 159.091 | 0.387   |
| Error                     | 18150   | 11 | 1650   |         |         |
| Total                     | 4140355 | 24 |        |         |         |

Appendix table 107 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *R. dominica* after 3 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 165036  | 3  | 55012  | 66.681  | 0.084   |
| Concentration             | 172517  | 1  | 172517 | 209.112 | 0.002   |
| Rep                       | 840198  | 3  | 280066 | 339.474 | 0.000   |
| Treatment * Concentration | 24555   | 3  | 8185   | 9.921   | 0.925   |
| Treatment * Rep           | 12519   | 1  | 12519  | 15.175  | 0.754   |
| Concentration* Rep        | 166732  | 2  | 83366  | 101.050 | 0.013   |
| Error                     | 9075    | 11 | 825    |         |         |
| Total                     | 1390632 | 24 |        |         |         |

Appendix table 108 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *R. dominica* after 6 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 159084  | 3  | 53028  | 57.328  | 0.129   |
| Concentration             | 233548  | 1  | 233548 | 252.484 | 0.001   |
| Rep                       | 921006  | 3  | 307002 | 331.894 | 0.000   |
| Treatment * Concentration | 24786   | 3  | 8262   | 8.932   | 0.951   |
| Treatment * Rep           | 12230   | 1  | 12230  | 13.222  | 0.802   |
| Concentration* Rep        | 166124  | 2  | 83062  | 89.797  | 0.021   |
| Error                     | 10175   | 11 | 925    |         |         |
| Total                     | 1526953 | 24 |        |         |         |

Appendix table 109 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *R. dominica* after 9 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 898173  | 3  | 299391 | 244.401 | 0.000   |
| Concentration             | 642440  | 1  | 642440 | 524.441 | 0.000   |
| Rep                       | 52500   | 3  | 17500  | 14.286  | 0.922   |
| Treatment * Concentration | 268383  | 3  | 89461  | 73.029  | 0.005   |
| Treatment * Rep           | 10640   | 1  | 10640  | 8.686   | 0.801   |
| Concentration* Rep        | 53223   | 2  | 26611  | 21.223  | 0.330   |
| Error                     | 13475   | 11 | 1225   |         |         |
| Total                     | 1938834 | 24 |        |         |         |

Appendix table 110 Factorial ANOVA showing the effects of adult *X. flavipes* and different concentrations of Spinosad on the adult population of *R. dominica* after 12 months of exposure

| Source                    | SS      | DF | MS     | F       | P value |
|---------------------------|---------|----|--------|---------|---------|
| Treatment                 | 120279  | 3  | 40093  | 25.456  | 0.480   |
| Concentration             | 214213  | 1  | 214213 | 136.008 | 0.015   |
| Rep                       | 1390059 | 3  | 463353 | 294.192 | 0.001   |
| Treatment * Concentration | 1544700 | 3  | 514900 | 326.921 | 0.999   |
| Treatment * Rep           | 113449  | 1  | 113449 | 72.029  | 0.067   |
| Concentration* Rep        | 483096  | 2  | 241548 | 153.364 | 0.003   |
| Error                     | 17325   | 11 | 1575   |         |         |
| Total                     | 3883121 | 24 |        |         |         |